
Long Transfer Lines in the main tunnel

B.Jeanneret CERN / AB CLIC Workshop, Oct 2008

Outline


- Long transfer line, Main + Drive Beam
 - Optics + longitudinal layout
 - Transverse layout
 - Integration in the tunnel (space reservation ...)
- Issues related to turnaround
- Issues around the dump sections




Long Transfer Lines, CLIC08, BJ


Long DB transfer line

- Aim: transport the Drive Beam trains from the central area of the site towards the head of the Main Linac
- Deflect a train in each turnaround, one after the other






Magnets, DB & MB





- Quadrupole and dipole embedded
- Forces
 - Quad : GI = 0.14 Tm/m
 - Dipole : BI = 0.03 Tm
 - Same for DB & MB
 - > not demanding for electrical supply & cooling
- Length: as yet free
 - say I < 2 m
- MB : need solid static positionning (yet to make it a specification)
- Need free space for survey




Turnaround: A first look at integration issues


Turnaround as of today, F. Stulle/PSI (this w'shop)






Drive Beam dumps: A first look at integration issues







Summary

- Long transfer line
 - Compact and light combined magnet are considered
 - Conflict services / beam line / survey must be resolved
- DB Turnarounds
 - Optics exists, but need to adapt to C.E. constraints
- '5th Beam line' between TA and input decelerator
 - Now non-negligible fraction of the linac length
- DB Dump line
 - Short 10m section with two lines must be studied
 - Dump exit through main tunnel to be solved (water pipe on the way)
 - Dump proper still to be designed