



# CLIC Perspectives beyond 2010

- Resources & Schedule
- CLIC R&D from CDR to TDR
- CTF3+
- X-band RF testing
- The next CLIC facility



*CLIC'08 cocktail  
tonight, 7pm*



*Hans-H. Braun  
CLIC'08, 14.10.2008*

Most material collected from a brainstorming last Tuesday with


*Roberto Corsini, Jean-Pierre Delahaye, Günther Geschonke,*

*Hermann Schmickler, Daniel Schulte, Walter Wuensch and myself*

# Tentative long-term CLIC scenario

## Shortest, success oriented and technically limited schedule

Technology evaluation and Physics assessment based on LHC results for a possible decision on Linear Collider funding with staged construction starting with the lowest energy required by Physics



# CERN DG's talk to Staff

3 October '08

## Prospects for Scientific Activities over the Period 2012 - 2016



To be decided in 2010-2011 in light of first physics results from LHC, and designed and R&D results from the previous years. This programme could most probably comprise:

- An LHC luminosity increase requiring a new injector (SPL and PS).

The total cost of the investment over 6 years (2011-2016: 1000-1200 MCHF + a staff of 200-300 per year. Total budget: ~200-250 MCHF per year.

- Preparation of a Technical Design for the CLIC programme, for a possible construction decision in 2016 after the LHC upgrade (depending on the ILC future).  
Total CERN M + P contribution + ~250 MCHF + 1000-1200 FTE over 6 years.

- Enhanced infrastructure consolidation: 30 MCHF + 40 FTEs from 2011.

NB: Over the period 2012-2016. Effective participation of CERN in another large programme (ILC or a neutrino factory) will not be possible within the expected resources if positive decisions taken on LHC upgrade and CLIC Technical Design. This situation could totally change *if none of the above programmes is approved* or if a new, more ambitious level of activities and support is envisaged in the European framework.

DG's speech:

*Expected CERN contribution for CLIC TDR phase is  
250 MCHF + 1000-1200 FTE over 6 years*



What's your  
contribution ?

## What's required for TDR ?

*Readiness to receive funding for building CLIC, this implies*

- Technical design of all components which are critical for schedule
- Technical feasibility of all components
- Detailed site consideration
- Detailed construction Schedule
- Detailed material cost and manpower resource estimates and risk analysis



## What hardware work needs to be done for TDR

- ***Full technical design, prototypes and industrialization for all schedule critical items***
  - Nominal two beam modules with all features  
*this includes accelerating structures & PETS*
  - Drive beam accelerator units (modulator, klystron, RF network, accelerating structure)
- ***Full technical design and prototypes for all technical components in critical item list***  
*(see Jean-Pierre's & Hermann's talks)*

## *Future facilities should provide*

- Engineering test-bed for critical components and industrialization of mass produced components
- Make a convincing case for project readiness
- X-band RF testing capabilities




## Use of CTF3 beyond 2010

- Test of fully equipped CLIC module in TBTS
- Demonstration drive beam phase feed forward with  $\approx 20$  fs resolution
- Demonstration beam loading compensation with staggered phase-switch timing
- Demonstration of stable & robust long term operation
- TBL decelerator as multi port X band RF test bed

*Prerequisite: consolidation !*





CTF3 – Layout




## Specific experiments – consolidation – evolution paths

- Phase stability / stabilization / feedback
- Beam loading compensation experiment (control of RF pulse shape with staggered phase switch timing)
- Beam loading compensation full demonstration (need CALIFES upgrade to 1.2 A beam current )
- CTF3 “reasonable upgrade” + 3 klystrons (CALIFES, test + bunchlength deflectors + PHIN tests, girder 14)
- Photo-injector option full implementation (if PHIN results positive)
- More than 1 module in TBTS, with ~ nominal parameters (need PETS priming or recirculation)
- CTF3 TBL upgraded to X-band structure processing testing plant  
(1/2 nominal current, 2 PETS chained, DB dump in DL)
- X-band testing plant requires rep. rate upgrade to 50 Hz (shielding – control of beam losses!)



# DB pulses with nominal CLIC 240 ns duration in CTF3



# The CLIC Module in TBTS






Straightforward continuation of the CTF3 baseline program



**CTF3 cannot provide 100 A drive beam  
 ⇒ PETS recirculation or priming for nominal power**

PETS with recirculation schematic:



RF input power needed for 135 MW nominal output

DB current	P1
5 A	80 MW
10 A	40 MW
15 A	12 MW

## Klystron based X-band test stand facility

In addition to SLAC and KEK facilities at 11.4 GHz  
a 12 GHz teststand at CERN with one testing port will be operational from 2010


For full fledged structure development program several klystrons  
with fully equipped test stands required.

### Motivation:

- High-throughput, long-period running capability for structure development program
- Verification of nominal design structures, reproducibility
- Test bed for higher-performance lower cost variants on nominal design
- Experimental area for high-gradient studies: breakdown, pulsed surface heating and dark current
- Test bed for other structures like crab cavities

## Options for long term use of CTF3: *Two beam X-band linac*


*The ultimate, only building limited two beam accelerator in CTF3 !*






## Options for long term use of CTF3: *Two beam X-band linac*


*The ultimate, only building limited two beam accelerator in CTF3 !*



## *A next facility towards CLIC*



## Drive Beam Accelerator DBA



- Nominal CLIC DBA injector  
(thermionic or Photo injector, depending on results of PHIN tests)
- 2 nominal accelerator modules  
equipped with nominal 33 MW, 1 GHz, 50 Hz, 140 $\mu$ s pulse length klystrons  
***development of nominal drive beam klystrons & modulators required***
- 58 nominal accelerator modules with reduced pulse length klystrons (6  $\mu$ s)


Total length  $\approx$  200 m, nominal 4.2 A beam

final energy 0.48 GeV instead of 2.4 GeV for CLIC

6 $\mu$ s pulse length instead of 140 $\mu$ s, *for economy, sufficient to produce one nominal bunch train*

***all hardware nominal and re-usable for CLIC !***

## Delay Loop + Combiner Rings + Turnaround



- Nominal CLIC Delay Loop, 2 x current multiplication
- Nominal CLIC combiner ring 1 , 3 x current multiplication
- Nominal CLIC combiner ring 2 , 4 x current multiplication
- Nominal DB turnaround with bunch compressor


Total beamline length  $\approx 800$  m, *all components nominal and re-usable for CLIC*


Magnets operate at 1/5 of nominal strength.

# Two Beam Demonstrator

- 46 nominal CLIC modules  
(type 1, 6 accelerating structures, 1 main beam quadrupole, 3 power extraction structures and 2 drive beam quadrupoles per modules)
- Drivebeam corresponds to 1/10 of a nominal decelerator sector with deceleration to nominal final energy of  $T=0.24$  GeV
- Main beam gets a total acceleration of 6.3 GeV
- Califes type 0.2 GeV injector ,  
(but with nominal CLIC main beam current 1.2 A and 156 ns pulselength)
- total length  $\approx 120$  m

*all components nominal and re-usable for CLIC*





## Next facility towards CLIC

### Rational

- Creates drive beam train nominal for everything but energy (0.48GeV instead of 2.4 GeV)
- Demonstrates nominal DBA injector with all parameters
- Demonstrates nominal DBA module with klystron and modulator with all parameters
- Demonstrates two beam acceleration over significant distance with fully nominal modules
- Forces pre-series production of all mass produced components → Industrialization
- Well suited to create confidence in CLIC technology
- All hardware investment is re-usable for real CLIC

### Problems

- Combiner ring beam dynamics more difficult than in real CLIC (like in CTF3)
- Expensive (but re-usable)
- No obvious use of 6.5 GeV main beam but for testing (injector for proto damping ring, FEL ? )



*Where can we put it ?*

*Could fit in one of the big experiment halls at CERN*

*Problem: They are all in use*

*Can be put in final location*

*Problem: immediate cost and time delays*

## Tentative schedule for CLIC R&D 2010-2016

Year		2010	2011	2012	2013	2014	2015	2016
CTF3+	module test	design	build	commission				
	TBL+	finish TBL program	modify	X RF test	X RF test	X RF test	X RF test	X RF test
	phase feedforward	design	build	commission & run				
	general	consolidation						
Next facility towards CLIC	DBA Injector		Design	build	commission			
	Nominal DBA modules		Design	build		commission		
	Economy DBA modules				build		commission	
	combiner rings		Design		build		commission	
	TBA		Design		build		commission	
	civil engineering	Design	build					
Stand alone X-band sources	build & commission additional test ports			RF test program				
X-band structure development	continuation							
Design & beam dynamics studies	continuation							
LC Detector R&D	continuation							

## *More issues*

- Demonstration of injector parameters (polarised  $e^-$ , unpolarised and polarised  $e^+$ )
- Demonstration low emittance generation (ATF, SR sources, ...)
- Demonstration low emittance transport (SLC heritage, Linac driven FEL's, ...)
- Demonstration CLIC final focus parameters and stability (ATF2, ...)
- Integration of R&D program with other relevant facilities around the world (see Nobu's talk)
- Name for next facility
- ...

*You are welcome to discuss your ideas in the working groups !*