

---

# Structure Fabrication Status, SLAC

Juwen Wang

Stanford Linear Accelerator Center

CLIC08

October 2008

# What we are contributing

- Experiences in accelerator electrical design.
- Experiences in accelerator mechanical design and fabrication technologies.
- Fabrication of test structures designed by CLIC, SLAC and KEK.
- Microwave tuning and characterizations of test structures.
- High power tests for test structures at 11424 MHz test stations.

I will report:

- Work Done Since the Collaboration
- Work Ongoing
- Work for Other Future Structures

# Work Done Since the Collaboration

---

## 1. 2 x T18\_VG2.4\_DISC Structures #1, #2

One with SLAC flanges, which has been high power tested at NLCTA

Best performance so far

Backward feeding for more detailed studies for higher field breakdown

One with KEK flanges, which will be high power tested at KEK

## 2. HDX11 Cu Structure

SLAC Provided RF feed related components

Electrical polishing and reassembly

Microwave evaluation

High power tested in the NLCTA

## 3. T28\_vg2.9 (T26) Structure

Use T53VG3MC components and completion by the end of May, 2008

High power tested in the NLCTA since June 2008


Removal in the middle of October for inspection

# Schedule for 2 x T18\_VG2.4\_DISC Structures


---

- Completion of all parts by May13.
- Cell diffusion bonding and structure brazing assembly by May 23.
- Structure tuning and characterization by May 29.
- High temperature vacuum baking and final assembly on strongback by the middle of June.
- Best performance in high gradient test.


# Fabrication of T18\_vg2.4\_Disc Structures



Input/Output Couplers ready for brazing




Cooling Blocks under brazing




Accelerator Body under Diffusion Bonding

# Two T18\_VG2.4\_DISC Structures

Structure for SLAC Test




Structure for KEK Test




# T18\_VG2.4\_DISC with SLAC Flanges after Tuning

Field  
Amplitude



Cumulated  
Phase Change




# Tuning and Microwave Measurements for T18\_VG2.4\_DISC Structure with SLAC Flanges

---

- Target frequency and tuning: machining temperature for all parts was 20 degree C and design operation temperature was 30 degree C. Because the NLCTA cooling system is set 45 degree C, We set the bead tuning conditions and correct perturbations in order accordingly.
- Field distribution is ~ linearly ramping with  $E_{out} / E_{in} \sim 1.58$  for regular accelerating cells, which is consistent with design calculation. But, the input coupler has field overshoot.
- Structure matching:  $S_{11}=0.035$  with negligible reflection.
- Power loss in the structure:  $S_{12}=0.8$ ,  $P_{out}/P_{in}=0.64$ .
- Filling time: 36 ns.




# T18\_VG2.4\_DISC Structure with SLAC Flanges Installed at NLCTA for High Power Test




# T18\_VG2.4\_DISC with KEK Flanges after Tuning

Field  
Amplitude




Accumulated  
Phase Change




120°

# Design for T28\_VG2.9 (T26) Structure



Structure Type	L (cm)	Total Acc. Cells	$V_g$ % c	2a mm	T mm	r MΩ/m	$\tau$	$Q_{ave}$	$T_f$ ns
Even Cell Of T53VG3	26	30	3.30-1.62	7.8-6.3	1.66	92-107	0.19	6843	35.8


Accelerating Field with Input 50 MW  
T26 (Even or Odd Cells of T53VG3)




- Input and output to use existing universal coupler assembly.
- Check and small modification of input/output matching.
- Regular cups: 28 even number cups from T53VG3.
- Total 30 accelerating cells in the structure.

# T28\_vg2.9 (T26) Structures

Coupler Parts



Accelerator Cups




# Setting Up for Brazing of T28\_vg2.9 (T26) Structure




# T28\_vg2.9 (T26) Structure after Tuning

Field  
Amplitude




Accumulated  
Phase Change




120°

# HDX11 Cu Structure after Reassembly

Field  
Amplitude



Cumulated  
Phase Change



60°

# Microwave Measurements and Evaluation for HDX11-Cu Structure

---

After electrical polishing and reassembly, the microwave measurements were done in the room temperature, nitrogen condition:

- The field distributions based on the bead pulling studies were done for the frequency from 11405 MHz to 11430 MHz, the corresponding cumulated RF phase shift was ranging from 65 degrees to 28 degrees. the amplitude modulation gets worse when the phase shift reduces. When we do the high power tests, we have to consider the uniformity of the fields: the couple cells have higher field and every four cells have higher fields. As we know the trip rate could on order higher, when the gradient increase 10%.
- At this stage, it is hard to determine the exact impact to the frequency from the electrical polishing, because of lack of comparison with data before polishing.
- All S parameters of S11, S12, S22 were recorded. The filling time was measured to be ~ 4 ns.



# Work Ongoing

---

## 1. 2 x T18\_VG2.4\_DISC Structures #3 and #4

Surface finish check completed

All parts cleaning completed

#3, #4 body bonded

Coupler surface conditions under discussion

## 2. TD18\_VG2.4\_QUAD #3

SLAC provides RF feed related components

Four quadrant brazed with cooling tube flanges and vacuum baked

Final assembly and start of high power tested by end of November

## 3. T26 Structure Test in Station - 2

High power testing at the Station-II of the NLCTA;

Higher breakdown rate at 150 ns, 95 MV/m.

## 4. T18 Backward Test in Station -1

## 5. Four Short (10-cell) Test Structures with Various Iris and Disc Thickness for High Gradient Studies.

2 x C10\_VG 0.7 #1, #2

2 x C10\_VG 1.35 #1, #2


# TD18\_VG2.4\_DISK #3 and #4

---


- Surface finish check completed.
- Both #3, #4 accelerator bodies bonded.
- Couplers brazing on hold due to the finding of some machining problems for coupler parts.
- Discussion with KEK for two option:
  - Re-machining of coupler parts in Japan;
  - Fixing the parts at SLAC.

# ZYGO Surface Flatness Measurement for a Typical Cup of T18\_VG2.4\_DISC #3 and #4


Both sides show less than 1 micron concaved




16D-A



14D-C



17D-A



17D-C


# ZYGO Data for T18\_VG2.4\_DISK #3

Cell #	Surface Variation A side	Concave or Convex?	Surface Variation C side (cavity side)	Concave or Convex?
Input	0.39	Concave	0.51	Concave
0	1.72	Concave	0.68	Concave
1	2.01	Concave	0.6	Concave
2	1.34	Concave	0.53	Concave
3	1.35	Concave	0.34	Concave
4	1.2	Concave	0.53	Concave
5	1.34	Concave	0.35	Concave
6	1.38	Concave	0.64	Concave
7	1.21	Concave	0.64	Concave
8	1.41	Concave	0.74	Concave
9	1.57	Concave	1.03	Concave
10	1.24	Concave	1.02	Concave
11	1.5	Concave	1.01	Concave
12	1.27	Concave	1.21	Concave
13	1.36	Concave	1.03	Concave
14	1.39	Concave	0.8	Concave
15	1.4	Concave	0.98	Concave
16	1.18	Concave	1.29	Concave
17	1.09	Concave	0.95	Concave
18	1.31	Concave	0.95	Concave
19	1.42	Concave	0.34	Concave
20	1.11	Concave	1.27	Concave
Output	0.36	Concave	0.33	Concave
Avg Variation - Microns	1.28	Concave	0.77	Concave
Max Variation -- Microns	2.01	Concave	1.29	Concave
Min Variation -- Microns	0.36	Concave	0.33	Concave


# ZYGO Data for T18\_VG2.4\_DISK #4

Cell #	Surface Variation A side	Concave or Convex?	Surface Variation C side (cavity side)	Concave or Convex?
Input	0.57	Concave	0.49	Concave
0	0.86	Concave	0.34	Concave
1	1.12	Concave	0.51	Concave
2	1.06	Concave	0.62	Concave
3	1.27	Concave	0.49	Concave
4	1.13	Concave	0.47	Concave
5	1.24	Concave	0.46	Concave
6	1.37	Concave	0.62	Concave
7	1.27	Concave	0.66	Concave
8	1.50	Concave	0.56	Concave
9	1.07	Concave	1.35	Concave
10	1.11	Concave	1.11	Concave
11	1.06	Concave	1.29	Concave
12	1.02	Concave	1.06	Concave
13	1.16	Concave	1.13	Concave
14	1.00	Concave	0.85	Concave
15	1.02	Concave	1.06	Concave
16	0.92	Concave	1.25	Concave
17	1.00	Concave	1.27	Concave
18	0.93	Concave	0.88	Concave
19	0.86	Concave	0.72	Concave
20	0.94	Concave	0.76	Concave
Output	0.63	Concave	0.58	Concave
Avg Variation - Microns	1.05	Concave	0.81	Concave
Max Variation -- Microns	1.50	Concave	1.35	Concave
Min Variation -- Microns	0.57	Concave	0.34	Concave

# Alignment Check for T18\_vg2.4\_DISK #4 Diffusion Bonding




# Tool Marks of Milling on the Flat Surface




Subassembly for Test Cells

# Measurement Traces by Taylor Hobson Profile meter






# Measurement of Tool Marks by Taylor Hobson Profile meter



**Current Point**  
 X 0.9256 in  
 Z 191.4925  $\mu$ in  
 Modified Profile

**Reference Point**  
 X -0.0001 in  
 Z 0.0000  $\mu$ in  
 PV 253.3750  $\mu$ in

**Difference**  
 $\Delta$ X 0.9257 in  
 $\Delta$ Z 191.4925  $\mu$ in  
 Pitch 0.9257 in




		Slope	-0.401	°	Pz(JIS)	210.945	$\mu$ in		
Pa	31.635	$\mu$ in	Pq	48.413	$\mu$ in				
Psk	1.9768		Pku	6.7372					
Pp	191.492	$\mu$ in	Pv	61.882	$\mu$ in				

# Measurement of Peaks of Tool Marks by Taylor Hobson Profile meter


*PEAK OF  
MTL. THAT  
didn't  
clean-up*

Taylor Hobson







	Slope	-0.403	°	Pz(JIS)	159.111	$\mu$ in							
Pa	77.945	$\mu$ in	Pq	191.685	$\mu$ in								
Psk	3.1323		Pku	10.4351									
Pp	716.942	$\mu$ in	Pv	15.863	$\mu$ in								
PLo	0.148093	in	Pt	732.804	$\mu$ in	Pmr(C)	62.82	% Height (mean)	0.00	$\mu$ in			
			Pdq	1.67	°	PHSC	0	peaks Height (mean)	0.00	$\mu$ in			
Pda	0.85	°	Pz	732.804	$\mu$ in	Pdc	732.804	$\mu$ in	mr1%	0.00	% mr2%	100.00	%
PS	0.000000	in	PSm	0.000000	in	Pmr	50.00	% offset	0.00	$\mu$ in	mr%	50.00	%
Pln	0.148031	in	Pc	0.000	$\mu$ in	PVo	0.0403	vol offset	0.00	$\mu$ in	mr%	50.00	%
						PPc	67.6	pks/in	Height (mean)	0.00	$\mu$ in		

# Tool Damages on Matching Bumps





# Mode Converter Coupler



$$|E^s|_{\max} = \sim 34 \text{ MV/m @ 48 MW}$$

$$|H^s|_{\max} = \sim 98.4 \text{ kA/m @ 48 MW (on inner edge of waveguide iris)}$$

$\Rightarrow$  pulsed heating  $\sim 3^\circ$


Input Power of only 55.5/2 MW is needed for 100 MV/m for T18 structure

# Plan for 1<sup>st</sup> Four C10 Structures

---


- Four structures: 2 x C10\_VG\_1.35 #1, #2 and 2 x C10\_VG\_0.7 #1, #2.
- CERN has completed the electrical design.
- SLAC makes the mechanical design, fabrication and high power tests.
- Draft of the addendum 3 is completed.
- Engineering design is completed.
- Test cells from an outside vendor (Robertson) have been examined by SLAC and fabrication of all cells will be completed in by October, 2008.
- The completion of the structures is scheduled to be in November, 2008.

# Schematic View for C10 Structures - II




Subassembly for Test Cells

# Schematic View for C10 Structures - I



Structure Assembly



TM01 Mode Launcher




# Work Plan for TD 18\_VG2.4\_QUAD #3


---

- Cooling tube fitting flanges brazed at a hydrogen furnace with 25/75 Au/Cu alloy
- Four quadrant assemblies vacuum baked at 650°C
- Test assemblies completed
- Final assembly, microwave measurements and leak check will be completed by October 25<sup>th</sup>.
- Installation at the NLCTA in the last week of October.


# T8\_vg2.4\_QUAD Structure Brazing



# Temperature Profile for T18\_vg2.4\_QUAD Structure Brazing



# T18\_vg2.4\_QUAD Structure #3 Test Assembly



# Work for Other Future Structures

2008

1. 2 x C10\_VG\_1.35 #1, #2 and 2 x C10\_VG\_0.7 #1, #2  
Assembly completion and High power testing
2. CERN T24\_VG1.8\_DISK #1  
High power testing
3. CERN T18\_VG2.4\_DISC #5  
High power testing
4. CERN TD18\_VG2.4\_DISK #1  
High Power Testing

2009

1. TD18\_VG2.4\_DISK #2, #3  
Assembly, Tuning and High power testing
2. C10 Structures 2xVG2.25 and 2xVG3.3  
Fabrication, Assembly, tuning and High power testing
3. KEK CD10 2xVG1.35#1, #2  
Assembly, tuning and High power testing
4. CERN CD10 2xVG1.35 #3  
Assembly and High power testing
5. TD24\_VG1.8\_DISK #1  
High power testing
6. T-500GeV  
High power testing