

LHC machine integration experience

PicoSEC-MCNet System Integration Training

26th May 2014 - Julie Coupard




Contents

- Introduction to the LHC machine
- Installation 1995-2008
- First long shutdown 2013-2014
- Summary

Introduction to the LHC machine

CERN's Accelerator Complex



LHC Large Hadron Collider SPS Super Proton Synchrotron PS Proton Synchrotron

AD Antiproton Decelerator CTF3 Clic Test Facility AWAKE Advanced WAKEfield Experiment ISOLDE Isotope Separator OnLine Dvice


LEIR Low Energy Ion Ring LINAC LINear ACcelerator n-ToF Neutrons Time Of Flight HiRadMat High-Radiation to Materials

© CERN 2013





The LHC machine

- LEP tunnel




The LHC machine

- 27km of circumference composed of 8 sectors of $\sim 3,3\text{km}$
 - 8 arcs of 2,4km
 - 8 long straight section of $2 \times 440\text{m}$
- From 50 to 175m underground



Cost structure of the LHC main ring


LHC project: ~ 5 BCHF (2008)
 Personnel: ~ 1.2 BCHF
 Materials: ~ 3.8 BCHF



Installation

- The first idea of the LHC started in the **80s**, during the LEP construction.
- **The Project has been fully approved in December 1994 by the CERN Council.**
- Between 1994 and 1998
 - Tests of prototype
 - Publication of the Technical Design Review
 - Approval of the Experiments
 - Financial contribution of the member States
- **Construction and Installation from 1998 to 2008**

Challenge to carry out a MegaProject



Challenge to carry out a MegaProject

Mega project factors

- **Time Horizon**
 - Multi-years
 - Multi-phases
- **Chain of Command**
 - Multi-layers organization
 - Matrix Structure
- **High-degree of Specialization**
 - Subject Matter Expertise
 - Cutting-Edge Technology
- **Dispersed Teams**
 - Virtual teams in multiple locations
 - Outsourcing to other countries




Impact on the Project

- **Risks** had to be properly analyzed
- **Responsibilities** had to be clear
- **Coordination** was crucial
- As well as clear and transparent **communication**

The aspects of the Mega-project

- Project management plan
- Organization
 - Scheduling and coordination
 - Integration studies
 - Configuration management
- Risks assessment
- Issues example



Project management




- **Project Assurance Quality (PAQ)** put in place in 1995 based on PMBoK

- Project Integration Management
- Project Scope Management
- Project Time Management
- Project Cost Management
- Project Quality Management
- Project Human Resource Management
- Project Communications Management
- Project Risk Management
- Project Procurement Management
- Project Stakeholders Management



with large-scale projects, one PM plan shall not impose a PM methodology.

Project management



- Some issues in the PM plan:

No link between the cost control system (cost packages)
and the scheduling system (work packages)


- Technical Coordinator "*the project is behind schedule*"
- Project Administrator "*the project is under-running*"

⚠ Need an appropriate Project control system

Project management



- Project control 2.0
 - Multi-levels planning and scheduling
 - Earned Value Management-based
 - Interfaced to accounting system: Actual Costs
 - Payment milestones of result-oriented contracts refer to effective deliveries
Finish dates of contract activities are always known!
 - Interfaced to contract management system
 - Interfaced to human resource management system
 - In-kind contributions
 - Collaborative and web-based
 - Reporting
 - Transparency of the physical progress reporting
A "10 magnets out of 20" physical progress statement is more informative than a "50% complete" statement!



Organization

The project is defined in a **Work Breakdown Structure (WBS)**

- Organize the people with their roles and responsibilities
- Organize the requirements and the procurements

- **Work Unit (WU):**

A Work Unit is synonym with activity, an element of work performed during the course of a project. A Work Unit consists of one or several resource assignments that have a cost estimate or a manpower estimate and one or several deliverables.

- **Deliverables (DE):**


Any measurable, tangible, verifiable outcome, result or item that must be produced to complete a project or part of a project.

Organization



Pillars of coordination

Scheduling and coordination





Scheduling and coordination



- Multi-level planning



- ⚠ Have a coherent information up-to-date
- ⚠ Be able by experience to identify the over/under-estimation
- ⚠ Contingencies have to be taken into account at one level






Integration studies

- The integration office designs the first draft and determine the volumes for the design offices = pre-studies





Integration studies



- **The design offices provide their 3D models to integration office**

- Civil engineering and metallic infrastructure
- General services and power devices
- Machine equipment



- **The integration office creates the puzzle**



- Identification of the interferences with proposal of solution
- Space reservation




- **Once the integration is approved, the integration team follows-up the installation**

- Identification of non-conformities of installation
- Scans
- Update of the 3D models


Integration studies





Integration studies

- Major difficulties



- During integration studies




Volume of transport





Volume for the survey

Configuration management



- Provides a **clear and coherent** picture of the status of a project or machine at a **given point in time**.
- In order to achieve this, we use three important tools
 - Changes to the machines and transfer lines are documented, circulated and approved in the **Hardware Baseline** (also known as a Product Breakdown Structure)
 - We register the layouts of the accelerators and all changes to them within the **Layout Database** that has to remain up-to-date.
 - Sequence of functional positions = space management
 - Integration and Installation Drawings match the recorded layout to ensure that envelopes of reserved space still match the physical equipment dimensions
 - Naming is critical throughout the lifecycle of the machines/projects. To store and manage naming, we use the [Naming Portal](#)
- Keyword is **coherence** between the tools.



Configuration management



• Hardware Baseline

- ...is an EDMS (Electronic Document Management System) based tool.
- The hardware baseline contains all the information needed to re-build the machine, including:
 - Engineering Specifications, Drawing Folders, ECR, Procurement Documents
 - LHC Baseline was the first to be issued
 - SPS and PS Complex Hardware Baselines are in progress
- Logical structure of nodes, based on hardware types and functions
- Documentation can be linked to multiple locations


Configuration management



• Layout Database

- Stores the sequence (layout) of accelerator and transfer line components.
- Equipment types and details
- Functional positions for mechanical and electrical layouts
- Asset names – functional position is exported to MTF database and associated to an asset. Layout just shows the result.
- Expert name – optional, alternative functional name

Configuration management



- The link with the manufacturing tool
 - The *MTF* is an integral tool of the CERN *EDMS* that allows a detailed follow-up of the equipment during the manufacturing and test processes. Predefined workflows with tasks and technical measurements can be logged and followed-up in a fully configurable manner for each type of equipment. The Non-Conformity management is another important module for the manufacturing follow-up, which allows formalized procedures for solving problems discovered during production.
- For the LHC project, over 600.000 components were individually followed up with *MTF* during the manufacturing and test phases.

Home | Help | EDMS site | News | Login
User: PEREA

Search: Equipment | Location | Slot | System

Slot Folder: Installation Jobs

Slot Identifier: ADTMH.B5L4.B1
Other Identifier: None
Description: RF Transverse Damper

Main | Slot data | Installation & Commissioning | Operation | Documents | History


Actions: Create Job

Job Id	IR/E	Status	Res.	Description	Show Last Repeated
14507922		Pending		10-Test Control Cabling	Started Ended INC
14507923		Pending		12-Test RF Cabling	
14507924		Pending		14-Test Ug1 and Ug2 Power Supplies	
14507925		Pending		16-Test Ua Power Supplies	
14507926		Pending		18-Test Controls and Interlocks	
14507927		Pending		20-Test PIN/Signal conditioner/HV divider	
14507928		Pending		22-Test Water Cooling System 4 Amplifiers	
14507929		Pending		24-Test with 4 amplifiers with Low Power	

Risks assessment

By definition, **risks can occur** and the prevention is less control for new machine like LHC which stays a **prototype** with unique systems.

- How we prevent risks
 - Anticipation, follow-up, monitoring
 - Strict quality control
 - Long term analysis schedule
 - Flexibility (plan A, plan B)
- When a risk occurs
 - Dedicated task force: correct expertise and appropriate experts !!
 - Being ready for the unexpected and determining your response to it



Issues example

The study and installation of the cryogenics distribution line (QRL)

- The situation:

1 unique firm for the study and installation of around 25 km of QRL

- The issue:

Design of the supports of the QRL underestimated, the installation of the QRL could not be done properly

- Plan B: CERN Task Force

Decided to repair the delivered equipment

Change in the Master Plan

- Impacts:

Delay in the installation of the magnets → storage

Logistic of transport of the magnets



99

00

01

02

03

04

05

06

07

08

Issues example

The installation of the cryomagnets

- The situation:

The installation has to be carried-out in parallel of works in the tunnel

- The issue:

Co-activities in underground → difficulties with the logistic of transport (only one pits to bring the magnets in underground)

Delay on availability on surface → 1 hour = 1 day

- Plan B:

Transports of the magnets during the night

Coordination with the co-activity to allow the transports

- Impacts:

Long time window dedicated for the installation

Co-activity on several km of tunnel



99

00

01

02

03

04

05

06

07

08

Issues example

The installation of the collimators

- The situation:

The handling volume during installation was not taking into account in time

- The issue:

Interference between the cooling system and the handling of the collimators

- Plan B:


Modification of the cooling system and cable trays

- Impacts:

Storage of the collimators

Additional work for the cooling team

Updating of the drawing and 3D models



99

00

01

02

03

04

05

06

07

08

Issues example

Deformation of the plug-in modules contacts during warm-up

- The situation:

PIM contacts did not slide during the magnet warm-up and instead got buckled into the beam pipe aperture

- The issue:




The deformation of the plug-in modules would become an obstruction for the circulating beams

- Plan B: working group

Send inside the beam pipe a ball equipped with a radio-frequency transmitter in order to identify the defective PIMs to repair.

- Impacts:

New task to integer in the schedule after warm-up of a sector



99

00

01

02

03

04

05


06

07


08

Success – 10th September 2008

First complete turn of the beam



"It's a fantastic moment," said LHC project leader Lyn Evans, ***"we can now look forward to a new era of understanding about the origins and evolution of the universe."***



Issues example

Incident 19th September 2008

- The situation:

Last electrical tests at higher Energy (7TeV)

- The issue:

Collateral damage due to pressure forces

- Magnets displacement
- Support displacement and rupture of ground anchors

- Plan B: CERN Task Force

Dismantle, repair and re-install the whole damaged sector and repeat the hardware commissioning with powering test with limit at 3.5 TeV beam energy.

- Impacts:

1 year to repair, consolidate and tests again the machine.

New safety measures put in place.


Studies of the issue for next consolidation.



Success – 30th March 2010

7 TeV collision events seen by the LHC's four major experiments

(clockwise from top-left: ALICE, ATLAS, CMS, LHCb)



Success – 4th July 2012













The ATLAS and CMS experiments at CERN's Large Hadron Collider announced they had each observed a new particle in the mass region around 126 GeV.



First Long Shutdown

- New challenges

CERN Principaux travaux de consolidation pour le LHC en 2013-2014

Ouvrir et refermer définitivement 1 695 interconnexions	Refaire entièrement 1 500 de ces interconnexions	Consolider les 10 170 interconnexions de 13 kA: installer 27 000 dérivations	Installer 5 000 systèmes d'isolation électrique consolidés	Réaliser 300 000 mesures de la résistance électrique	Réaliser 10 170 soudures orbitales de lignes en acier inoxydable
					
					
Réaliser 18 000 tests d'assurance qualité électrique	Réaliser 10 170 tests d'étanchéité	Remplacer 4 quadripôles	Remplacer 15 dipôles	Installer 612 nouvelles soupapes, ce qui porte leur nombre total à 1344	Consolider les circuits de 13 kA dans les 16 boîtiers principaux d'alimentation électrique

Lessons learnt

- Improvements
 - Intervention Management Planning & Activity Coordination Tool (**IMPACT**)
 - Engineering Change Request template (**ECR**)
 - Dashboards

IMPACT European Laboratory for Particle Physics

Activity: AR 46279: changement gaine WCC PT2droit - DFBXD

Status: In progress

Responsible: [Name]

Facility: LHC Machine
System: E - Electricity

Priority: Shutdown
Type: Consolidation

When
Proposed Date: [Date] Duration: 30 Days
Earliest Start: [Date] Latest End: [Date]
Working Time: Anytime: Mon - Sun, 00:00 - 24:00

Scheduled: 05-May-2014 to 03-Jun-2014
Access: 04-May-2014 to 04-Jun-2014
Intervention Period: LS1 - LHC (24-Nov-2012 to 01-Sep-2014)
Granted Working Time: Anytime: Mon - Sun, 00:00 - 24:00



Where
Locations: UA27, RA27, RB26, UJ26
Access Points: PM25, PM25, UJ27, PM25, UJ27, PM25, UJ27

How
Modus Operandi:
Material Resources:
Waste:
Constraint:
Linked Documents:

Hazards
Activity Hazards:
• Working at height
• Comment: echafaudage
• Compensatory Measure:
• Activity generating electrical risks
• Comment: consignation convertisseur de puissance
• Compensatory Measure:

Safety Procedures
• VIC (1090)

Contact Phone: 75101 Max Participants: 15



CERN CH-1211 Geneva 23 Switzerland

EDMS NO. 1308162 REV. 1.0 VALIDITY RELEASED

REFERENCE LHC-XRP-EC-0009

Date: 2013-10-14

ENGINEERING CHANGE REQUEST
Moving ATLAS/ALFA RP station


BRIEF DESCRIPTION OF THE PROPOSED CHANGE(S):
To gain in angular resolution and therefore in t-resolution, the proposal is to move the ATLAS/ALFA B stations (B7L1 and B7R1) by 4m away from the IP. We would take advantage from the fact that the stations need anyway to go to surface for upgrade activities (see ECR LHC-XRP-EC-0008) and from the fact that the DQR's (the stations are located in between two DQR's) will undergo preventive maintenance. The impact in terms of additional work is described in the following.

Lessons to come

- Remaining difficulties

- Simplified 3D model and reality

- Cabling
- Mechanical pieces
- Cooling system



- Communication between meeting of decisions and worker on site

- Information online
- Screen on site giving the important news




Lessons learnt

- New Projects at CERN after LHC

 LINAC4 Project 





 LIU - LHC Injectors Upgrade Project

 High Luminosity LHC


HL-LHC: High Luminosity Large Hadron Collider




Current situation

<http://lhcdashboard.web.cern.ch/lhcdashboard/ls1/>




Master schedule in time with forecast

What's next ?



Summary



Thanks to my colleagues for their contributions:
K. Foraz, Y. Muttoni, S. Chemli, T. Birtwistle, P. Bonnal



THANK YOU FOR YOUR ATTENTION