

Status of DFA + link to Q6 in point 7

Délio Ramos, WP6 meeting, 5.3.2014


Outline

- Naming
- Visit to point 7
- Base concept and approach
- Time scale

Naming Proposal

DFHA [A-H] (or [A-P]?)
 DFHM idem
 DFHX [A-D]

DSH A [A-F]
 B [A-F]
 C [A-B]
 D [A-D]
 E [A-F]
 F [A-D]
 G [A-B]
 H [A-F]





In point 7 the DFM function may be integrated into the DFA

DFA [A-P]
 DFM [A-P]
 DFX [A-H]

Point 7 Left

Site visit organised by J-P Corso,
26.11.2013


DFBA



Point 7 Left


Site visit organised by J-P Corso,
26.11.2013

Resistors



DFBM

Shielding




Short link
DFBM-Q6



Current Base concept (all sites)

Helium at max. 17 K






- The 17 K limit for the MgB_2 link allows only the 5 K, 3.5 bar helium from line C as coolant.
- The link will be cooled by helium gas created by evaporating the liquid helium in the spice box.
- Thermal shield solution not shown.
- Either with 20 K, or with 70 K gas.

Minimum change approach



- Minimise work in the tunnel
 - Assemble and test before LS2 starts
 - Aim for installation within short time slot (radiation cooldown time may be long..)
- Remove HCM only and replace with DFA
 - Keep 2x13 kA leads in current position
 - Keep cryo jumper in current position
 - Vertical link connection
 - Keep existing support beam and shuffling module
- Remove DFBMH and link Q6 to DFA
 - Possibly with no changes to Q6 QQS and jumper
 - Link routed above QRL

Point 7 Left

ST0053741_13



DFBA.7L7 CDD number - LHCFBAM0119





LHCDFBM_0003

LHCDFBA_0010




Point 7 Right



ST0296494_07



DFBMH.6L7



DFBAN.7R7 CDD number - LHCDFBAN0315




LHCDFBA_0010

LHCDFBM_0003



DFA to Q6 in NbTi
Supercritical He because of
changes in level




52x600 A

4x600 A

Keep jumper and 13 kA
leads in same location
to avoid changes in
power cables and cryo
distribution


48x600 A




Splice




Matching section IR7 left



DFBAM 7 Left



DFBMH




Q6


For Q6 link, 13 kA and MgB2

To shield links

Link shield 20 K inlet with existing jumpers and valves



Link shield 70 K inlet



Typical time scale

- From an established concept to ready for tendering documentation: 1 year (usually more...)
- Tendering: 6 months
- Fabrication: 1 year
- Ready for installation: + 6 months (possibly more if cold tested)
- i.e. 3 years minimum
- We should start now:
 - Agree on the cooling scheme
 - Validate integration in the tunnel (links and DFA)
 - Determine piping dimensions and extent of modifications to QRL and Q6
 - Start the DFA and Q6 link mechanical design

