



www.cern.ch

Machine Protection backbone: Upgrades


Session 5: Machine Protection and availability

I. Romera Ramírez


Acknowledgments: R.Denz, S. Gabourin, J.Wenninger, M.Zerlauth and many other colleagues

5th Evian Workshop – 2-4 June 2014

LHC Machine Protection System




Magnet Protection




Electrical circuit definitions

- Definition of **essential and auxiliary circuits** embedded on the PIC
 - “**Essential circuits**” => Beam dump under any condition (including safe beams)
 - “**Maskable circuits**” => Beam dump if unsafe beams - can be masked as f(SBF)
 - “**None**” => No impact on beam
- No difference** between Essential and Maskable definition **with unsafe beams!**
- RQSX3 included in the list of maskable circuits** during Run1 after trip provoking fast orbit changes and beam losses in SR7 [1]




Electrical circuit definition – Run2 proposal

- During Run1:
 - RB, RQD, RQF, RQX, RD1-4, RQ4-RQ10 as **ESSENTIAL**
 - RCS, RQT%, RSD%, RSF%, RCBXH/V and RCB% as **MASKABLE**
 - RCD, RCO, ROD, ROF, RQS, RSS **no impact**
- Run 2:
 - ROD/ROF**: Trips on such circuits provoked several dumps due to EMC on neighbouring circuits (typically RSF and RSD) => **MASKABLE**
 - RCBCHS5.L8B1**: Circuit repaired and back to operation => **MASKABLE**
 - Highly resistive circuit (around 22 mΩ) on the cold side at 4.5K. It was replaced by a nc circuit during Run1.
 - RQS**: To correct beam coupling, these circuits have similar function as RQSX3, which were included in the PIC configuration (no evidence of beam dumps during Run1...) => **MASKABLE**
- New configuration to be applied to the reference DB and deployed in the PIC**
- Commissioning required once Powering Tests completed following the procedure [2]**
- Consistent circuit configuration will be tested with automated sequence in ACCTESTING**



How to ensure access while powering

- **New interlock system** between access and powering systems [3]
- **Improves reliability** in the transmission of the access status to the SIS
- **Prevent access** while magnets are powered and current levels **above phase I limit**
- System to be commissioned during the **sector access tests starting on 6th June**
- **“Access restriction in LHC and SPS during LHC powering phase II” released!**



Powering phase II interlocking

- EDMS document updated (LS1 changes etc).
 - Approval in progress.
- Logic will be implemented in the LASS-SIS-PIC interlock.
 - New system will be deployed in the coming weeks.

Tentative test dates:

- | | | |
|---------------------|-------------------|-------------------------------|
| □ Friday 6 June | LHC8-LHC1-TI8 | powering of sector 8-1 |
| □ Friday 13 June | LHC6-LHC7-LHC8 | powering of sectors 6-7 & 7-8 |
| □ Friday 20/27 June | LHC1/1.8-LHC2-TI2 | powering of sector 1-2 |
| □ Friday 4 July | LHC2-LHC3-LHC4 | powering of sectors 2-3 & 3-4 |
| □ Friday 25 July | LHC4-LHC5-LHC6 | powering of sectors 4-5 & 5-6 |

Contains the complete list of doors that are interlocked with powering



LHC

1010637 3.0 IN WORK
LHC-OP-OSP-0016




OPERATIONAL SAFETY PROCEDURE
Access Restriction in LHC and SPS during LHC powering PHASE II

4/16/14

CSAP - LMC

Quench Protection



Dependability improvements

Machine Protection Workshop Anecy'13 (B.Todd)

QPS Failure Mode	#	Total [hours]	Average [hours]
Radiation Induced Malfunction	39	35	0.9
Internal Communications Lost	25	15.5	0.6
Spurious Signal	23	23	1.0
Power Converter Trigger	13	13	1.0
WorldFIP Fault	12	17	1.4
DFB / Current Lead Fault	9	18	2.0
Mains Perturbation	8	9	1.1
600A Energy Extraction Fault	7	13	1.9
13kA Energy Extraction Fault	6	11	1.8
Electro-Magnetic Interference	2	3	1.5
CMW	1	0.5	0.5
13kA Power Supply Fault	1	2.5	2.5
Others	9	6	0.7
Combined	155	166.5	1.1

QPS/EE provoked dumps in 2012

External
Random Hardware
Radiation Hardware
Exploitation

- **Equipment relocation** previously installed in in UJ14, UJ16 and UJ56 for inner triplet protection
- **Deployment of radiation tolerant hardware** for the protection of IPD, IPQ and 600A circuits in RR13, 17, 53, 57, 73, 77 where relocation was not possible during LS1
- Radiation tests indicates that new board will be about a **factor 100 less sensitive** to SEU
- **Instrumentation cabling for IPQs** optimised with respect to EMC => Less trips expected during storms and power outages
- **Enhanced power-cycle options** for DAQ systems including automatic restart of field-bus couplers (minimize access)

Main circuits protection



- Upgrade of the **main dipole protection racks** (1232 yellow racks)
- Enhanced **quench heater supervision**
 - Upgrade reduce the risk of **damage to the quench heater circuits**
 - New system records both **discharge voltage and current** at 192kHz/16bits
- New AC-DC power supplies fully adapted to **redundant UPS powering**
 - Ensures adequate magnet protection **if losing a UPS distribution** power path
- Installation of **earth voltage feelers** for main circuits
 - Monitor **electrical insulation strength** during fast discharges
 - Identification of the fault position on the half-cell level
- **nQPS upgrades**
 - **Symmetric quench detection firmware** adapted to higher operating currents
 - **Splice protection board firmware** to provide better SEU immunity
- **General revision of the EE [4]**
 - Main dipole dump resistors reconfigured (discharge time **increased to 102 secs**)
 - Main quad dump resistors reconfigured (discharge time **increased to 32 secs**)
 - Installation of snubber capacitors for voltage transient suppression during commutation

600A detection thresholds and EE changes

- Detection thresholds

- QPS thresholds **on both busbar and magnets** for all 600A circuits reviewed
- New thresholds **aimed to reduce the sensitivity while maintaining protection**
- Detection involves a voltage threshold (**U_{th}**) and evaluation time (**dt**)
- **Max. hotspot temperatures** set to 300K for busbars and 200K for magnets
- For all 600A circuits powered via the N-line, **the busbar detection determines the maximum allowable threshold parameters (U_{th}, dt)**

- Energy extraction [5]

- **Several 600A exhibit coupling-current induced quenches** (quench back) during FPA
- Study of **quench back current**, impact on **reduced R_{EE}** on the limits for QPS detection parameters, **temperature increase in the modified EE resistor** during FPA and the increase in **coil peak temperature** after a magnet quench due to a slower current decay
- **0.4Ω EE resistors** for all eight RQTL9 circuits




Operational software tools

- QPS parameters and **settings integrated in LSA DB** (consistency HW checks)
- Changes in the **PM data retrieval** (redundant boards visible, higher resolution and sampling rate which will also imply longer data collection, despite having doubled the field-bus segments)
- **Pre-operational checks** for the QPS device configuration and integrity of signals to be sure that the detection systems are up and running
- **New power cycle tools** only active under safe operational conditions (no beam, power converter in idle mode...)

The screenshot shows the 'QPS Swiss tool - dev' interface. On the left, there are filters for 'Text Filter', 'Ops Crate Type', 'LOCATION', and 'CIRCUIT TYPE'. The main area displays a list of components across four banks (bank 1 to bank 4). On the right, there is a 'Parameters' table for 'DAQHAG_14_1_50'.


Name	Units	Format	Offset	Scale	Signif...
MBL...	V	000.0	204...	0.10	16
MBL...	V	000.0	204...	0.10	16
MBL...	V	0.000	-0.25	0.00	16
MBL...	V	0.000	1.00	1.00	16
MBL...	V	0.000	1.00	1.00	16
MBL...	V	0.000	0.00	0.02	16
MBL...	V	0000.0	0.00	0.02	16
MBL...	V	0000.0	0.00	0.02	16
MBL...	V	0000.0	0.00	0.02	16
MBL...	V	0000.0	0.00	0.02	16
MBL...	A	0.000	0.00	0.00	16
MBL...	A	0.000	0.00	0.00	16
MBL...	A	0.000	0.00	0.00	16

Beam Protection



Setup Beam Flag equations

- **Safe Machine Parameter system holds the SBF equations** used to configure the MPS
- SBF defines the intensity limit below which **beam can be considered safe**
 - **“SBF = TRUE”** => Beam intensity and energy **below damage limit**
 - **“SBF = FALSE”** => Beam intensity and energy **above damage limit**
- Maskable inputs of the BIS can be **masked if SBF=TRUE** (BLM, Collimation, RF,...)




- **NORMAL** was defined a factor 2 below the damage limit
- **RELAXED** has been established to allow 1 nominal bunch at high energy
- **VERY RELAXED** has been established to allow 3 nominal bunches at high energy

After LS1, the LHC will operate to an energy close to 7Tev => Normal SBF would allow an intensity of $\sim 1 \times 10^{10}$ (pilot beam)


SBF proposal -> See L.Ponce's talk

Beam Interlock System



Redundant BIS-LBDS re-triggering link

- **New direct link** from the BIS to the LBDS re-triggering lines (RTS)
- Motivation is to reduce the potential **risk for common mode failures** (e.g: +12 Vdc LBDS powering) following an extraction demand from the BIS
- Additional electronic boards **CIBDS** included in the **Beam Permit Loops**
- **Asynchronous Beam Dump** to be requested with a **250us delay**



- Dependability studies to analyse the impact on **machine availability** [6]:

Energy [GeV]	REQUIREMENTS	DEPENDABILITY STUDIES
Asynchronous dump	2 per 10 years	0.025 per 10 years
Synchronous dump	2 per year	0.011 per year

New user channels

LOCATION	INPUT	USER	ACTION
LHC P1	7	LHCf detector	ADDED
LHC P4	2,9,14	FBCCM/DIDT See E.Bravin's talk	ADDED
	7	WIC	DISABLED but maintained
LHC P5	13	CMS magnet	UPDATED (trigger on FPA)
LHC P6	6	CIBDS (BIS-LBDS retriggering)	ADDED to both left and right BICs
	14	TCDQ Beam 1&2 (BETS interlock)	ADDED
LHC P7	11	Crystal collimator experiment	ADDED

Beam Interlock System – Commissioning

- “MPS aspects of the Beam Interlock System commissioning” reviewed [7]
- **User permit validation** (some clients automated in ACCTESTING)


- **Software Interlock Permit – Applied to 2 BICs (CCR+SR3)**

- **Setup Beam Flag transmission through the GMT**


- **Beam Permit to LBDS (CIBDS)**

- Reliability run See N.Magnin’s talk
- Optical interfaces validation

- **LHC Beam Permit propagation to the injection BICs**




FMCM




Sensitivity to electrical network perturbations

- Electrical network glitches became one of the **main dump causes from powering systems**
- A large fraction **only affecting RD1 and RD34** circuits with no other equipment trip
- EPC **working on a new switch mode power converter** to replace the existing RPTG thyristor converters
- Current plans:
 - **LS1**: Power converter design, infrastructure preparation (cooling, electricity...)
 - **2015**: Production of the two RD1 and commissioning during 2015-16 Xmas
 - So far budget only approved for RD1, **no big gain without replacing RD34 as well!**



Software interlocks



New interlocks ADDED

- Currently **52 interlock types** implemented on SIS
- **Collimator BPMs:** interlock on the beam offset wrt collimator center
 - Current strategy is to prepare interlocks to dump if the beam is too far off from the center, but to activate later – need some experience with the new BPMs
- **Abort gap monitoring (BSRA):** [See E.Bravin's talk](#)
 - Activation of cleaning & dump
- **Virtual beta* for TLs:**
 - Similar concept as for ring collimators
 - For each TL optics, define all quad currents in LSA together with virtual β^*
 - SIS reads currents and compares to reference settings (every cycle)
 - If within tolerance publish the virtual β^* value associated with the optics
 - On TCDI side read β^* from MTG and check if in limit

Existing interlocks UPDATED

- **Access-Powering Interlock:** simpler and more robust link from LASS to SIS
 - Only active with no beam in the LHC. Ready for the restart of powering tests
- **COD interlock:** remained active in 2012 in parallel to the PC interlock server
 - Should be moved from SIS since PC interlock server was shown more powerful
- **PC current interlocks:**
 - Surveys the current for a series of PCs (QD/QF at injection) -> can be done better in the PC interlock server
- **TCDQ-beam interlocking:**
 - incorporate the TCSG6 BPM – more accurate!
- **Particle type interlock:** avoids that protons are sent into a ring setup for ions and vice-versa (injection)
 - So far tricky identification of the particle type with the current of SPS injection line (TT10) dipoles. To be replaced with information from the SPS telegram

Summary

- Quite some changes and upgrades implemented on the MPS backbone aiming at **increasing the machine dependability** and to adapt to new operational requirements
- **Consolidations will reduce machine downtime from magnet powering systems** mainly due to the reduced number of radiation induced spurious trips, improved rejection against mains perturbations, ...
- MP3 has **reviewed the powering procedures** and acceptance criteria to qualify all electrical circuit families
- Few changes on beam protection related systems (SBF equations, re-triggering BIS-LBDS link, SIS,...) will be validated **following dedicated MPS procedures already reviewed by the MPP**

Thanks a lot for your attention!

REFERENCES:

- [1] I.Romera, “Change of PIC configuration data for inner triplet corrector circuits RQSX3”, EDMS 1203408
- [2] I.Romera, “MPS aspects of the Powering Interlock System commissioning”, EDMS 896390
- [3] I.Romera, T.Ladzinski, “Change of the Interlocking of Powering and Access Systems”, EDMS 1246780
- [4] MP3, “MP3 Recommendation on the Decay Time Constants of the 13 kACircuits after LS1”, EDMS 1320722
- [5] MP3, D.Rasmussen, “MP3 Recommendation for the Reduction of Energy-Extraction Resistor Values in Selected 600A Circuits”, EDMS 1343241
- [6] V.Vatansever, “Dependability studies on the connection between LHC BIS and LBDS re-triggering system”
- [7] B.Todd et al, “MPS aspects of the Beam Interlock System commissioning”, EDMS 889281