





TI8: 23rd Oct 2004



TI8: 2005 The first hole



TI2: Autumn 2007

LHC TRANSFER LINES AND SECTOR TESTS


2014

First: credits → CO, ABT, ABP, ASR,
BI, OP, RF, CV, EPC, MPE, VSC, MEF,
ALICE, LHCb, CMS, ATLAS

Verena Kain
Reyes Alemany



TI8: 22nd Aug 2008



S7826LBDS: 5th Sep 2008

during LS1




after LS1




Motivation



Machine sub-systems operational





Fully integrated into the control system



Associated application software and cycle management available

Motivation






SPS-LHC Injection synchronization & Timing

BLM, BTV, BPM Commissioning



Linear Optics and Dispersion (TL+Ring matching)

BPM & MAGNETS POLARITY

First probe of the APERTURE





- Test scheduled **weekends** to minimize the inconvenience to the experiments and hardware commissioning
- **Pilot beam** $2-5 \cdot 10^9$ → less intensity → less radiation → less impact on post test tunnel activities



- + Contingency weekend



Strategy

- Setting up of TT60/TT40 extraction (before sector test, date to be defined)
- Beam down to TI₂/TI₈ TED






- Beam to TDI with MKI OFF (TI2 TED out)
- Beam to TDI with MKI ON

B1



- Beam to TDI with MKI OFF (TI₂ TED out)
- Beam to TDI with MKI ON
- Beam to IR₃ (TDI out)

B1






Pre-requisites

- HWC+ IST
- Powering test
- Dry runs
- Access system
- DSO
- Machine checkout



How to stop the beam



- Collimators with minimum gap on anti-collision switches = 0.5 mm
- 5 mm overshoot across nominal orbit
- Possible to tilt collimator to leave NO clearance

SECTOR TEST S23

INJ 1	CIB.SR2.INJ1.1	CIB.SR2.INJ1.2
	LHC Beam1	Nothing needed
	Permit	
	Operator switch	
	MKI2 status	
	Vacuum	
	MKI2 erratic	
IR2 (B1)	CIB.UA27.R2.B1	L2.B1
	MKI	BLM
	Vacuum	Vacuum
	ALICE detector	
IR3 (B1)	CIB.UJ33.U3.B1	CIB.SR3.S3.B1
	ACCESS_SB ⁽²⁾	BLM
	WIC ⁽²⁾	



(1) Should be tested @DSO test; if there are issues could have a jumper.
 (2) Covered by SIS; if doesn't work could have a jumper.

B1&B2 need to be commissioned


SECTOR TEST S78-S67-LBDS

INJ 2	CIB.SR8.INJ2.1	CIB.SR8.INJ2.2
	LHC Beam2	LBDS.B2
	Permit	
	Operator switch	
	MKI8 status	
	Vacuum	
	MKI8 erratic	
IR6 (B2)	CIB.UA67.R6.B2	CIB.UA63.L6.B2
	Vacuum	Vacuum
	LBDS (TSU)	WIC (septa)
	LBDS (PLC)	BLM
	CIBDS B2	
IR7 (B2)	CIB.SR7.S7.B2	CIB.TZ76.U7.B2
	BLM	Vacuum
		WIC ⁽²⁾
IR8 (B2)	CIB.UA87.R8.B2	L8.B2
	Vacuum	Vacuum

1. PIC is covered by SIS
2. The unmaskable inputs not needed for the Sector and will be disabled.
3. The maskable inputs if not commissioned and operator will have a jumper.



ALICE Shielding



**During sector test →
Non-designated area**




**Limit= 2.5 uSv/h at
the surface of the pit**



**One pilot lost goes
beyond the dose**

*One meter away from the pit
the dose rate is a factor of ~10
less

ALICE Shielding



Dose/ 10^{10} protons	CR	Top of pit	Top of pit @ 1m
No shielding (μSv)	100	10	1
PX24 shielding = 2 m (μSv)	1	0.1	0.01
D/ 10^{12} protons (μSv)	100	10	1
Time (min) allowed for 2.5 μSv	1.5	15	150
Time (min) allowed for 15 μSv	9	90	900

Special procedure will be written
 → access CR will not be possible, neither the access to PX24 through the surface building.

Thanks ALICE!! → planning modified to allow the installation/removal of the shielding for Sector Test

The tests were undoubtedly an essential precursor to the successful start of LHC Beam Commissioning

2004 TI8 test

2005 TI8 test (high intensity beam)



2007 TI2 test

2008 5 injection tests

1. S23
2. S78, S23
3. S78-S67, S23-S34-S45
4. S23-S34-S45
5. Whole ring

2009 2 injection tests

1. TI2, S23, first ions in LHC
2. TI2/TI8, S23, S78-S67-S56



(Following plots → ref: M. Lamont et al. “The LHC Injection Tests”, LHC Performance Note 2008-10-21)


A bit of History

First trajectory

BPMs triggered at the first passage (async mode)

Orbit correction to **+/- 10 mm H/V within few shots**

First corrected trajectory: **+/- 3 mm** (LHC design specs: +/- 4 mm)



A bit of History



First BPM and COD polarities check

check

BPMs polarity errors spotted

Phase error S23: erroneous application of b2 harmonic compensator (Fig. top)


Wrong amplitude S67:
Inversion of polarity of Q6.L7 (Fig. bottom)



— Theoretical response
█ BPM measurement

A bit of History

First BPM and COD polarities check




Kick response measurements can spot cross-plane coupling


— Theoretical response
█ BPM measurement

A bit of History

First dispersion measurement




Dispersion measurement revealed optics problem in IR3
Right → some of the trim quads powered with the wrong polarity,



and a strong mismatch between TI8 and S78 → a real puzzle and took some time to understand


A bit of History

First aperture



First aperture scan (first quench with beam, 1 pilot $\sim 4 \cdot 10^9$ p) \rightarrow two COD/plane 90° phase advance; BLM determine the loss location

Bottleneck in injection region found, confirmed by radiation survey and fixed (Fig. top)




H ARC Aperture 18-20 mm. V limitation at Q8/Q7-L3 of about 10 mm (Fig. bottom)

Coupling errors detection

A bit of History

BLM commissioning



BLM response at
collimators

TI2/TI8/S23 test schedule

	Time	SECTOR TEST 1: TI8, TI2 & S23	Δt(h)
Friday	12	Patrol and closure of LHC and experiments. Magnets pre-cycle. Last interlock checks/tests. TT40/TT60 extraction (TEDs in)	3
	15	Beam down to TI2 TED, establish rough trajectory. LHC mastership. MSI & MKI pulsing. First TLBI commissioning. Timing of beam and	4
	19	TI2 TED out, MKI off/on, beam to TDI. Thread last part of TI2 and MSI. Set TDI, CLI	2
	21	TDI out, beam to R3 right. First BLI commissioning (BLM, BPM, BTV). Threading	3
Saturday	0	BPMs and orbit corrector polarity checks TI2 & Ring, linear optics & dispersion TI2 & Ring	8
	8	Beam down to TI8 TED, establish rough trajectory. LHC mastership. MSI & MKI pulsing. First TLBI commissioning. Timing of beam and	4
	12	Screen matching TI2 injection	2
	14	TDI in, physical aperture measurements in TI2 and the injection region. ALICE BCM+BLM calibration in parallel	8
	22	MKI2 waveform scan	2
Sunday	0	TL trajectory stability TI2 beam on TED. More TLBI commissioning	3
	3	MKE waveform scan LLS4/LLS6	4
	7	BLM latency check	1
	8	BLM response (collimator splashes)	2
	10	Aperture R2 and S23 Could be combined	8
	18	Magnet polarity (skew quads, sample of MQT, MQTL)	3
	21	BMPs and orbit corrector polarity checks TI8	2
23	Set CDI, automatic application TI2	3	
Monday	2	Rough LLS4 extraction region aperture scan	1
	3	Pre-cycle effects	3
	6	End of TI2/TI8/S23 test. RP survey	2

Preliminary

ALICE
BCM+BLM
calibration > 1
hour

**TOT: 66 h →
8.25 shift**

S78-s67-LBDS test schedule


	Time	SECTOR TEST 2: T18, S78-S67, LBDS B2	Δt(h)
Friday	12	Patrol and closure of LHC and experiments. Magnets pre-cycle. Last interlock checks/tests. T60 extraction (TEDs in)	3
	15	Beam down to T18 TED, establish trajectory. LHC mastership. MSI & MKI pulsing. LHCb TED shots in parallel.	2
	17	T18 TED out, MKI off/on, beam to DI. Thread last part of T18 and MSI. Set DI, CLI. More LBI commissioning	2
	19	TDI out, beam to R7 right. First BL commissioning (BLM, BPM, BTV). Threading	3
	22	Beam to R6 LBDS B2 with orbit correctors (TCDO & TCSG in beam and interlocked). Steering. Beam dump line BL commissioning. Synchronization. Rough check of extraction channel aperture.	3
Saturday	1	Beam to R6 LBDS B2 with inject and dump (TCDO & TCSG in beam and interlocked). Steering. More check BL. Synchronization. Rough check of extraction channel. MKD knob test. MKB	6
	7	BPMs and orbit corrector polarity checks T18 & S78-S67, linear optics & dispersion T18 & S78-S67	9
	16	Screen matching T18 injection	2
	18	TDI in, physical aperture measurements in T18 and the injection region. LHCb BCM+BLM calibration in parallel	8
Sunday	2	MKI waveform scan	2
	4	TL trajectory stability T18 beam on TED. More LBI commissioning. LHCb TED shots in parallel	3
	7	Rough SS6 extraction region aperture scan. LHCb TED shots in parallel	1
	8	BLM latency check	1
	9	BLM response (collimator splashes)	2
	11	Aperture R8 and S78S67 Could be combined	9
	20	Magnet polarity (RCO.A78B2, Q5L8, skew quads, sample of MQT, MQL)	4
Monday	0	Set TCDI, automatic application T18 (if not done in ST1)	3
	3	Pre-cycle effects	3
	6	End of T18/S78S67/LBDS B2 test. RP survey	2

Very Preliminary

ST2 program = f(outcome of ST1)

LHCb TED shots = 2+3+1 hours

TOT: 66 h → 8.25 shift



LHC SECTOR TESTS 2014

Home

SCHEDULE

MACHINE CONFIGURATION

BEAM MEASUREMENTS

MEETINGS AND DOCUMENTS

LHC Sector Tests 2014

1. SCHEDULE
2. MACHINE CONFIGURATION
3. BEAM MEASUREMENTS
4. MEETINGS AND DOCUMENTS

lhctest2014.web.cern.ch

Conclusion

- Sector tests are **essential precursor** and a **high profile milestone** in preparation for full beam commissioning
- Two sector tests are proposed for 2014:
 - **ST1: 1-2 Nov 2014** → ti2/ti8 & s23
 - **ST2: 22-23 Nov 2014** → ti8 & s78-s67-lbds b2
 - **ST3: 13-14 Dec 2014** → contingency
- First draft plan is circulating for comments and optimization