

The LHC beam commissioning in 2015 will be based on the experience accumulated during the run 1. On the other hand, the operation at higher energies and with different bunch spacing will pose new challenges and will require additional measurements. The commissioning plans for the first months of operation are discussed and the required beam measurements to confirm/decide the key parameters for the 2015 machine configurations are presented. The additional requirements for systems that during LS1 underwent significant upgrades or changes are taken into account.