

5th LHC Operations Workshop, Evian2014

June 2nd-4th, 2014


Hôtel Hermitage, Evian Les Bains, France

Strategy for the First Two Months and Key Early Measurements

Stefano Redaelli, BE-ABP

with G. Arduini, M. Giovannozzi, M. Lamont, R. Tomas, J. Wenninger

Ackn.: Elias, Nicolas, Stéphane, Tatiana, Roderik, Verena, many others





Outline



- Introduction
- Lessons from 2012
- Commissioning steps
- Decision points
- Conclusions



Introduction



- ☑ This talk will address:

Commissioning strategy and key measurements for the first two months of operation in 2015.

Definition: first turn to first stable beams with 2-3 bunches.

Period presently allocated in the 2015 LHC schedule (M. Lamont et al.).

- ☑ **The 2015 beam commissioning plan will be based on our mature experience from the LHC Run 1**

We hope that we can proceed as in 2012 . . .



Realistically, the 2011 case will be more representative

- ☑ **The basic assumptions for machine configurations are taken as an input**

Will not repeat the discussions of the 1st day of this Evian.

Try to give some inputs on how to decide it...

Recap.: 2011 versus 2012



Intensity ramp up:


- Increase number of bunches,
- then push bunch intensity

Followed by a re-commissioning of the optics.

Achieved “ultimate” parameters in record time, then fine tuning.



More details in Laurette’s talk

2012 commissioning





2012 commissioning





We achieved safely a record setup time!


Among the many ingredients:

Excellent performance and knowledge of accelerator systems and of the machine (stability, reproducibility, ...).

A careful choice of parameter set, with "reasonable" risks (and some luck?)

Ex.: 0.5 sigma margins compared to the 2011 estimates; beta-beating below 10%.

→ What is a reasonable risk for the startup after LS1?



Additional important aspects for the success:

- ***Commissioning effort was focused on high-intensity proton operation!***
- ***Minimum (no?) hardware changes to cope with, from 2011.***
- ***No changes in optics configurations compared to 2011.***
- ***Relying that few nominal bunches at top energy were SAFE.***


This is not the case for the 2015 baseline!

MP implications on commissioning




7 TeV equiv.
inferred from
HRM beams

- New damage limits proposed in line with updated accident scenarios (Annecy '13):
 - Onset of plastic damage : 5×10^9 p
 - Limit for fragment ejection: 2×10^{10} p
 - Limit of for 5th axis compensation (with fragment ejection): 1×10^{11} p



Inermet 180, 72 bunches



A. Bertarelli et al.



7 TeV equiv.
inferred from
HRM beams

- New damage limits proposed in line with updated accident scenarios (Annecy '13):
 - Onset of plastic damage : 5×10^9 p
 - Limit for fragment ejection: 2×10^{10} p
 - Limit of for 5th axis compensation (with fragment ejection): 1×10^{11} p


Several new constraints to cope with:

- Protection settings for **first ramp** and for setup at top energy;
- Definitions for safe setup conditions and impact on validation procedures;
- Details of intensity ramp-up plan
-

Need to followup the transverse collimator movements in IR1/5!



Inermet 180, 72 bunches



We should expect a reduced commissioning efficiency. Details have to be sorted out for the different commissioning steps.



- Introduction
- Lessons from 2012
- Commissioning steps**
- Decision points
- Conclusions



- ☑ **2015 machine configuration** (inputs from sessions 1-2):
 - *Beam energy ≤ 6.5 TeV;*
 - *Same excellent aperture in interaction regions;*
 - *Same optics correction accuracy below 10%;*
 - *Collimator hierarchy as in 2012 (mm settings);*
 - *11 real sigmas for crossing angle (3.75 micron emittance);*
 - *Assume that there is no need of additional margins if optics changed;*
 - *Machine reproducibility as in Run 1.*

- ☑ **This gives about 65 cm β^***
 - *If we go from day 1 at the aperture limit!*
 - *70 cm would provide some margins...*


- ☑ **What is the decision on collide&squeeze / levelling?**
 - *1 slide late on implications, not put in my commissioning plan.*

- ☑ **I do not treat the fall back option of 50 ns.**

- ☑ **Hardware change: collected inputs from sessions 1-5**




Overall commissioning strategy



A very simplified diagram!



Commissioning phases as foreseen




Commissioning phases as foreseen



Work in progress

Stage A


Pilot physics run



LHC Beam Commissioning

Home

Phase A.1	First turn: injection commissioning; threading, commissioning beam instrumentation. Ring 1, ring 2.
Phase A.2	Circulating pilot: establish circulating beam, closed orbit, tunes, RF capture, ...
Phase A.3	450 GeV initial commissioning: system commissioning: instrumentation, beam dump,...
Phase A.4	450 GeV optics: beta beating, dispersion, coupling, non-linear field quality, aperture,...
Phase A.5	450 GeV, increasing intensity: prepare the LHC for unsafe beam
Phase A.6	450 GeV, two beam operation
Phase A.7	450 GeV, collisions
Phase A.8	Snap-back and ramp: single beam/two beams
Phase A.9	Top energy checks
Phase A.9.5	Beam commissioning with experimental magnets
Phase A.10	Top energy, collisions
Phase A.11	Squeeze: Commission the betatron squeeze in all IP's



Snap-back Ramp

CERN
CH-1211 Geneva 23
Switzerland

CERN
CH-1211 Geneva 23
Switzerland

CERN
CH-1211 Geneva 23
Switzerland



the
Large
Hadron
Collider
project

LHC Project Document No.
LHC-OP-BCP-0002 rev 1.0

CERN Div./Group or Supplier/Contractor Document No.

LHCCWG

LHC Project Document No.
LHC-OP-BCP-0005 rev 0.2

CERN Div./Group or Supplier/Contractor Document No.

LHCCWG

LHC Project Document No.
LHC-OP-BCP-0012 rev 0.2

CERN Div./Group or Supplier/Contractor Document No.

LHCCWG

EDMS Document No.

876869

Date: 2007-11-30

Beam Commissioning Procedure

LHC COMMISSIONING WITH BEAM: PHASE A.11 (BETATRON SQUEEZE)

Abstract

This document describes the LHC beam commissioning procedures for the betatron squeeze at 7 TeV in all IP's without crossing angle. It covers the entry conditions, the commissioning procedures and exit conditions of this phase. Possible problems and open questions are also listed.

Prepared by :

R.Alemany Fernandez
M. Giovannozzi
M.Gruwé
V.Kain
L.Ponce
S.Redaeli
W.Venturini

Checked by:

LHCCWG

Approved by:

R.Bailey
O.Bruning
P.Collier
M.Lamont
S.Myers

On behalf of the LHCCWG


LHCCWG list:

R.Alemany Fernandez, G. Arduini, R. Assmann, R.Bailey, O.Bruning, H.Burkhardt, A.Butterworth, P.Collier, S.Fartoukh, M.Giovannozzi, B.Goddard, J.-J.Gras, M.Gruwé, R.Jones, V.Kain, P.Koutchouk, M.Lamont, A.MacPherson, L.Ponce, S.Redaeli, R.Saban, F.Schmidt, R.Schmidt, R.Steinhausen, E.Todesco, J.Uythoven, W.Venturini Delsolaro, J.Wenninger, T.Wijnands, F.Zimmermann

Approval list:

F. Bordry, L. Bottura, T. Camporesi, P. Ciriani, K. Eggert, L. Evans, M. Ferro-Luzzi, R. Garoby, J. Lettry, P. Lebrun, T. Linnecar, S. Maury, V. Mertens, K.-H. Mess, G. Mornacchi, M. Nesi, W. Riegler, G. Roy, H. Schmickler, A. Schopper, F. Strubini, E. Tsismelis, R. VanWeelden

Building on Run 1 experience...



In reality, blocks are interleaved with each other!

Key activities:

Threading, capture, initial BI

Initial orbit and optics, more BI, polarities, etc.

System commissioning: feedback systems, collimation, RF, injection, LBDS, detailed BI, ...

Optics measured and corrected.

Flat orbit setup followed by IR bump commissioning.

Beam measurements: aperture for given

Ramp. FiDeL, decay, saturation. Feedbacks.

Squeeze. Steps followed by continuous functions.

Re-iterate on orbit, optics, aperture, ...

Collisions.

Machine protection and validation.

No details on the “standard” phases in this presentation.

Emphasis on:

- New requirements following LS1 changes
- New key measurements to determine LHC configuration.



New commissioning requirements (i)



☑ Experiments

- *Special runs needed early on.*
- *Dedicated optics setup for VdM scans.*

☑ Operations

- *New measurements/corrections for FiDeL (saturation);*
- *Cleaner corrections in IRs (optics, orbit);*
- *“Exponentially increasing” number of optics to measure precisely*
- *...*

☑ Collimation

- *New hardware with BPMs: dedicated tests;*
- *Verification of new IR layouts with TCL collimators;*
- *Improve / optimize validation procedures.*



New commissioning requirements (ii)



Beam instrumentation

- *Beam size measurements;*
- *BLM system: new LIC's in IR2/8;*
- *New threshold setup?*
- *New BI for interlock purposes;*
- *New DOROS BPM's, in addition to the ones in collimators.*

RF / ADT

- *Many new features / hardware changes;*
- *Measurements as in Philippe's talk.*

Injection and LBDS

- *Validation of new BETS interlocks;*
- *New TDI and TCDQ block hardware; check TDI heating;*
- *Wave form scans and kick response;*
- *Repeat measurements previously not done yearly (see Wolfgang).*

Can we fit all that in 2 months?




Outline



- Introduction
- Lessons from 2012
- Commissioning steps
- Decision points**
- Conclusions

Key “decision points”





- Propose to foresee early on a measurement with bumps at injection: first iteration on beta***
 - *Was only done in 2009, but recent analysis indicated that it can give a good feeling of beta* after squeeze!*
 - *Should be done after establishing 450 GeV orbit and optics*
 - *0.5-1.0 shift to cover IR1/5*

- Then, require aperture checks and detailed measurements at top energy, squeezed for final parameter validation.**
 - *Different iterations following optics corrections;*
 - *Detailed plan of validation of provided protection levels (as 2012);*
 - *Note that we will need to be more careful at higher energy!*



Non-linear correctors



- ☑ **We will need known and clean starting conditions to optimize the effects of Landau octupoles**
- ☑ **Models of de-tuning with amplitude not fully understood: discrepancy at 450 GeV**
 - *Need to understand better effect of MCO's (and MDO's)*
- ☑ **In addition, the optics team proposes:**
 - **improved check of MCS correctors.**
 - **settings up of MSS as measured in MDs.**
- ☑ *Rogelio can provide the full details.*



- Need to comparatively assess different setting options against impedance, with nominal bunches**
 - *Tune-shift measurements versus settings?*
 - *Recap.: “2 sigma retraction” give a significant gain compared to 2012 settings in mm if ok for impedance.*

- Propose to explore “pre-collision” settings with individual secondaries more open.**
 - *Tricky in several aspects (cleaning vs MP): do not want to rely on new schemes if not validated by measurements.*
 - *Becomes critical in case of problem with the relaxed settings.*
 - *See RB’s presentation at an LBOC in Feb. 2014.*

- At least initially, monitor regularly performance: cleaning, machine stability, loss spikes.**
 - *Anticipate MDs on halo studies/control in case of problems.*



Impedance, 2 beams and octupoles



- ☑ **In my opinion, the goal during commissioning should be to conclude as soon as possible about the need for collide and squeeze in IR1/5.**
 - *But firm conclusions can only come during the intensity ramp.*
- ☑ **Clean measurements of Q' , including reproducibility, must be part of the initial commissioning**
 - *Foresee dedicated fills for measurements, single vs 2 beams*
- ☑ **Instability threshold measurements.**
- ☑ **What other measurements can we do with single bunches?**
 - *Ongoing preparation by Elias' team*



Collide&Squeeze/Squeeze-in-collision



- ☑ **We need to decide as soon as possible if this is part of the first commissioning!**
 - *The choice has a major impact on the commissioning plan.*
- ☑ **Two options are under discussion**
 - (1) *Levelling in stable beams for LHCb;*
 - (2) *Collide&Squeeze in IR1/5 for beam stability purposes.*
- ☑ **Both scenarios have important impacts:**
 - *Special commissioning of optics corrections, in particular for (1).
“exponential increase” of optics configurations.*
 - *Adequate validation strategies have to be defined.
Optimizations possible, but the validation of (1) will not come for free!*
 - *Challenges: prepare commissioning with “minimum” impact in case fall back is required.*



Conclusions



We had the machine well under control in Run 1

Recalled commissioning achievements in 2012 and 2011

An ambitious restart plan is now on the table

Necessary system re-commissioning will require time.

New optics conditions and operational scenarios not fully proved.

Inputs from Evian2014 must now be put into a complete program.

Are two months enough to fit all that? Is there room to optimize the number of scenarios?

Key “decision points” will confirm (decide?) the 2015 LHC configuration: presented a first list.

MP impact on efficiency should not be underestimated.

The overall performance would profit from a well prepared re-commissioning after some stable physics

More relaxed startup conditions to easy and fasten the commissioning

Then re-tune more precisely parameters after we have re-learnt.

Can happen in Sep. 2015 or be postponed until the Christmas stop.