



Two Beam Module Program News



- **Organizational changes**
- **Measurements on the Test Module**
- **Status of the CLEX module**
- **Outlook and conclusions**





Organizational changes



- Germana left the BE-department and the rf-group as of May 1st
- All activities have been integrated into BE-RF-MK
(section leader: Olivier Brunner)
- Nuria took on the x-band structure fabrication and development
- Markus and Steffen are responsible for the two beam module program
- Future industrialization studies remain with Philippe, some structure related studies are likely followed up by Nuria



TBM status



- Mechanical prototype module successfully constructed
- Currently under thermal and alignment testing
- Two more modules under assembly for integrated tests

- One module under construction for beam testing in CTF3.
Installation will start end of June

- Module test program in the lab until 2015, in CLEX until 2016
- Future plans: Incorporate lesson learned form the test program into the design of next generation modules and industrialization studies



Thermal test data example




Water only

Unloaded


Loaded



Temperature evolution (Zero - Unloaded - Loaded conditions)



Temperature fluctuation: ± 0.2 °C



Elena Daskalaki, Alex Vamvakas,
Anastasia Xydou




Results



Thermal time constants

Component	Time constant τ (min)
SAS#1	5.16
SAS#2	5.30
SAS#3	5.05
SAS#4	5.08
AS Load 1	1.86
AS Load 2	2.00
AS Load 3	1.90
AS Load 4	1.80
PETSu#1	16.19
PETSu#2	18.83
WG	18.61
RFN Loads	1.80





Results and comparison with FE-simulations





Components' temperatures in steady-state (°C)

	DBQ only			Unloaded			Loaded		
	Experiment	Simulation	Diff.	Experiment	Simulation	Diff.	Experiment	Simulation	Diff.
SAS#1	23.7	24.5	0.8	29.5	31.9	-2.4	29.0	30.7	-1.7
SAS#2	24.3	24.5	0.2	32.2	29.7	2.5	31.5	29.3	2.2
SAS#3	24.4	24.5	0.1	32.2	31.8	0.4	31.5	31.2	0.3
SAS#4	24.2	24.4	0.2	32.2	29.2	3.0	31.5	29.0	2.5
PETSu#1	22.7	23.2	0.5	25.9	29.8	-3.9	26.4	27.6	-1.2
PETSu#2	23.2	23.2	0.0	29.4	32.4	-3.0	30.1	29.3	0.8
DBQ#1	37.6	39.3	1.7	34.4	32.2	2.2	33.2	31.8	1.4
DBQ#2	36.1	38.4	2.3	33.6	33.9	-0.3	31.8	33.6	-1.8



Further analysis



$$\dot{Q}_{water} = \dot{m}c_p (T_{water, out} - T_{water, in})$$

$$\dot{Q}_{air} = h(T_{comp} - T_{amb})A$$



Further analysis






	$T_{\text{water,in}}$ (°C)	$T_{\text{water,out}}$ (°C)	ΔT (°C)	Q_{water} (W)	T_{amb} (°C)	T_{comp} (°C)	Q_{air} (W)	Q_{tot} (W)	F (m3/h)	F_{measured} (m3/h)
SAS1	24.12	30.02	5.90	744	20.00	29.16	73	817	0.108	
SAS2	24.44	32.12	7.69	720	20.00	32.18	97	817	0.081	
SAS3	25.05	35.01	9.96	701	20.00	34.53	116	817	0.061	
SAS4	25.12	33.34	8.22	714	20.00	32.94	103	817	0.075	
SAS total									0.324	
PETS	24.63	29.37	4.74	267	20.00	27.79	153	420	0.048	
Total									0.373	0.311

- One flow meter measures the total flow
- Flow at each cooling channel (4 SAS and PETS) is not known

Flow meter accuracy: $\pm 2\%$ measured value




CLEX module installation






CLEX module supporting system received and tested





Status of main components



Pets, DB-Quad and girder available
ACC-structures: final brazing steps
Waveguide system: final brazing steps
BPM: rf test and assembly


Missing: some supports, clamps,
transition beam chambers



CLEX module installation



Cabling scheme preparations






Module electronics for CLIC




Examples base on NI-hardware, a radiation environment test is planned in CTF3 acquiring rf signals from the CLEX module






Klystron base module design



Alexandre Samochkine



Klystron base module design



ST0580463_01 CLIC-K Two tunnels



Outlook and conclusions



- The two beam module program will continue as advised by the module review committee
- Good progress in analyzing the data taken on the Lab-module (see as well Helene's talk), to be continued
- Highest priority right now is to get the CLEX module installed and start experiments with it
- Will have to review (again) the objectives and configurations of the lab-based module program evolution
- Prepare transition to 'next' generation modules



End



The Evolution Of The Bmw 5 Series



1980

2012



LADA. Perfect From The Beginning

9GAG.COM/GAG/4298226

Phase 2: Duty cycles tests



STEP	#	INPUT									
		T _{amb} (°C)	v _{air} (m/s)	Q (W)					T _{i,water} (°C)	ΔT _{o,water} (°C)	
				SAS	AS Load	PETS	RFN Load	DBQ		SAS	PETS
Nominal operation mode	DBQ only	20	0.7	0	0	0	0	150	25	0	0
	Unloaded	20	0.7	820	178	220	178	150	25	10	6
	Loaded	20	0.7	683	137	220	178	150	25	8.3	6
	DBQ only	40	0.7	0	0	0	0	150	25	0	0
	Unloaded	40	0.7	820	178	220	178	150	25	10	6
	Loaded	40	0.7	683	137	220	178	150	25	8.3	6
Failure mode SAS breakdown	Loaded	20	0.7	683	137	220	178	150	25	8.3	6
	SAS breakdown	20	0.7	0	27.4	220	178	150	25	0	6
	PETS off	20	0.7	0	27.4	55	0	150	25	0	1.5
	Loaded	20	0.7	683	137	220	178	150	25	8.3	6
	Loaded	40	0.7	683	137	220	178	150	25	8.3	6
	SAS breakdown	40	0.7	0	27.4	220	178	150	25	0	6
	PETS off	40	0.7	0	27.4	55	0	150	25	0	1.5
	Loaded	40	0.7	683	137	220	178	150	25	8.3	6
Failure mode PETS breakdown	Loaded	20	0.7	683	137	220	178	150	25	8.3	6
	PETS breakdown	20	0.7	683	137	55	0	150	25	8.3	1.5
	SAS off	20	0.7	0	27.4	55	0	150	25	0	1.5
	Loaded	20	0.7	683	137	220	178	150	25	8.3	6
	Loaded	40	0.7	683	137	220	178	150	25	8.3	6
	PETS breakdown	40	0.7	683	137	55	0	150	25	8.3	1.5
	SAS off	40	0.7	0	27.4	55	0	150	25	0	1.5
	Loaded	40	0.7	683	137	220	178	150	25	8.3	6