

Wrap up from WP6

**A. Ballarino for the WP6
CERN, Geneva**

KEK, 21st November 2014

16th Hi-Lumi LHC Extended Steering Committee

Task leaders: A. Ballarino, U. Wagner (**CERN**)

Y. Yang (**University of Southampton**), F. Broggi (**INFN**)

Presentations

Tuesday, 18/11/2014

- Status of project and future milestones, A. Ballarino
- Radiation aspects at LHC P7, P1 and P5 C. Adorisio


Wednesday, 19/11/2014

- Cryo for Superconducting Links, S. Claudet
- Progress on cryostat design, Y. Yang
- Update on electro-thermal behaviour of superconducting cables in the links, Y. Yang
- Update on integration studies at LHC P1, P5 and P7, Y. Muttoni

Thursday, 20/11/2014

- Update on energy deposition studies at IP1, C. Santini
- Preliminary results on energy deposition studies at IP7, A. Bignami

SC Links for LHC



R2E → Powering of arc

Hi-Lumi → Powering of Triplets + D1
Hi-Lumi → Powering MSs

R2E → Powering of arc


Hi-Lumi → Powering of Triplets + D1
Hi-Lumi → Powering MSs

R2E

Betatron Cleaning Collimators

A. Ballarino


SC Links for LHC



R2E Workshop at CERN in October 2014

A. Ballarino

SC Link, LHC P7



$L = 20 \text{ m}$
(25×2) 1 kA @ 25 K, LHC Link P7

High-Current Rating, LHC P1 and P5

Hi-Lumi Triplets and D1



Cu



MgB₂, $\Phi = 0.85$ mm



18 MgB₂ wires
 $\Phi = 6.5$ mm

20 kA

Six cables, $\Phi = 19.5$ mm



Concentric ± 3 kA

Seven cables, $\Phi = 8.4$ mm




0.4 kA

Four cables



0.12 kA

Eighteen cables





$\Phi_{\text{ext}} \sim 65$ mm

Mass ~ 11 kg/m
(880 kg for $\Delta H=80$ m)

I_c Measurements

Short Samples – 4.2 K


- To characterize and qualify the wire, critical current measurements on **15 cm-long** samples are carried out in **parallel** magnetic field



Billet MFT 281	0 T	0.2 T	0.5 T	1 T	2 T	3 T
No. of samples	13	24	39	69	69	69
Average I_c [A]	841	811	649	402	192	108
RMS I_c %	3	3	3	4	3	3
Max I_c %	3.4	3.2	4.2	7.0	6.6	6.4
Min I_c %	-5.1	-7.2	-8.9	-9.7	-9.0	-7.9

B. Bordini, EUCAS 2013

MgB₂ Cables developed and tested at CERN





A. Ballarino

ΔT along line $< 1 \text{ T}$

Problems for a Single DFH with Multiple Chimneys of Current Leads

The chimney assembly of LHC DFC becomes difficult for DHF of SC link:

1. Constraints of transport to TZ76 require the in-tunnel integration of current leads.
2. Installation of current leads is tricky due to limited height in TZ76.
3. Splice of SC link in situ requires substantial side access, leading to oversized cryostat, too tight for the TZ75 width.




Y. Yang, University of Southampton

WP6.3 New DHF Design for P7

1. Individual current leads


3. Electrical interconnection box



Y. Yang, University of Southampton

WP6.3 New DHF Design for P7

- ❑ Compact DFH design assembled in tunnel with fully open access for inter-connection to SC link
- ❑ Discrete current lead units flexibly attached to DHF via HTS cables in transfer-line
- ❑ Easily transported within the tight constraints in TZ76.







Y. Yang, University of Southampton


WP6.4 Measurements on the Quench

Characteristic of MgB₂ Twisted-Pair Cables


Y. Yang, University of Southampton



Radiation aspects at P7, P1 and P5



IR7 – LS3, 1 month of cooling time



C. Adoriso, CERN


- **Installation of the Super Conducting Link passing through the LSS7:** evaluation of detailed Work and Dose Planning is needed to optimize the intervention
- For the **removal of the DFBX** and the installation of the SC links the evaluation of detailed Work and Dose Plannings is needed to optimize the interventions (working and passaging through activated area (inner triplet area) and activated equipment (e.g. TCL collimators, TAN))

Cryogenics for SC Links

- For P1 & P5, a completely new cryogenic distribution system will be studied and implemented: the needs for the sc links will surely be part of the design and associated optimisation. The potential vertical part might need specific study (transient, stability)
- For P7, a cooling process compatible with existing constraints exists since spring'14, we would be ready to proceed with definition of piping & valve requirements


S. Claudet, CERN

Overview of Point 7




Y. Muttoni, CERN

Integration at LHC Point 7




Y. Muttoni, CERN

Integration of Cold Powering System at LHC P7



Option 2: more complex routing routing




Option 1: simplified routing

Integration tests at CERN in Spring 2015 using a 60 m long SC Link (cryostat + cable) to verify the two options – and select the most convenient

Y. Muttoni, CERN

Integration of Cold Powering System at LHC P7




Space reserved for collimators ?

extracted from : ST0609460_01
JP.Corso le 7.10.2014

Option surface: all other equipment

Point 5



MACHINE SIDE, WITH NEW SHAFT + PC

7) SD (Steel)

- Dimension: 20 x 30 = 600m²
- Hmax = 12.0m
- Services (in;out): HV, water, SC Links ; ?
- Crane not costed (20t ?)

8) WARM COMPRESSOR (Conc)



- Dimension: 15 x 40 = 600m²
- Hmax = 9m
- Services (in;out): HV, water, Cryo pipes ; ?
- 20t crane not costed

10) PARKING, ROADS, GALLERIES

- Car Park: 20 places added
- New Road: 180m(L), 8m(W)
- New Access road: 70m(L), 6.5m(W)
- Galleries for services: 110m(L), Cross section 2.0m(W) by 2.5m(H)
- Landscaping: 6,600m²


Option: underground

Point 5





Surface or underground installation: huge implication on system design
Activity on test of vertical SC-Link start in Jan 2015

Sc Link in P7 – Radiation aspects



Dose at LHC P7



The maximum dose is about 40 kGy integrated over a period of 30 fb⁻¹



If also we extrapolate proportionally to 3000 fb⁻¹ we will obtain only **4 MGy** over the whole period of exercise