





2m Model Magnet Development of D1 and Plans

T. Nakamoto, M. Sugano, H. Kawamata, S. Enomoto KEK

4th Joint HiLumi LHC-LARP Annual Meeting 17-21 November 2014, KEK




The HiLumi LHC Design Study is included in the High Luminosity LHC project and is partly funded by the European Commission within the Framework Programme 7 Capacities Specific Programme, Grant Agreement 284404.



2m-long Model Magnet - Overview

Single-layer coil, 4-split spacer collars, collared yoke by keying



Deliverables and Near-term Plan

One 2m long model magnet will be built and tested at KEK. The second model development is also planned.

Up to now, one 2m long test coil was fabricated and the coil size measurement has been done.

- Dec. 2014 A short mechanical model
- April 2015 1st 2m long model
 - Field optimization by ROXIE and end spacer design are underway.
 - Coil winding would start at Jan. 2015.
- June 2015 Commissioning of test stand
 - A new header (cryostat flange) for D1. To be inspected by local government.
 - A new pair of 15kA CLs
 - Upgraded 15kA P/C and buses
- Sep. 2015 Cold test of 1st model
- Dec. 2015 2nd 2m long model
- Feb. 2016 Cold test of 2nd model

SC Cable Supply & Schedule


NbTi LHC MB outer cable supplied by CERN for the new D1.


Delivery Date	Objective	Requirement	Remark
Feb. 2013	10 stack meas. (a piece length > 0.3 m)	~50 m w/ MB type insulation	Both MB inner and outer cables w/ MB type insulation
Jan. 2014 May 2014	1 practice coil [*] + 2 real coils for the 1 st 2-m long model + 1 spare coil	220 m** x 4	LHC MB outer cables w/ MB type Apical insulation
April. 2015	2 practice coils + 2 real coils for the 2nd 2-m long model	220 m x 4	LHC MB outer cables w/ MB type Apical insulation
JFY2016 (prospect)	6 or 7 full-scale magnets + 4 practice/spare coils	600-640 m x 18	LHC MB outer cables w/ MB type Apical insulation





GFRP End Spacers, Wedges

- GFRP: MGC BT2160/2170 + S2 glass by ARISAWA
 - Radiation resistance beyond 50 MGy
 - similar modulus as G10: 29 GPa
 - But 30 % higher mechanical strength
- End-spacers: manufactured in-house
 - Design by ROXIE
 - Modeling with NX, Drawing with Solid Edge
 - CAD/CAM CATIA V5
- Wedges
- Adhesion: Cyanate Ester (MGC BT2160RX)












2m Model Coil

Demonstration of coil fabrication with a first 2m (test) coil.








The detail of test coil fabrication is presented by M. Sugano.

Ground Insulation

- Ground Insulation: same concept as MQXA
 - 4 layer of 0.125 mm thick Polyimide insulation (Upilex-RN)
 - Large shrinkage of the coil during the assembly should be taken into account.
- Brass shoes to intervene laminated collar sheets and the insulated coil.
- Collaring mandrel ensuring the proper coil form.
- Concept and design checked by the practice model.









QPH & Spot Heater

- QPH might not be necessary for the D1 because peak temperature is estimated to be 300K by a conservative scenario.
- Quench Protection Heater (0.25 mm think) for model magnet R&D
 - Still searching for manufacturer in Japan.
 - Possibility of supply from CERN
 - Necessity??
- Spot heaters will be implemented in the model magnet for the quench protection study.
 - higher field at the straight section
 - lowest field at the coil end (probably at lead-out)
- CLIQ might secure the quench protection?
 - Experimental study with the 1st model magnet



Collars


- Stainless steel: NSSC 130S (same as YUS130S)
 - 12 tons of NSSC-130S sheets (2.3mm & 2.6mm thick) delivered. This can cover the model magnet development and >30% of the 7-m long full-scale magnets production.
 - Specification, once set for the LHC MB, is fulfilled. Very low permeability of 1.002 confirmed at RT/4.2K.
- 4-way split collar concept for the dipole coil to avoid the unwanted warp at the fine-blanking process.
 - Collars work as spacers between the coil and the yoke.
 - A sub-stack of the collars is laminated by the
 2.3mm thick "fixing collar" and the 2.6mm thick
 "spacer collar". Similar with MQXA.
 - Four sub-stacks are connected by lock pins and provide the coil pre-stress below 5 MPa.
 - Emboss of 0.2mm
- Procurement of fine-blanking dies is on-going.
- Radiation resistant GFRP collar at lead end, same design concept as the J-PARC SCFM.



e.g.) GFRP collar to clamp the ramp box and the lead-out on the single layer coil for J-PARC SCFM.


Collaring Press and Mandrel

- Horizontal collaring press in preparation.
 - coil pre-stress below 5MPa.
 - coil deformation controlled by the collaring mandrel.






- Demonstration of collaring mandrel
 - 3D rapid prototyping.
 - Main mandrel can be removed by using "Flat Roller" after yoking.





Yokes


- Low carbon steel: EFE by JFE steel
 - 15 tons of EFE sheets (5.6mm & 6mm thick) delivered for the model magnet.
 - Another 15 tons will be procured within this year.
 - Y.S.: > 240 MPa. Magnetic property: OK.
- Yoke is locked by 3 keys at each side. The coil pre-stress of 90-100 MPa will be given by the yoking.
- Mechanical short model study: Demonstration of mechanical structure
 - Concept of 4-way split collars and pre-alignment feature.
 - Increase of thickness difference (5.6mm & 6.0mm): help for yoke stacks assembly.
 - Coil pre-stress measurement at assembly and cool-down to LN₂ temperature
- For model magnet:
 - KEK placed an order of fine-blanking dies. Yoke stacks will be delivered by Feb. 2015.
 - Holes on the yoke sheet are not finalized and will be machined for the model magnets.





assembly of top and bottom yoke stacks for J-PARC SCFM 12

Presses, Jigs




3.6 m long hydraulic press for coil curing and yoking is ready.


Preparatory Work for Cold Tests

- Modification and procurement of the cryostat for "12 kA, 150 mm aperture" D1 magnet.
 - Old Spec. of 9m-deep vertical cryostat: 7.5kA, 70 mm aperture dedicated for MQXA.
 - New header w/ larger warm bore.
- New 15 kA CLs to be delivered in March 2015
- Upgrade of PC and bus lines. (7.5 kA >> 15 kA).
 - New 15kA-DCCT procured by KEK is being calibrated at CERN.
 - New dump resistor of 75 m Ω with grounding at the middle.
- New DAQ systems



New 15kA bus lines









New 15kA-CLs

New header, cold tube, quench antenna

Deliverables and Near-term Plan

Two 2m long models will be built and tested at KEK.

Up to now, 2m long test coil fabricated. Coil size measurement done.

- Dec. 2014 A short mechanical model
- April 2015 1st 2m long model
 - Field optimization by ROXIE and end spacer design are underway.
 - Coil winding would start at Jan. 2015.
- June 2015 Commissioning of test stand
 - A new header (cryostat flange) for D1. To be inspected by local government.
 - A new pair of 15kA CLs
 - Upgraded 15kA P/C and buses
- Sep. 2015 Cold test of 1st model
- Dec. 2015 2nd 2m long model
- Feb. 2016 Cold test of 2nd model