



# Beam Interlock System SPS CIBU Connection Review

Christophe Martin  
TE/MPE



## Outline:


- CIBU distribution in SPS
- “Conform connection” definition
- Commissioning Tool
- “non-conform connection” in SPS
- Open issues



**Outline:**



- CIBU distribution in SPS
- “Conform connection” definition
- Commissioning Tool
- “non-conform connection” in SPS
- Open issues




Location	Channel	Nb Used	Short Name	Additional info	Groupe
BA1	1	YES	Vacuum LSS1 +TT10		TE-VSC-ICM
BA1	2	YES	MKD		TE-ABT-EC
BA1	3	YES	Q KICKER		TE-ABT-EC
BA1	4	NO	WIC	New Input	TE-MPE-MS
BA1	8	YES	BLM LSS1		BE-BI-BL
BA1	9	YES	Beam Position		BE-BI-SW
BA1	10	YES	BLM Ring		BE-BI-BL
BA2	1	YES	Vacuum LSS2		TE-VSC-ICM
BA2	2	NO	WIC	New Input	TE-MPE-MS
BA2	8	YES	BLM LSS2+TT20+Spl		BE-BI-BL
BA2	9	YES	TBSE TT21		EN-STI-ECE
BA2	10	YES	TED TT20		EN-STI-ECE
BA2	11	YES	Vacuum TT20		TE-VSC-ICM
BA2	12	YES	ZS Electronic system		TE-ABT-EC
BA2	13	YES	ZS Spark		TE-ABT-EC
BA3	1	YES	Vacuum LSS3		TE-VSC-ICM
BA3	2	YES	ACCESS Chain-1		GS-ASE-SSE
BA3	3	YES	Operators Buttons		TE-MPE-EP
BA3	4	YES	MPS Dipoles		TE-EPC-MPC
BA3	5	YES	MPS Quadripoles		TE-EPC-MPC
BA3	6	YES	MPS Sextupoles		TE-EPC-MPC
BA3	7	NO	WIC	New Input	TE-MPE-MS
BA3	8	NO	SPS Eco	New Input	BE-OP-SPS
BA3	9	YES	BCT		BE-BI-SW
BA3	10	YES	RF		BE-RF-FB
BA3	11	YES	Vacuum TT80		TE-VSC-ICM
BA3	12	YES	ROCS interlock		TE-EPC-CCS
BA3	13	NO	WIC Ring Line	New Input	TE-MPE-MS

Location	Channel	Nb Used	Short Name	Additional info	Groupe
BA4	1	YES	Vacuum LSS4		TE-VSC-ICM
BA4	2	NO	WIC	New Input	TE-MPE-MS
BA4	3	YES	MKE4 Status		TE-ABT-EC
BA4	8	YES	BLM LSS4		BE-BI-BL
BA4	9	YES	BCT		BE-BI-SW
BA5	1	YES	Vacuum LSS5		TE-VSC-ICM
BA5	2	NO	WIC	New Input	TE-MPE-MS
BA5	8	YES	Collimators		EN-STI-ECE
BA5	9	YES	BLM LSS5		BE-BI-BL
BA5	10	YES	UA9 Collimators		EN-STI-ECE
BA6	1	YES	Vacuum LSS6		TE-VSC-ICM
BA6	2	NO	WIC	New Input	TE-MPE-MS
BA6	3	YES	MKE6 Status		TE-ABT-EC
BA6	8	YES	BLM LSS6		BE-BI-BL
BA6	9	YES	Turn by turn Interlock		BE-BI-QP

### For the SPS, 43 CIBU in total

- 35 CIBU in operation before LS1
- 8 new CIBU installed during LS1




## Outline:



- CIBU distribution in SPS
- **“Conform connection” definition**
- Commissioning Tool
- “non-conform connection” in SPS
- Open issues





# CIBU User manual

**CERN TE DEPARTMENT**  
CH-1211 Geneva 23  
Switzerland

*CERN Div./Group or Supplier/Contractor Document No*

**TE/MPE/MI**

*EDMS Document No.*

**636589**

Date: 11 JULY 2011

## TECHNICAL NOTE


### USER INTERFACE TO THE BEAM INTERLOCK SYSTEM

#### *Abstract*


This note describes the functionality and the requirements of any User System's connection to the Beam Interlock System via the User Interface; this connection is critical for machine safety and must be implemented in a very specific manner to provide safe and reliable interlocking. The same unit is provided for all of the different applications of the Beam Interlock System; LHC ring, LHC injection, SPS ring and SPS Extraction & Transfer Lines.

➤ EDMS 636589

**The reference document used to qualify a CIBU connection is the CIBU user manual 1V51**




### CIBU redundant signals




Distinct connection ✓ OK

- The redundancy is applied at least at the “Output stage” of the User electronic




### CIBU redundant signals




Serial connection      **NON-CONFORM !**







### CIBU redundant signals



Parallel connection    **NON-CONFORM !**




### CIBU Switches position




Wrong switches position    **NON-CONFORM !**

- This schematic was the recommended implementation in the CIBU user manual 1V4 up to 2009 !!!
- Following the presentation “CIBU Connection Review” of Benjamin Todd of December 2008, this schematic has been reported as “non-conform”



### User output impedance




Serial resistor


**NON-CONFORM !**

- In the CIBU user manual 1V4 up to 2009 a misinterpretation can lead the users to provide a current into the CIBU.


The current loop is inside the CIBU, the user has to provide a voltage !



# CONNECTION DETAILS BETWEEN THE USER SYSTEMS AND THE CIBU



- If wire "1" and "2" are not connected, the cabling is not conform (No return path for the CIBU voltage suppressor in case of over voltage)



## EMC COMPLIANCE INTERCONNECTION





Figure 11: Principle of Interconnection for Complete EMC Compliance

- The shielding must be present on the connection cable (visual control)

*Reminder: The interconnection cable between the User electronics and the CIBU is under the responsibility of the user!*






## Outline:

- CIBU distribution in SPS
- “Conform connection” definition
- **Commissioning Tool**
- “non-conform connection” in SPS
- Open issues






BIS Handheld tester


# NEW CIBU COMMISSIONING TOOL

## Main features:

- Checks the voltage applied on both user permit (A+, A- & B+, B-)
- Checks the User Output impedance (A & B)
- Checks the current drawn by the CIBU (A & B)
- Checks the redundancy of user permit A & B (serial connections are detected)
- Checks the ground connection (pin 1 & 2)
- Automatically generates an Excel report (Bluetooth connection with a windows PC)



NI CVI remote application on Windows PC



# COMMISSIONING TEST SEQUENCE

**CERN TE DEPARTMENT**  
CH-1211 Geneva 23  
Switzerland

<small>Document No.</small> <b>TE-MPE-EP-Note 1v0</b>
<small>CERN Div./Group or Supplier/Contractor Document No.</small> <b>TE/MPE/EP</b>
<small>EDMS Document No.</small> <b>1400288</b>

➤ [EDMS 1400288](#)

Date: 2014-07-21


## TECHNICAL NOTE

### **CIBU COMMISSIONING STEPS WITH THE USER SYSTEM ELECTRONIC**

#### *Abstract*

This note describes the different commissioning steps required to validate the connection between the User System and the Beam Interlock System (BIS) through the User Interface (CIBU); this connection is critical for both machine safety and machine operation. Therefore, the commissioning test must be executed in a specific way to provide a safe and reliable interlocking.


- In order to efficiently realise the commissioning test, the owner of the system can find in this document all details related to the test sequence.




## Outline:

- CIBU distribution in SPS
- “Conform connection” definition
- Commissioning Tool
- **“non-conform connection” in SPS**
- Open issues






### SPS CIBU CONNECTION STATUS




As found in June



After User improvement

- Conform
- Non-conform
- Not tested






## SPS NON-CONFORMITY DETAILS

Systems	Number of CIBU	Resistor in series	Seial connection	Parallel connection	Switch on GND	No GND	GND On CIBU connector
BLM	6	X		X		X	
BCT	2				X		
RF	1				X		
Collimators	3				X		
Turn by turn	1				X		
MKD	1		X			X	
MKE6	1		X			X	
Q Kicker	1		X			X	
MKE4	1		X				
SPS operator switches	1					X	
WIC	7					X	
Beam Position	1			X		X	
Vacuum	8			X		X	

**Total non-conformity 34**

As found in June




## SPS NON-CONFORMITY DETAILS


Systems	Number of CIBU	Resistor in series	Seial connection	Parallel connection	Switch on GND	No GND	GND On CIBU connector
BLM	6	X		X		X	
BCT	2				X		
RF	1				X		
Collimators	3				OK		
Turn by turn	1				X		
MKD	1		X			X	
MKE6	1		X			X	
Q Kicker	1		X			X	
MKE4	1		X				
SPS operator switches	1					OK	
WIC	7					OK	X
Beam Position	1			X		X	
Vacuum	8			X		OK	


Total non-conformity **30**

After User improvement



# GND ON CIBU CONNECTOR






## NOT TESTED CIBU IN THE SPS

Currently, the following systems have been not yet tested:

Location	Short Name	Group
BA3	ACCESS Chain-1	GS-ASE-AC
BA2	ZS Spark	TE-ABT-EC
BA3	ROCS interlock	TE-EPC-CCS
BA3	MPS Dipoles	
BA3	MPS Quadripoles	TE-EPC-MPC
BA3	MPS Sextupoles	

**Not tested CIBU: 6**

*Note: the test of the CIBU "ACCESS Chain 1" is foreseen on the 27/09 during the DSO tests*




## Outline:

- CIBU distribution in SPS
- “Conform connection” definition
- Commissioning Tool
- “non-conform connection” in SPS
- Open issues









- Many connections in the SPS are reported as “non-conform”.  
What will we do with these connections ???
  
- We needed more or less 2 months for testing 34 CIBU in the SPS
  - LHC => 152 CIBU
  - Extraction => 108 CIBU
  - Injection => 37 CIBU

Total => 297 CIBU !!!

We can assume that a lot of time will be required if we have to re-test all these CIBU



Thanks for your attention




# Spare slides

# BLM DETAIL CONNECTION

Maintenance châssis 2013/2014

DECEMBRE 2013



New Power supply  
+5V → OK  
(New cabling)

New Power supply  
+12V → OK (V1)  
-12V → OK (V2)

New Power supply  
+15V → OK (V1)  
-15V → OK (V2)

Nouvelle dim.  
SIN 324908433  
U<sub>net</sub> = 864V  
(+8%)

Aucun câble raccordé dessus

DUMP BIC

BA4  
BLRING DUMP  
CABLAGE CHASSIS

BLR41S-RA314-

SPS 3580-00

14 60424 01/09

7<sup>th</sup> August 2008

No Beam In the Machine

Final Commissioning Vacuum System to Beam Interlock System


1. Vacuum Valves moved IN around IR3
2. Vacuum UJ33 USER\_PERMIT\_A stayed TRUE
3. Vacuum UJ33 USER\_PERMIT\_B stayed TRUE
4. BIC Test Mode showed ALL OK


Commissioning Fail



## AS TESTED (Vacuum mid-July)

1. All ground / earth / 0V connected
2. Spare wires grounded
3. Shield 360° at both ends
4. No pig-tails
5. More than 5m is forbidden
6. Cable correct type:
  - a. Twisted Pair NE8/NF8






**WHEN CONNECTED  
CIBU ALWAYS TRUE  
(next slides)**


## Presumed Failure


### 1. Excessive Voltage

Is applied in the Access System PLC rack, due to erroneous cabling



2. This subjects the CIBU negative current loop to an excessive voltage (48V)







3. The Transient Voltage Suppressor (SM6T30CA) Clamps the voltage and dissipates the energy



4. Experiments show that after 1-2 seconds the TVS will fail, this TVS fails open-circuit  
The 'A' loop TVS now absorbs the excess




5. 1-2 seconds later this TVS fails short-circuit




6. The fault is discovered in the ACCESS system  
and is removed

But the TVS is so badly damaged it fuses to ground



7. At this point both USER PERMIT A and B are stuck TRUE as current flows to ground through A (green) and B (blue) using the damaged TVS



## Several events = complete Blind Failure

1. Two Equipment systems sharing the same channel
2. PLC Voltage against rules
3. TVS Blocked Short-Circuit
4. Inputs were not redundant
5. Not re-commissioned by MI after a significant change

## In addition...

- a) Cable length against rules
- b) EMC would have been a show-stopper anyway!