

# Long Shutdown (LS1) in the LHC

G. Schneider

# Contents

- ❑ **Motivation for the interventions**
- ❑ **Instruments concerned**
- ❑ **Lessons learned**

# Motivation for Interventions

- ❑ **Repair of damaged components**
- ❑ **Service instrument park**
- ❑ **Increase performance**
- ❑ **Temporary removal or displacement of instruments (SMACC, Bakeout, ....)**



# Instruments concerned

- BTV**
- BPM**
- BRAN**
- BGI**
- BGV**
- BSRT**
- Wire Scanner**
- Schottky**
- BLM**
- BCT**

# BTV:

Set-up instrument to measure the beam profile

- ❑ 4x BTVSI and 2x BTVST NEG coated
- ❑ 2x BTVSE, 2x BTVSS RF-contact repair
- ❑ BTVST: Change Titanium to Aluminium Screen



# BTV:

- ❑ **Work for NEG coating:**
  - ❑ Design and manufacture NEG- coating tooling
  - ❑ Manufacture and NEG-coat inserts and vacuum chamber (BTVST only)
- ❑ **Work for RF-contact repair:**
  - ❑ Identify origin or the problem: Excess copper in the vacuum chamber
  - ❑ Remove copper
  - ❑ Manufacture of new inserts
  - ❑ Establish test procedure before and after vacuum acceptance test
- ❑ **Work for BTVST Aluminium Screen**
  - ❑ Design and make assembly tool
- ❑ **Common:**
  - ❑ Remove from tunnel, dis-assemble, re-assemble, test, re-installation, camera re-installation
  - ❑ New optical line with dual camera system design finished, hardware ready to be installed
- ❑ **BTVDD upgrade :**
  - ❑ New optical line with dual camera system design finished, hardware ready to be installed
- ❑ **Camera exchange due to lower dose rates:**
  - ❑ System camera RAD exchange with CCD ones for 2x BTVSS and 4x BTVSI




# BTV:


Set-up instrument to measure the beam profile

## □ After re-assembly

BTVSE after vacuum acceptance and 50 movement tests



BTVST with NEG coating



BTVST re-installed in the tunnel






# BRAN:

Beam Rate Neutral Particles, Luminosity measurement on either side of collision points = 8 total

- ❑ **Remove and re-install instruments for bakeout**
- ❑ **New BRAN C in Point 8 for higher radiation resistance**
- ❑ **New installation tooling and procedure**
- ❑ **Pressure tests of installation**






# BWS: Wire Scanners

Instrument to measure the beam profile


2 for each horizontal and vertical for each beam = 8 total

- ❑ **Leaks on bellows (more than 10000 cycles)**
- ❑ **Wire refurbishment**



# BWS: Wire Scanners



- ❑ Scanner (LEP-design) 'reverse engineered' in existing space to allow integration of a bellows rated for 40'000 cycles
- ❑ Complex drive mechanism is non-linear and with friction – long analysis and experiments were required to understand and simulate movement → new type of spring for compensation
- ❑ Challenging material supply and assembly: Leaks created during final EB weld assembly



# BGI:

Instrument to measure the beam profile using beam – rest gas ionization.



1 horizontal and 1 vertical in each beam line = 4 total





# BGI:

- ❑ **Leak tightness: Surface roughness and profile defined; Seal type changed and grooves in spacer added**
- ❑ **Leaks opened after bakeout. Why?**
- ❑ **Instrument refurbishment:**
  - ❑ **Exchange of MCP (Multi Channel Plate) and Phosphor Screen**
  - ❑ **Cameras more radiation hard**
  - ❑ **Installation of thermometers in vacuum**








# BGV:

Beam profile measurement; Inspired by VELO detector in LHCb

- ❑ **One new demonstration instrument**
  - ❑ **Vacuum Chamber**
  - ❑ **Detectors (outside the vacuum system)**
  - ❑ **Cabling**
  - ❑ **Data analyses**








# BPM:

Beam Position Monitor


Total 1145 Monitors installed in the machine

- ❑ **Engineering Change Requests (ECR) to move, add and change BPMs**
- ❑ **BPM cables to be removed for each bakeout**



# BPM:

- ❑ **Modification of Interlock BPMs in IR6 and displacement to make room for TCDQ upgrade**
- ❑ **Installation of new combined BPMWK in TAS->Q1 regions of IP1 & IP5 to optimize mechanical tolerances (vacuum)**
- ❑ **Installation of one BPM per BGI to allow precise BGI calibration with beam**
- ❑ **Re-Alignment of BPMWB close to D2 before Recombination Areas at Points 1 and 5**
- ❑ **New BPLX for Gated Tune measurement**
- ❑ **Replacement of BPMWE for new passive absorbers (TCAPC) in LSS3**
- ❑ **TOTEM Roman Pots stations displaced in IR5**
- ❑ **ATLAS Roman Pots BPM Modification in IR1**
- ❑ **BPMD position measurement added**
- ❑ **NEG coated BPTX in 5L2 & 5R8**
- ❑ **Arc BPM: DN100 re-clamped - O-ring seals exchanged - 4 SSS replaced - BPMC cryo cables removed for Interconnect work.**
- ❑ **18 Collimators with embedded BPMs in all IRs for improved positioning (TCTP & TCSP)**




Courtesy: C. Boccard



# BSRT:

Synchrotron Radiation Telescope to measure the beam profile



- ❑ Instrument overheated due to RF-coupling in Run1
- ❑ New design proposed, made and tested
- ❑ New mirror now made with fused silica instead of silicon
- ❑ Optical table refurbishment
  - ❑ focusing lenses in the near UltraViolet (UV,  $\sim 250\text{nm}$ ) for imaging @ 6.5-7TeV minimizing diffraction
  - ❑ minor changes in optical filters layout and control
  - ❑ New interferometer line, for alternative (to imaging) beam size measurements, in principle diffraction-free (ongoing)



# BSRTR:

New calibration instrument for BSRT-system, replaces BSRTA

- ❑ **Motivation: free about 30% space on the optical table**
- ❑ **Alignment and calibration done via the same optical line. Laser/target light sent into the beam pipe via BSRTR.**
- ❑ **Based on BTVSI-design**








# Schottky (BQS):

Incoherent tune and chromaticity measurement instrument  
 1 for each horizontal and vertical for each beam = 4 total

- ❑ Aluminium wave guide changed to copper
- ❑ Slots optimised
- ❑ Performance measured
- ❑ Front end electronics overhaul



# Beam Loss Monitor (BLM):

Outside beam vacuum


- ❑ **Remove and reinstall BLMs in order to have access to the interconnects**
  - ❑ **all BLMs in ARCS (total ~2500 of which 816 were re-located)**
  - ❑ **about 70% of LSS BLMs (total ~1000)**





## Beam Loss Monitor (BLM):


- ❑ **Exchange 40 multiwire cables with the NES18 type**
  - ❑ Reduce noise on 240 detectors
- ❑ **Exchange 360 acquisition crate backplanes (ARC)**
  - ❑ Under ARC quadrupole
  - ❑ Better defined feedback voltage to improve reset and test function of electronic cards
- ❑ **Modify 309 signal distribution boxes and add high voltage divider boxes (LSS)**
  - ❑ Better defined feedback voltage to improve reset and test function of electronic cards
- ❑ **Installation/Connection to WorldFIP**
  - ❑ Allow remote access and re-set per card



Improved backplane

# Beam Loss Monitor (BLM):

- ❑ **Modifications in the tunnel acquisition electronics**
- ❑ **Modifications in the surface installation**
  - ❑ Racks now with water cooling
  - ❑ Removal and re-installation of crates, cables....
- ❑ **Preventive maintenance of the Treshold Comparator electronics**
  - ❑ Cleaning and re-testing of the cards
- ❑ **Modification of the BLECS and BLETC firmware**




*Courtesy: Ch. Zamantzas; E. Effinger*

# BCTDC:

Integrated Beam Current Transformer  
2 per beam

- **Addition of magnetic cores in order to reduce the interferences in the RF-range**




# BCTF:

Fast Beam Current Transformer

Motivation: Reduce bunch length and bunch position dependency

- **Two new types (BCTI and BCTW) were developed**  
BCTI already installed, BCTW foreseen to be installed before end 2014

## BCTI





# Lessons Learned

- ❑ **Definition in advance what to do saves time, nerves and resources**
  - ❑ Designer availability
  - ❑ Orders are more relaxed
  - ❑ Workshop has more time to prepare
  
- ❑ **Document the work done and make information available**