

TOTEM & CT-PPS

Consolidation and upgrade strategy

Review activities during LS1 (CERN activities)

Schedule for 2015

Summary

Roman Pot consolidation & upgrade strategy

CONSOLIDATION -> LS1

- Remove RP147 m stations & patch panel (allows installation of TCL4)
- Relocation of RP147 m stations (including Si strip detectors) in +/- 210 m region
- Exchange of ferrites of all RPs, Integration of ferrite support spring

Consolidation
RP147&RP220
-> during LS1

UPGRADE - Roman Pot station -> LS1

- Installation of additional **new** RP stations (horizontal) in +/-220 m region (1 RP stations in each sector (4/5), (5/6))
- Integration of RF optimized horizontal Roman Pots in relocated horizontal stations in +/- 210 m region

Upgrade
Roman Pot station
-> during LS1 or
In end of year technical
stops after LS1
(break of vacuum)

UPGRADE – new movable beam pipe devices -> after LS1

- Development of new movable beam pipe devices

Upgrade
movable beam pipe
devices
-> after LS1
(break of vacuum)

UPGRADE detector -> after LS1





- Integration of **new** pixel detectors in the (relocated RP147m) RPs in 210 m region
- Integration of **new** timing detectors in the **new** horizontal RPs

Upgrade
Roman Pot detector
-> during LS1 or
in short technical stops
after LS1

ROMAN POT: Milestones during LS1

L
H
C
C

March 2013



June 2013
consolidation
& upgrade

January 2014
CMS-TOTEM
MoU

September 2014
TOTEM timing TDR
CT-PPS TDR

November 2014


March 2015
Restart LHC
Run 2



LHC LS1 access for RP installation





August 2014



ECRs related to consolidation & upgrade @LHC ip5

Roman Pot consolidation & upgrade overview (schematic)



EDMS NO.	REV.	VALIDITY
1314925	1.0	RELEASED

EDMS NO.	REV.	VALIDITY
1283826	1.0	RELEASED

LHC

ENGINEERING CHANGE REQUEST

Installation and Renaming of Absorbers for Physics Debris (TCL type collimators) on both sides of IP1 and IP5 in front of D2/Q4

BRIEF DESCRIPTION OF THE PROPOSED CHANGE(S):

It is proposed to install TCL4 (TCL type) collimators in the forward regions of IR1 and IR5, in front of D2/Q4 cryostats. These collimators were built as part of the present LHC collimation system and their installation was delayed to allow the operation of the "close" TOTEM Roman pot stations in IR5.

EDMS NO.	REV.	VALIDITY
1357736	0.1	DRAFT

LHC

ENGINEERING CHANGE REQUEST

Installation of Physics Debris Absorbers (TCL) on both sides of IP1 and IP5 in front of the Q6 Quadrupole

BRIEF DESCRIPTION OF THE PROPOSED CHANGE(S):

It is proposed to install TCL, physics-debris collimators, on both sides of IP1 and IP5 in front of the Q6 Quadrupole (TCL6). This request follows the ECR EDMS Doc. 1283867 where the preparation of the TCL6 infrastructure was proposed and approved. This proposal to install the TCL6 is now brought forward taking into account the latest information on collimator production schedule and results of simulations that were deemed necessary before taking the final decision.

TOTEM

CMS-TOTEM

ENGINEERING CHANGE REQUEST

TOTEM Consolidation Project

BRIEF DESCRIPTION OF THE PROPOSED CHANGE(S):

The TOTEM Roman Pot (RP) stations that were installed on the outgoing beam at a distance of 147m on both sides of IP5 have been de-installed. TOTEM proposes to move these stations to 210 m (between Q5 and Q6) on both sides of IP5, so that after LS1 the TOTEM setup will contain a new 210 m station with a near and far unit in addition to the existing 220m station. The new 210 m far unit will be rotated by 8° around the axis of the beam. To foresee the later addition of timing detector units, TOTEM proposes to add one piece of dummy beam pipe between the existing near and far units of the 220m station.

EDMS NO.	REV.	VALIDITY
1361537	0.1	DRAFT

ENGINEERING CHANGE REQUEST

TOTEM Upgrade Project

BRIEF DESCRIPTION OF THE PROPOSED CHANGE(S):

The TOTEM Upgrade Proposal [1] foresees the installation of additional horizontal Roman Pots (RPs) between the existing RP units at 215 and 220 m from IP5. These new RPs, intended to house time-of-flight detectors for elastically or diffractively scattered protons, have been designed in cylindrical geometry minimising the beam impedance and offering enough space for 12 cm long Cerenkov detectors, one of the technologies being explored for the time measurement.



Furthermore, the existing horizontal RPs of the units at 203 and 213 m will be equipped with Faraday shields to reduce their impedance.

This ECR elaborates on the technical details of the new RP elements and their integration in the LHC. It thus complements the already approved consolidation ECR [2].


UPDATE ON
rd Physics and Detectors

RP installation at IP5 (before LS1)

TOTEM RP-147m (near-far)






TOTEM RP-220m (near-far)



CMS ip5
~ 147 m
←

CMS ip5
~ 220 m
←


Roman Pot installation in LHC tunnel completed (consolidation) during LS1



November 2014

R&D of new ROMAN POT (2013-2014)


RF test of new Roman Pot design with thin window of 300 μm
 combination of new bellow & beam pipe & circular ferrite with new cylindrical RP or RF shield





New bellow & beam pipe with circular ferrites & ferrite support ring → integrated in horizontal RP test station

Horizontal RP test station


Movement of horizontal RP in steps of 100 μm




Measurements with and without ferrites
 Results show good agreement with simulation





New cylindrical Roman Pot & RF shield for box Roman Pot




New design
 Cylindrical or RF shield




Old box design
 without RF shield





New timing and tracking detectors to be installed in Roman Pots 2015 & 2016 (CTP-PPS)




Cylindrical RP and timing detector



Possible to integrate Cerenkov timing detector or other type of timing detector










RP with RF shield and tracking detector



12/17/2014

Building & testing & installation & calibration of new Roman Pot




J. BAECHLER
LHC Forward
15-17 December 2011, Cracow, Poland

TOTEM

Physics program - R&D and detectors

LHC
 $\beta^* = 90\text{m}$




Physics program


R&D timing detectors
 50 ps

Precision clock
 distribution

Timing detector
 to be integrated
 in vertical Roman Pots
 +/- 220 m region of ip5
 (2015-2018)



CT-PPS project



LHC standard optics

- Physics program
- Timing detector baseline (Cerenkov) and R&D 10 ps
- Rad. Hard pixel
- New Roman Pot & movable beampipe

Tracking detector integrated in standard Roman Pots with RF shield
 Timing detector to be integrated in new cylindrical horizontal Roman Pots +/- 220m ip5 (2015-2018 + x)








Figure 110: CT-PPS organizational chart.

Commissioning of cylindrical RP (timing) at LHC

Integration of flange equipped with temperature sensors
RadMon and heat exchanger



2. Setup for first Runs



R&D Timing detector

- In 2014 several test beams at CERN and PSI were used to:
 - test & develop solid state detectors in combination with amplifier
 - perform measurements with Scope and SAMPIC
- Timing detector infrastructure

2015 Q1/Q2

FIRST BEAM
9th MARCH

	Jan			Feb				Mar					
Wk	1	2	3	4	5	6	7	8	9	10	11	12	13
Mo	29	5	12	19	26	2	9	16	23	2	9	16	23
Tu													
We				HW tests									
Th												Recommissioning with beam	
Fr													
Sa													
Su						Sector test (S23)		Sector test (S78)					

	Apr				May				June				
Wk	14	15	16	17	18	19	20	21	22	23	24	25	26
Mo	30	6	13	20	27	4	11	18	25	1	8	15	22
Tu													
We									TS1				
Th		Recommissioning with beam									Intensity ramp-up with 50 ns beam		
Fr													
Sa													
Su													

SCRUBBING FOR 50 ns

SCRUBBING FOR 25 ns

2015 Q3/Q4

	July			Aug					Sep					
Wk	27	28	29	30	31	32	33	34	35	36	37	38	39	
Mo	29	6	13	20	27	3	10	17	24	Special physics run	31	7	14	21
Tu														
We	1	MD 1		Intensity ramp-up with 25 ns beam					TS2			MD 2		
Th														
Fr														
Sa														
Su												lower beta*		

	Oct			Nov					Dec				
Wk	40	41	42	43	44	45	46	47	48	49	50	51	52
Mo	28	5	12	19	26	2	9	16	23	30	7	14	21
Tu			Floating MD					Ions setup				Technical stop	
We							TS3						
Th										IONS			
Fr					MD 3								Xmas
Sa													
Su													

End physics [06:00] ↓

Summary

- The consolidation program was completed during LS1
- All goals as outlined in the upgrade proposal were achieved during LS1
- MoU of the CT-PPS project was signed by CERN – CMS – TOTEM management
- 2 TDRs were presented in LHCC – September 2014 (TOTEM, CT-PPS)
- R&D on timing detectors has started