

## Background

- The main function of the cold circulator (CC) is to establish and maintain forced-flow supercritical helium (SHe) flow at flow-path of the toroidal field (TF) superconducting magnet of ITER.
- The major challenging tasks of CC are to operate at vigorous operating regime of superconducting magnet having an isentropic efficiency of 70 %. Two cold circulators for TF superconducting magnet have been designed, manufactured by industrial partners in order to perform the qualification test of cold circulator prior to the final design of ITER cryo-distribution system.
- Interface management has been identified as the high-risk area for the project involving three industrial partners; M/s. IHI Corporation, Japan for Cold Circulator-1 (CC-1), M/s. Barber-Nichols Inc., USA for Cold Circulator-2 (CC-2) and M/s. Taiyo-Nippon Sanso Corporation, Japan for TACB as well as the cryogenic test facility at JAEA-Naka, Japan.

## Design Interfaces of Cold Circulators

The methodology of interface management and control has been implemented by (i) identifying all the interface points, (ii) defining design responsibilities of the interface points, (iii) updating the counter-interface design suiting the original interface and (iv) verifying the integrated system by suitable analysis, which reduces the design iterations.

### List of Interfaces of cold circulator


#### Interfaces

##### Physical Interfaces

- Interface Point
  - SHe suction and discharge nozzles,
  - 80 K thermalization
  - Mounting plate/flange of the cold casing
  - Shield for magnetic field (as applicable)
  - Interface with utilities (cooling water nozzles, electrical power)
  - I&C signal interface PLC of TACB and cold circulators
  - Logical interfaces between the cold circulator and TACB
  - Cable tray
  - Cabinet interface at the cryogenic test facility
  - Functional interface must satisfy all the operating conditions during the qualification test.


##### Instrumentation and control Interfaces (I&C)

##### Functional interfaces at facility



Schematic diagram of CC with interfaces


## Thermo-mechanical Analysis



### Interface loads for cold circulators

Description	Unit	Nozzle Loading on CC-1		Nozzle Loading on CC-2	
		Inlet	Outlet	Inlet	Outlet
Forces-X direction	[N]	-196.75	-377.53	-116.67	-28.99
Forces-Y direction	[N]	202.79	325.9	289.21	61.52
Forces-Z direction	[N]	189	-7	-385	153
Moment-X direction	[Nm]	316.12	315.68	357.8	57.98
Moment-Y direction	[Nm]	204.45	361.23	231.93	29.7
Moment-Z direction	[Nm]	73	4	47	-5



### Pressure Test Condition




## Installation Methodology

- Roundness measurement of casing before all welding
- Welding of other internal piping near CC-1
- Positioning of elbow at final welding point for smallest piping stress
- Welding of Cold circulator with its inlet and outlet straight pipe & elbow
- Mounting a casing with top plate
- Roundness measurement of casing before final welding
- Roundness measurement of casing
- Thermal shield of CC-1 has been cut appropriately
- Pressure test, Leakage test
- Mounting of motor cartridge
- Pressure test, Leakage test
- It was found that thermal shield has clashed with TACB thermal shield
- Displacement measurement of connecting point during pressure test
- Roundness measurement of casing
- Mounting of thermal shield (CC-1 only)
- Interference checking with TACB (mock up of installation on the TACB flange)
- Roundness measurement of casing before welding
- Final welding of CC vacuum flange to top plate of TACB


### Control Methodology



## Functional Interface




- Stable operation during the qualification test for CC has been ensured by analysing the functional interface with the cryogenic test facility at JAEA-Naka facility with capacity as ~ 5.0 kW@4.5K or 800 l/h.
- Functional interfaces evaluated for (i) Nominal, (ii) Maximum mass flow at 110 % speed, (iii) Maximum pressure head at 110 % speed, (iv) Different speeds at 80 %, 60% and 20%, (v) Cold Circulator inlet at 10 Bar, (vi) Cold Circulator inlet at 6 K and (vii) cold circulator OFF.



## Acknowledgement

Authors would like to thank the colleagues from ITER-India, ITER Organization in France for their contribution to ITER Cold circulator and TACB project with specific gratitude to the Project Director, ITER-India and Director, IPR. Special thank is extended to the Industrial partners namely M/s Barber Nichols Inc. (USA), M/s IHI (Japan), M/s Taiyo Nippon Sanso (Japan)

## Realization



- Manufacturing of TACB is near completion and will be ready for Japanese regulatory inspection for the completer system including both cold circulators

## Factory Acceptance Test

- Factory acceptance test (FAT) of cold circulators from both suppliers has been completed successfully.
- Verification of all the interfaces has been performed satisfactorily. The test results are summarized in Table below, which have been performed under no-load condition.

Summary of FAT results		
	CC-1	CC-2
Speed at Design Point (rpm)	12000	8000
Mock-up Cartridge Replacement time (mm:ss)	60:00	55:35
Electrical input power to motor at 100% speed (kW)	0.33	2.1
Electrical input power to motor at 110% speed (kW)	0.43	2.2
Vibration Upper bearing at 100% speed (Resultant)	1.0 µm	1.36 mm/s
Vibration Lower bearing at 100% speed (Resultant)	1.0 µm	0.77 mm/s
Vibration Upper bearing at 110% speed (Resultant)	1.0 µm	1.19 mm/s
Vibration Lower bearing at 110% speed (Resultant)	1.0 µm	0.54 mm/s
Acoustic Noise at 1 m distance, 100% speed (dB)	62.5	64.2
Acoustic Noise at 1 m distance, 110% speed (dB)	62.5	65.6

## Conclusion

- Designs of two cold circulators along with TACB have been completed with supporting analysis.
- Integrated analysis has been performed in order to obtain a safe interfacing design condition for physical interfacing points.
- Results show that stresses and deflections are within the allowable limit as per the selected material and construction codes and standards.
- Functional interface has been evaluated considering all modes of operation for the cold circulators suitable to the cryogenic test facility.
- Factory acceptance tests for both the cold circulators have been successfully completed and ready for the final qualification test.

## References

- R. Bhattacharya, B. Sarkar, H. Vaghela, P. Patel, Srinivasa M., H.-S. Chang, T. Isono, Katsumi Kawano, Minoru Sato, M. Chalifour, "Control methodology and test modes during the qualification test of ITER Cold Circulator", in press Physics Procedia (2014)
- Chang H.-S., Monneret E., Forgeas A., Maekawa R., Bonneton M., Fauve E., Chalifour M., Serio L., Park D.-S., Joo J.-J., Moon K.-M., Park Y.-M., "Design Specification of the ITER Cryodistribution Cold Rotating Machines", Proceedings of IEEE 24-ICMC 2012, pp: 599-602
- K. Hamada et al., "Final Design of a Cryogenic System for the ITER CS Model Coil", Cryogenics Vol 34, 1994, 65 – 68
- Sarkar B. et al., "Adaptability of Optimization Concept in the Context of Cryogenic Distribution for Superconducting Magnets of Fusion Machine", Advances in Cryogenic Engineering 57, 1951- 1958 (2012)
- H. Vaghela, B. Sarkar, R. Bhattacharya, H. Kapoor, M. Chalifour, H.-S. Chang, L. Serio, "Performance Evaluation Approach for the Supercritical Helium Cold Circulators of ITER", Advances in Cryogenic Engineering, AIP Conf. Proc. 1573, 872-879 (2014); doi: 10.1063/1.4860795