
The CERN Neutrino Platform

20th October2014

Marzio Nessi, CERN & University of Geneva

CERN Neutrino Platform



PHYSICS (Short and Long Baselines)

Projects presently under consideration

- WA104 ICARUS detector overhauling
- WA105 construction and test of 2 large prototypes/demonstrators
- WA104 NESSiE R&D and test of a new generation of muon spectrometers
- Baby MIND : demonstrator and test of a new muon tracking detector (LBNO, ND-HKK?)
- LBNF test of a TPC module
- ArgonCube : prototypes of a new generation of highly modular TPCs
- HKK : R&D and test of detector components (EU)
- Construction and test of a new magnetized TPC (future ND ?)
- Generic cryogenics support to various detectors (new cryo group at CERN)
- Participation in the design and construction of LAR1-ND cryostat and cryo plant


A few examples !!

WA104 : ICARUS detector overhauling

ICARUS Collaboration with INFN and CERN help

- Move the detector from the GS Laboratory to CERN (2014)
- Prepare at CERN all the necessary infrastructure (clean rooms, cryogenics, ...)
- Reshape the detector with new components
- Construct a new generation of cryostats
- Reshape, maintain and modernize the cryo plant
- Reassemble the 2 T300 detectors inside their cryostats
- Construct a new outer vessel
- Make it ready for shipment to FNAL

ICARUS Detector at Gran Sasso being dismantled and moved to CERN



From 19 September




ICARUS Detector at Gran Sasso being dismantled and moved to CERN




Ready to start




ICARUS detector overhauling









To be constructed : two cold vessels with these dimensions





Fig. 1 : Vertical cross section, in a transversal plane. Internal and external dimensions.



SBL at the FNAL ~ 0.8 GeV v Booster Beam

LAr1-ND

		Total	Active
	LAr1-ND	180t	82t
	MicroBooNE	170t	89t
MINOS	T600	760t	476t
NOVA		TT Cart	
MiniBooNE	A LANGER AND		
MicroBooN			
			123/ 12
		s M	2/12 1
A States H	NUM		Alex 1
	Line	State A	11 Pal
	110m - Near Detector		
SciBooNE	LAr1-ND	Pres	and the second
BNB Target			
		MINDS NOVA NOVA SCIBOONS MINIBORNE TOOM - FAR D.C. CO COM - FAR D.C. CO CO COM - FAR D.C. CO CO CO CO CO CO CO CO CO CO CO CO CO C	LATI-ND 180 MINDS 100 NOVA 600r - Far De totor Carlus / too MiniBooNE MicroBooNE MicroBooNE MicroBooNE MicroBooNE

Mass

A


WA105 : LAGUNA detector Demonstrator

LAGUNA Collaboration with CERN help

- Prepare at CERN all the necessary infrastructure (clean rooms, cryogenics, ...)
- Construct a new generation of cryostats based on membrane technology
- Provide all the necessary cryogenics
- Construct and test 2 prototypes of a 2-phases LAr TPC
 - $-3x1x1m^{3}$
 - $-6x6x6m^{3}$
- Charged beam tests at the SPS with full readout capabilities

The WA105 - LBNO-Demo Detector

Liquid argon density	T/m^3	1.38
Liquid argon volume height	m	7.6
Active liquid argon height	m	5.99
Hydrostatic pressure at the bottom	bar	1.03
Inner vessel size (WxLxH)	m ³	$8.3 \times 8.3 \times 8.1$
Inner vessel base surface	m^2	67.6
Total liquid argon volume	m ³	509.6
Total liquid argon mass	t	705
Active LAr area	m^2	36
Charge readout module $(0.5 \text{ x} 0.5 \text{ m}^2)$		36
N of signal feedthrough		12
N of readout channels		7680
N of PMT		36



External dimensions: 12.5(w)Å~12.5(l)Å~11.2(h) m

The WA105 - LBNO-Demo Detector

Courtesy :WA105 collab. CERN-SPSC-2014-





FIG. 13: Plan view section of the $6 \times 6 \times 6m^3$.

FIG. 14: Vertical cross section of the $6 \times 6 \times 6m^3$.

First membrane cryostat under construction (ready in spring 2015, 17 m³ LAr)



The outer structure


Overview


Steel profiles (IPE240) bolted and welded together

Internal dimensions (now confirmed): 6'812mm x 4'412mm x 4'002mm (L x W x H)

Weight:

12T (confirmed)






Transportation

Divided in 18 pieces: Weight: 1 – 1.5 T each Sizes: 4.5m x 2.5m


Standard trucks: Probably two 10T each 2m height each



WA104 : Magnetized Muon Spectrometer

NESSIE Collaboration with CERN help


- Prepare at CERN all the necessary infrastructure (space, logistics)
- *R&D* on a warm air core magnet
- *R&D* on a cold air core magnet
- Construct and test prototypes of a possible muon spectrometer
- Charged beam tests at the SPS with full readout capabilities



LBNF : Test of a large TPC module

LBNF Collaboration with CERN help


- Prepare at CERN all the necessary infrastructure (space, logistics)
- Prepare a large cryostat for receiving this detector (new cap)
- Bring to CERN components assembled in the UK and USA
- Prepare/adapt the necessary cryogenics
- Charged beam tests at the SPS with full readout capabilities



CERN support groups

- ✓ a detector mechanical engineering team (3 eng. already involved)
- ✓ a new Lar cryo group : 3 staff engineers + 3 Project associates eng. in rotation. The support of the CERN cryolab infrastructure (cryo tecs and frames contracts)
- ✓ a team of technicians
- ✓ an electrical engineer
- ✓ a controls group
- ✓ a (Si)PM characterization lab
- \checkmark a simulation group for beam issues
- ✓ safety and environment experts
- secondary beam experts (from CNGS + new people)
- ✓ access to many CERN technology groups (EL, power, CV, material,)
- a new physics team

EHN1 extension as a new test area



CERN Prototype Meeting – M.Nessi N.Lopez, M.Manfredi (GS-SE)

The Experimental Hall North 1 - EHN1



Technical Aspect: Location




The EHN1 is a large industrial building situated on french territory, in Prévessin. The building has to be extended for the new generation of experiments on the neutrinos.

The Extension will extend northwards from the building for about 70 m in the direction of the beams.



CERN Prototype Meeting – M.Nessi N.Lopez, M.Manfredi (GS-SE)

Technical Aspect: General info



The Extension's dimensions are 72 m long by 50 m wide and 20 m high.


The extension includes two large pits of 7.35m and 9.0m deep.

The top metallic structure is similar to the existing building, allowing for an easy continuation of the overhead crane and services.

The technical gallery will be prolonged. Swallow service trenches will provide the access from the sidewalls to the pits.

CERN Prototype Meeting – M.Nessi N.Lopez, M.Manfredi (GS-SE)

Technical Aspect: Civil Engineering main activities (1/2)




-Construction sheet piles (or Reduce Cost Alternative Option)

-Construction diaphragm wall and final tie beams

-Construction of reinforced concrete structure (raft foundations, slabs, walls, etc.)

-Demolition of the existing gable retaining wall

Section B-B



CERN Prototype Meeting – M.Nessi ______N.Lopez, M.Manfredi (GS-SE)

Technical Aspect: Civil Engineering main activities (2/2)



The works to be carried out will include: -General worksite installation -Rerouting and cutting existing underground networks -Mass and ditch earthworks -Drawdown of the water table -Road works, car parks and landscaping.

-Rainwater treatment structures (worksite and definitive)

Notes:

Particular attention should be kept to the extracted cut material within 5.50m of distance from the TDC85

<u>Radiological Protection</u>: People allow to enter the technical gallery or inside the existing building 887 should equipped (passive/operational dosimeter) and accredited by CERN. No special measure need to be planned to work outside

CERN Prototype Meeting – M.Nessi N.Lopez, M.Manfredi (GS-SE)


Technical Aspect: Structural steel main activities (1/2)

ELEVATION FILE C

-Structural steelwork and associated components (Main and Secondary structures, Internal structures, Travelling crane structures)


-Metalwork: guardrails, stairs, ladders, doors

-Removal of the north gable of the existing building (not before the extension is water-tight and air-tight)



CERN Prototype Meeting – M.Nessi N.Lopez, M.Manfredi (GS-SE)

Nord Area EHN1 extension



and the second water and the second second



Ready for beams in 2017

Schedule

Anticipated start of the works (if possible) + 18 months

										¥	Planning Travaux	
N*		Nom de la tâche	Durée	Début	Fin	Pré écesseurs			2015		2016	
	0						Oct	Nov Déc	Jan Fév	la	ar Avr Mai Jui Jui Aoù Sep Oct Nov Déc Jan Fév Mar Avr Mai Jui	Jul Aoi
1		Infrastructure Est	166 jours	Lun 03/11/14	Lun 22/06/15		<u>.</u>	Infrastructure Est				
2		Etudes	7 moiséc	Lun 03/11/14	Lun 01/06/15						Etudes	
3		Préparation chantier	2 moiséc	Lun 03/11/14	Ven 02/01/15				Préparation chant	tier		
4		Décapage	15 jourséc	Lun 17/11/14	Mar 02/12/14			Décapag	e			
5		Terrassements	2 moiséc	Mar 02/12/14	Sam 31/01/15		1	*	Terras	sements	s and the second se	
6		Palplanches	15 jourséc	Lun 15/12/14	Mar 30/12/14		1		Palplanches			
7		Infrastructure Est	4 moiséc	Lun 02/02/15	Mar 02/06/15		1				Infrastructure Est	
8		Drainage et remblai Est	3 sm	Mar 02/06/15	Lun 22/06/15	7	1				Drainage et remblai Est	
9		Infrastructure pignon	65 jours	Lun 01/06/15	Dim 30/08/15		1				lafrastructure pignon	
10		Infrastructure pignon	2.5 moiséc	Lun 01/06/15	Sam 15/08/15		1				Infrastructure pignon	
11			15 iourséc	Sam 15/08/15	Dim 30/08/15	10					tainage et remblai pignon	
12			0 jour	Lun 12/01/15				1	0/01 Travaux			
13			87 jours		Mer 13/05/15				Parois moulée	5		
14					Lun 27/04/15	12	1 1		*		Parois moulées	
15			1 moiséc		Mer 13/05/15		1 1				Pompage	
16		Infrastructure Ouest	86 jours		Mar 07/07/15		1 1			-Infe	Unfrastructure Quest	
17			3 moiséc	Lun 09/03/15						_	Infrastructure Ouest	
18	_		1 moiséc		Mar 07/07/15	17					Drainage et remblai Ouest	
19		Fosses		Lun 18/05/15							Fosses	
20			4 moiséc	Lun 18/05/15							Terrassement fosses	
21	_		2 moiséc		Sam 14/11/15	20					Dallage drainant fosses	
22			3 sm		Ven 04/12/15						Voiles fosses	
23					Mer 23/12/15	**					u Dallaces	
24			8 moiséc		Mer 23/12/15						Dallage drainants Hall	
25		Charpente	90 jours	Lun 23/11/15							Charpente	
26			4.2 moiséc								Charpente	
27			85 jours	Lun 15/02/16								
28			3 moiséc	Lun 15/02/16							Couverture	
29				Lun 29/02/16								dage
30					Lun 13/06/16	2055						urerie
31			1 moiséc		Lun 13/06/16							itions
32			0 jour	Lun 11/04/16		SUFF					11/04 🐟 Hors d'eau	
33			0 jour		Mer 01/06/16						01/06 💩 Hors d	air
34			55 jours		Sam 25/06/16						Wignon existant	Г" Г
35		•	3 sm		Ven 29/04/16	33					Dépose pignen	Ĩ
36			3 sm 3 sm		Ven 29/04/16 Ven 06/05/16	34					E P	
37			3 sm 3 sm		Ven 06/05/16 Ven 27/05/16	26						ont roulant
37			3 sm								edition ;	
38			3 sm 15 jours		Ven 27/05/16							Dallage
40					Mar 21/06/16						<u>↓</u> •	Sanitaires
40					Sam 25/06/16	32		w VRD				
41			417 jours 3 sm		Mar 21/06/16			Dév. R	kenne		* 1 *	1
42 43			3 sm 1 sm		Ven 05/12/14			Dev. R	caedus.		Voie Est	
43 44					Ven 26/06/15						Voie Ouest	
44 45			1 sm		Ven 29/05/15						-	
45 46			15 jours		Ven 01/04/16		- L				Bassin EP + réseaux	
46			15 jours		Ven 19/02/16	44						
			1 moiséc		Mer 11/05/16						Voie Noted	
48			1 moiséc		Ven 10/06/16	47						ies Ouest
49			1 moiséc		Mer 30/09/15						Réseau Incendie	
50			1 moiséc		Ven 30/10/15	49					Réseau drainage	
51			15 jours		Ven 20/05/16						Platiforme	
52		Merion + TV	15 jours	Mer 01/06/16	Mar 21/06/16	33						Merion + TV

Source : ARCADIS \rightarrow to be updated after tendering procedures

Civil engineering CERN team


- ✓ Luigi Scibile (group leader)
- ✓ Matasha Lopez (project leader)
- ✓ Martin Manfredi (CE engineer)
- new CERN CE engineer to follow the construction on side to be appointed
- ✓ firm ARCADIS as responsible for design and construction follow up (contract running)

Consortium of firms selected for the construction, Contract still in 2014 after CERN Finance Committee approval


The EHN1 Extension - Detector Integration

Floor loading at the pit: 30 t/m²
 - detector load distributed over the full surface
 - ex. for WA105 12.5×12.5 = 156m² ⇒ 4690 t


The EHN1 Extension - Detector Integration



Neutrino extension




Neutrino extension



Integration of services and experimental groups steered by one of the support group (leader I. Efthimiopoulos)


EHN1 Extension Integration - Control Rooms for Experiments

- Follow (if possible) the same design as in the existing building
- Counting rooms in ground and 1st floor
- Fully metallic structures, not connected to the building
 - modular design, allows reconfiguring upon needs
 - separate ventilation units per room (or groups of rooms)




EHN1 Extension Integration - Control Rooms for Experiments

- Follow (if possible) the same design as in the existing building
- Counting rooms in ground and 1st floor
- Fully metallic structures, not connected to the building
 - modular design, allows reconfiguring upon needs
 - separate ventilation units per room (or groups of rooms)



EHN1 Secondary Beams


H2 Beam Line – SPS North Area



Design of the Low-Energy Tertiary Beams

Four-bends layout


 Available magnets: MBPL 120mrad for 1-9 GeV beams



- design used for the ATLAS(H8)
 &CMS(H2) calorimeters in the past
- suffers from large background from the direct secondary beam

Three bends layout (EHN1-Ext)

 detector off-axis wrt incoming secondary beam




 reduces background to the experiment, critical for detectors with large drift volumes


The EHN1 Extension - Charged beams

VLE tertiary beams for the v detectors

- H2 extension: **1-20 GeV/c**, hadrons (π^{\pm} , μ^{\pm} , p mixed beam), electrons(e^{\pm})
- H4 extension: 1-5(7) GeV/c, hadrons (π[±], μ[±], p mixed beam), electrons(e[±])



The EHN1 Extension - Charged beams



Preliminary layout seems to work ok.

Detailed designs ongoing, including all performance aspects for the beam

- hardware installation {magnets, beam instrumentation, handling, ...}
- safety {radiation protection, access, …}
- beam performance & background to the experiments !

key issue and motivation to have the detectors in the pits !!!

The EHN1 Extension - Charged beams


Issues to address/resolve for the beams:


- particle momentum : beam acceptance $\pm 5\%$ in Δp
 - If not sufficient, must design and build a low-Z spectrometer (chambers) around the last magnet

- particle content:

- we can make pure electron beams and muon beams with high (>80%) purity
- hadron (π, p) beams will always be mixed beams from e/ µ content
- particle tagging is possible with threshold Cherenkov counters (but also add material to the beam!)
- background to experiment:
 - from secondary high-intensity beam (~ 10⁴ higher rate!)
 - efficient trigger system would be required
 - LArgon part inside the cryostat upstream the active volume
 - possible to introduce an extruder, possibly covering part of acceptance to do tests with/without it?

π/μ ratio on axis for a π VLE beam





Integration team

... and to all colleagues for their work so far:

B.Bannister, J. Devine, J. Pierlot, M. Obrecht, M. Battistin, C. Bertone, I. Ruehl, A. Fabich, A.L. Perrot, S. Girod, M. Manfredi, L.A.Lopez-Hernandez, J. Gascon, A. Henriques, J. Bremer, S. Hutchins, C. Theis, H. Vincke



How to get in ?

MOU frame

Memorandum of Understanding

for providing a framework for developing a Neutrino Program at CERN

between

The EUROPEAN ORGANIZATION FOR NUCLEAR RESEARCH, an Intergovernmental Organization having its seat at Geneva, Switzerland, ('CERN,'), as the Host Laboratory,

and

The FUNDING AGENCIES/INSTITUTIONS PARTICIPATING IN THE NEUTRINO PHYSICS RESEARCH PROJECTS AT CERN ('the Neutrino Institutions'),

on the other hand,

on the one hand,

(collectively "the Parties")

Preamble

- (a) As endorsed by the CERN Research Board at its meeting of August 28th, 2013 and detailed in <u>Annex 1</u>, CERN has decided to develop a Neutrino Program at CERN ('the Neutrino Program') to pave the way for a substantial European role in future Long-Baseline Experiments and explore the possibility of major participation of Europe in leading Longbaseline Neutrino Projects in the United States and Japan;
- (b) The Neutrino Institutions, including possibly CERN, wish to collaborate in the research and development (R&D) and construction of prototypes, equipment and related infrastructure for the Neutrino Program and have obtained the support of their Funding Agencies to enable them to participate in the Neutrino Program;

How to get in?

- Present to the CERN SPSC a LOI or an expression of interest
- When approved we prepare together an MOU (addendum) which defines all responsibilities and resources needed
- Then a CERN experiment is created (WA104, WA105, ...), with all priviledges and requirements

https://edms.cern.ch/document/1353815

Several MOUs are being prepared for signature

Addendum No. 01

<u>to</u> the Memorandum of Understanding <u>for</u> Collaboration in the Neutrino Program

WA104

Overhauling of the ICARUS T600 and R&D on Liquid Argon Time Projection Chamber (LAr TPC)

ANNEXES

Annex 1:	List of the Sub-units (systems) and/or deliverables provided by participating institutes	
Annex 2:	Organization and Management structure <u>of</u> the Collaboration and persons currently holding management positions	
Annex 3:	List of Institutes, Funding Agencies and Representatives	
Annex 4:	Value of deliverables, grouped by Funding Agency and/or sub-units (systems) and payment profile	
	Design that the second	
Annex 5:	Project Milestones	

The European Organization for Nuclear Research (CERN)			
and			
The INFN, on behalf of the WA104 Collaboration			
declare that they agree on the Present Addendum to the Memorandum of Understanding for the overhauling of ICARUS T600 and R&D on Liquid Argon Time Projection Chamber (LAr TPC)			
Done in Geneva			
for CERN			
Sergio Bertolucci Director of Research and Scientific Computing			
For the participating institutes			
Institute / Funding Agency	Signatory		
Place and Date	Signature		

Summary

- CERN is providing the community with a Neutrino Platform to develop detectors, beams and components
- A new test area is under preparation
- CERN provides the community with technical support, logistics and expertise
- Any type of application is welcome
- Platform organized via an MOU system