




Module Construction

Pusan, 15 December 2014


V. Manzari – INFN-Bari & CERN




4th ALICE ITS upgrade, MFT and O² Asian Workshop 2014 @ Pusan

Detector Layout Overview


7 layers of Monolithic Active Pixel Sensors



Outer Barrel



Outer Barrel Stave



Outer Barrel (OB): 2 ML + 2 OL

Radial position (mm): 196, 245, 344, 393

Length in z (mm): 843, 1475

Nr. of staves: 24, 30, 42, 48

Nr. of half-staves/stave: 2


Nr. of modules/half-stave: 4 (ML), 7 (OL)

Nr. of chips/module: 14


Nr. of chips/layer: 2688, 3360, 8232, 9408

Material thickness: $\sim 1\% X_0$ per layer

Module to Module and Power Bus connections



Outer Barrel: full-scale prototypes of the mechanical structures






Inner Barrel



ALICE

Cooling Ducts

Inner Barrel Stave



Stave weight
~ 1.4 grams

Inner Barrel (IB): 3 Inner Layers

Radial position (mm): 23, 31, 39

Length in z (mm): 271


Nr. of staves: 12, 16, 20

Nr. of modules/stave: 1


Nr. of chips/module: 9

Nr. of chips/layer: 108, 144, 180

Material thickness: $\leq 0.3\% X_0$ per layer




Inner Barrel: full-scale prototypes of the mechanical structures



OB Module Components




Pixel chip with pads over logic




x 14

Flexible Printed Circuit (FPC) with plated holes
Cu/Polyimide double layer (20/75/20 μm)




x 1

Laser soldering




x 1400 (~100/chip)



Interconnection of Pixel chip to FPC by selective laser soldering



Before



After



Standalone Laser Soldering Systems :
CERN (operational) and
Bari (delivery end of Jan '15)


OB Module development - planning and milestones



Activity	2015												2016				
	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	
ALPIDE-2 Module																	
FPC Design and Production	█	█	█														
Module Production			█	█													
Module Characterization				█	█	█	█	█									
ALPIDE-3 Module																	
FPC Design and Production				█	█	█											
Module Production						█	█	█									
Module Characterization								█	█	█							
Final Module																	
FPC Design and Production									█	█	█						
Module Production											█	█	█				
Module Characterization														█	█	█	



Main steps of the Module Assembly Procedure

1. Chip visual inspection - dimensions, warp, integrity, cleanness




2. Chip alignment - pick up from the chip pallet and place above a vacuum chuck in nominal position with respect to reference markers

- 14 chips one after the other
- use reference markers on chip surface and vacuum chuck
- gap between adjacent chips:
 - 100 μm between nominal edge
 - 200 μm between center of cross reference markers





3. FPC alignment - placement above the chips arrays in nominal position by mean of a jig embedding a soldering grid

- use locating pinholes and ruby spheres
- the soldering grid is a ceramic plate with 0.5 mm holes corresponding to the FPC vias
- the jig gently press the FPC against the pixel chips to minimize the gap in between




4. Soldering balls placement - fill the soldering grid holes with the soldering balls by mean of the balls transfer tool

- the grid guides the soldering balls into the FPC vias
- one chip at a time, use pinholes for alignment
- visual inspection to ensure each hole is filled with one and only one soldering ball




5. Soldering readiness - install the vacuum tight lid equipped with the quartz window above the pixel chips, FPC and soldering grid stack-up


- start vacuum pump to empty the soldering volume till ready for laser soldering
- pressure of the chip vacuum chuck always smaller than soldering volume





6. Laser soldering - shoot laser through the quartz window onto each soldering balls in sequence to melt them and establish the connection between FPC and pixel chip


- Visual checks of soldering joints




































































































































































OB Module Assembly



ALICE




Half-Stave and Stave Assembly



Summary Table of OB Modules and Staves

Layer	Stave	Half-stave	Module	Chip
L3	24	48	192	2688
L4	30	60	240	3360
L5	42	84	588	8232
L6	48	96	672	9408
Spares (20%)	11	22	88	1232
	18	36	252	3528
Total	65	130	2032	28448
	108	216		




OB Module Construction - Organization



- Module production will be distributed among up to 6 production centers:
Bari (Italy), CERN, Liverpool (UK), Pusan (South Korea),
Strasbourg (France), Wuhan (China)
- Each production center will deploy an identical automatic assembly systems to ensures an homogeneous quality over the whole production



Procurement of the automatic assembly systems is centrally managed by the project with a tendering launched from CERN

Details in the next talk by Antonello



Tasks at the Module Construction Center after the assembly

- 1. Chips position** - measurements of chips position in the module with respect to reference markers, which will remain visible throughout the following construction and integration operations
- 2. Module characterization** - functional validation of modules according to a defined protocol
 - Test System developed by Bari group
- 3. Module transport** - shipment of qualified modules to the Stave Construction Centers
 - Liverpool, LBNL, Turin and LNF, NIKHEF




- ✓ ~40 m² of a clean room class 100000
- ✓ Compressed air and nitrogen supplies
- ✓ Automatic assembly system
- ✓ Optical microscope for visual inspections, equipped with image acquisition system
- ✓ Test bench equipped with readout and control test system, cooling system and power supply systems
- ✓ Radioactive source (typically ⁹⁰Sr, activity ~10MBq)
- ✓ Storage cabinets (antistatic, desiccator) for components and assembled modules
- ✓ ...

	2015				2016				2017			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Laboratory setting up	■	■	■	■	■							
Automatic Assembly System: Procurement, Installation and Commissioning				■	■	■						
Training (@ CERN and Bari/Italy)												
Manual assembly and Laser soldering	■	■										
Automatic assembly system		■	■	■	■	■						
Test System			■	■	■	■						
Module Production							■	■	■	■	■	■

Expected delivery date and commissioning of the first prototype of the automatic assembly system

OB Construction flow-diagram



Conclusions



- The manual assembly procedure for the OB (and IB) module is well advanced and the optimization is in progress
- This procedure will be implemented in the Automatic Assembly System, whose supply is object of a tendering, to ensure reproducible quality
 - Some operations will be controlled or automatized
- The production of the OB modules will be shared between 6 laboratories
 - Bari (Italy), CERN, Liverpool (UK), Pusan (South Korea),
Strasbourg (France), Wuhan (China)
- Setting up of the infrastructures and training next year
- Start Module production mid 2016

*Stave and Module construction are discussed in the WP6/7/8 meetings:
Thursday 16h:00 – 18h:00 (Geneva time) – dates for 2015 will be circulated soon*