

# LHC Injectors Upgrade





## LHC Injectors Upgrade

# Resonance Mapping in the PS

R. Wasef, G. Franchetti, S. Gilardoni, A. Huschauer, F. Schmidt,  
D. Schoerling, R. Tomás.



# Outline

- I. Status and Introduction of the PS
- I. Measurement of Octupolar Errors
- I. Resonance Driving Terms Measurement
- I. Resonance Compensation
- I. Summary and Conclusion





# Outline

- I. Status and Introduction of the PS
- I. Measurement of Octupolar Errors
- I. Resonance Driving Terms Measurement
- I. Resonance Compensation
- I. Summary and Conclusion









# Status and Introduction of the PS

- Started operation in 1959
- 100m radius
- 100 combined function magnets
- Each magnet consists of 10 blocks: 5 F and 5 D (cell: FDODF)
- Tunes are controlled with:
  - LEQ at low energy
  - PFW at high energy
- Injection kinetic energy 1.4GeV.



# Coil system: main circuit and auxiliary coils

Thermographic inspection of PFW






# Coil system contributions

## Main coil

- Hyperbolic pole shape
- Only **dipolar** and **quadrupolar** field at **low field** level
- Iron saturation
- Sextupolar and higher order components at high field level

## Pole-face windings + and figure-of eight loop


- 5-Current Mode
- *Un-balanced N and W circuit current generate octupolar and higher components*
- Non-linearities at high field (iron saturation)
- Field probably up to decapole





# Regular lattice optics (FDODF)

- Regular  $\beta$  functions between 12m and 22m.
- Dx between 2.2m and 3.8m.










# Current Situation in the PS

- Loss maps showed a relatively strong **skew sextupolar** resonances
- **Similar situation** at high energy (using PFW) and after re-alignment of the machine.




# Orbit correction by magnet tilting


- Some magnets are rotated (3 per plane) to correct orbit and maximize aperture
- Unfortunately some of the resonances are enhanced and prediction is still not sufficiently precise



Before align.



After align.





# Outline

- I. Status and Introduction of the PS
- I. Measurement of Octupolar Errors
- I. Resonance Driving Terms Measurement
- I. Resonance Compensation
- I. Summary and Conclusion





# Measurement of octupolar errors

- To measure and localize an octupolar error:
  - Vary the amplitude of a localized bump
  - Measure the tune shift w.r.t. the bump amplitude
  
- To test this method: a horizontal bump was introduced in the sections 53-57, as well as a fake octupolar errors.

The measurement was carried out:

- without octupoles
- with a single octupole located in the middle of the closed bump
- with a single octupole located outside the closed bump




# Measurement of octupolar errors

From the fit:  
 $K_3=35.6 \text{ m}^{-3}$

No octupolar  
component for the  
bare machine

From the fit:  
 $K_3=37.5 \text{ m}^{-3}$


Expected value of  $K_3=37.9 \text{ m}^{-3}$





# Measurement of octupolar errors

- Successful identification and localization of the excited octupolar error.
- No octupolar error was measured in the main magnets at low energy (over 4 straight sections).
  - ➔ agreement with high order chromaticity & no excitation of the 4Q resonance



Chromaticity measurement, bare machine at 2GeV

- This method could be applied to a running bump in the whole machine to localize octupolar errors.





# Outline

- I. Status and Introduction of the PS
- I. Measurement of Octupolar Errors
- I. Resonance Driving Terms Measurement
- I. Resonance Compensation
- I. Summary and Conclusion








# Resonance Driving Terms

- **43 shoe box pickups** located at the end of every magnet numbered x0,x3,x5,x7, with a respective phase advance of **67.5°**, **45°** and **45°** and **100μm resolution**.
- **Turn by turn** data available (**5000 turns** with the current acquisition system).
- **Challenges:**
  - ✧ No vertical kicker
  - ✧ Horizontal kickers available are too strong at low energy
  - ✧ Large natural chromaticity ( $Q' \sim -6$ ) → very fast decoherence
- Transverse feedback has been prepared to be used as **AC-dipole** after the winter shutdown.



# Resonance Driving Terms

- Injection missteering: **Injection bump** (tune variation) → only **80 turns** available at injection (~6% noise and peaks merged)



Expected Resonance line  
within the peak width



# Outline


- I. Status and Introduction of the PS
- I. Measurement of Octupolar Errors
- I. Resonance Driving Terms Measurement
- I. Resonance Compensation
- I. Summary and Conclusion





# Resonance compensation


- The bare machine (only main magnets powered) measurements show relatively strong skew sextupolar resonances ( $2Q_x + Q_y = 19$  and  $3Q_y = 19$ ).
- As a proof of principle, we tried to compensate each of these resonances during the 2013 run.





# Resonance compensation

- 2D calculation including Gaussian distribution of the position of the coils and the shape of the iron with up to 22 DOFs per magnet (OPERA) were performed.
- 1000 models per magnet type (4 types) and current level have to be calculated. Performed for momentum of 2.14 GeV/c, 2.78 GeV/c, 14 GeV/c, 26 GeV/c.




## Coils can be displaced, no rotation:

Main coils (2 x 4 DOFs),  $\sigma = 3$  mm


F8 (2 x 4 DOFs),  $\sigma = 1$  mm

PFW (2 x 2 DOFs),  $\sigma = 0.7$  mm

Iron is displaced in y-direction,  
 $\sigma = 0.02/3$  mm



## Dipolar Component





Kinetic energy: 1.4GeV

Reference radius

$r = 10$  mm



Vacuum chamber: 140x70mm





→ These errors were randomly distributed on the magnets in the PTC model to compute the driving terms of each of the resonances.



# 2Qx+Qy Resonance





Horizontal Scan





Vertical Scan

# 3Qy Resonance



Horizontal Scan



Vertical Scan




# Outline

- I. Status and Introduction of the PS
- I. Measurement of Octupolar Errors
- I. Resonance Driving Terms Measurement
- I. Resonance Compensation
- I. Summary and Conclusion



# Summary & Conclusion

- Measurement of octupolar errors showed that the bare machine has very small octupolar errors.
- Resonance Driving Terms measurements planned in 2015 with an AC Dipole.
- A successful implementation of resonance compensation was achieved but further investigations are needed to a better understand the source of these errors.



# LHC Injectors Upgrade

**THANK YOU FOR YOUR ATTENTION!**

