

LHC BLM SYSTEM:

TECHNICAL DETAILS AND PLAN FOR THE
MODIFICATIONS TO **FORCE** TRUE
THE BEAM PERMIT SIGNAL AT INJECTION

(aka Injection Interlock Inhibit)

Some reminders to ease the discussion on the modifications

CURRENT ARCHITECTURE

Current LHC BLM Design

In order to provide a **failsafe** design, among others, the following rules have been used:

- No mode or function can force the beam permit to true.
- The complete acquisition and processing chain does not have any other mode than the operational.
- Signal can be added but not subtracted.


Prerequisites for any modification

- Minimum impact on SIL and avoid branching
- Keep testability and traceability
- As few as possible changes in the system

Therefore:


- **Connectivity check** (part of the System Sanity checks) should be still possible.
- FPGA Firmware modifications should be applicable globally – maintain **one firmware** for all crates.
- Expect **notification signal** to be of high dependability.

System Overview



Surface Installation

- From each LHC point the fibres arrive to one service room at **SR buildings**
- Approx. **1600 fibres** in total, i.e. 2 from each acquisition module
- All the fibre minitubes (1-2 km) arrive to a **distribution rack** in the surface.
- **Patchcords** (5-7 m) are used to connect to the cards in the crates.





Fibre distribution Rack




Processing Rack

Processing Crates



- 1) **FEC/CTRP** – CPU / GMT timing
- 2) **BOBR** – BST timing
- 3) **BLECS** - Combiner & Survey
- 4) **BLETC** – Threshold Comparator

Beam Permit Signals Distribution



Details on the modifications proposed and the new functionality

MODIFICATION PROPOSAL


Modifications: Installation

- Move relevant **detectors** to separate acquisition cards
 - See ECR for injection BLMs for the list of monitors involved.
 - Re-cabling of signal and power distribution is necessary for some.
 - **Note:** we asked initially the current grouping of monitors to **not** be broken. This was later agreed to be an unrealistic demand.
- Add two new processing **crates**
 - Connect to the standard interlock daisy chain between crates
 - Will be the last in the chain to avoid inhibiting other crates' interlocks
- Add new **processing modules** and connect fibres.
- Update the **MTF**, **LAYOUT** and **LSA** databases with this configuration.

All to be completed during LS1

Configuration in SR2 & SR8


Configuration in SR2 & SR8



Modifications : Hardware

- **Modify the BOBM (BST master) configuration** to forward a timing event related to the injection
 - There are several to choose from, e.g. HIX.FW-CT, HIX.W100-CT, HIX.W20-CT, HIX.AMC-CT.
- **Modify the BOBR (BST receiver) configuration** to distribute the timing event in the backplane of the crate.
 - A pulse is broadcasted to all cards through a dedicated line of the VME64x P0 connection whenever the event is received
- **Modify the BLECS firmware** to force the Beam Permit line for a fixed period of time when it receives the injection signal and certain other conditions are satisfied.
 - Persistent FESA settings per crate will (in the future can become part of the MCS parameters):
 - ▶ **Activate/Disactivate** the inhibit functionality.
 - ▶ Define the **time** the beam permit is forced to TRUE
 - Inhibit of the output will happen only under certain conditions:
 - ▶ during injection,
 - ▶ energy is 450 GeV,
 - ▶ ...

Interlock Inhibit Functionality




Additional information

- The modified firmware, at this time, cannot affect the total reliability of the system but it can affect its **availability**, i.e. false dumps.
- **Measurement or threshold values** will not be modified at any time, i.e. no blinding.
- **Interlocks** by channels over threshold values will always be **logged**.
 - For all channels and all integration periods at 1 Hz
 - Though, it will be not possible to know when exactly or how many times inside the 1 s the interlock occurred.

Strategy proposed for the deployment and future upgrades

PLANNING PROPOSAL

Planning (proposed by MPP)



First high intensity injection
144b @ 50ns + 25ns
First benchmarking on injection losses post LS1

High intensity injection
288b @ 25ns
Doublets?

- Deploy BLM interlock inhibit at injection for potential use in TS1 (to avoid slow down of scrubbing and initial intensity ramp-up).
 - Special version ONLY on blind-able crates.
 - Commission blinding with timing signal but **INITIALLY DO NOT BLIND** in order to allow assessment of post LS1 situation.
- **Prepare for full deployment if need confirmed in TS2.**

Strategy Proposed

- At TS1 deploy special BLECS firmware on new crates
 - separate crates have been installed
 - detector distribution (+use of LICs) has been done
 - new functionality only on the two new injection crates
 - injection signal via the BOBR (via backplane)
- During 2015 maintain **two BLECS firmware**
 - evaluate the need of the inhibit functionality
 - discover the optimal settings and safeguards required (deadtime, max. repeat, checks etc.)
 - modify further firmware and deploy as necessary (MPP has accepted reduced reliability for these two crates)
- At **WTS 2015**, depending on outcomes,
 - decide if functionality is needed
 - deploy common firmware to all BLECS modules
 - move FESA settings to DB parameters with MCS

THANK YOU