

LHC Injectors Upgrade





LHC Injectors Upgrade

Functional specifications review for the stripping foil BSW magnets power converters


- Introduction (specs, topology)
- Integration
- Connections with power converter
- Development strategy
- Activities & Priorities
- Milestones schedule
- Next actions



Introduction

- 16 power converters required for individually feeding 16 magnets
- 2 types of converters (BSW1 different from BSW2, 3, & 4)
- 2 spares power converters – total of 18 converters


	BSW1	BSW2&3	BSW4
L (μH)	13	70	77
R ($\text{m}\Omega$)	3.5	7	7
I _{peak} (A)	6700	3400	3400
I _{rms} (A)	463	231	231
V _{max} (V)	450	450	450



BSW magnet's electrical specifications

Introduction

Overall current/voltage specification



t_{rise} (ms)	5
t_{flat} (ms)	1 to 2
t_{fall} (ms)	5
t_{rep} (ms)	900


Because infinite dv/dt not possible,
current smoothing agreed with beam
optics

Absolute precision:

100 ppm (± 50 ppm) during flat-top (starting
from when beam is injected)

1000 ppm (± 500 ppm) during ramp-down


~ 40 kHz harmonic content – amplitude ~ 50 ppm





Evaluated topology

Power converter topology and features



Possibility of re-using existing EPC converter components




EPC-MPC new APOLO power stack under evaluation:

- H-Bridge equipped with 1.7kV-1.6kA IGBTs
- Tests undergoing to check if they can be used for this project – 95% probability!
- If yes, two APOLO modules in parallel enough



Integration

Simplified analysis – cable length issue



- If cable length increases, L_{cs} increases
- di/dt imposed by specs
- V_{conv} and V_{sec} increase as well!
- **Power converter maximum power, volume, losses, and cost increase with cable length!!!**
- Overall design parameters are:
 - transformer ratio k and
 - cable length!

Simplified analysis

$$800 \text{ V} \geq (L'_{mag} + L'_{cs}) \frac{di_{conv}}{dt}$$



$$k = \frac{i_{mag}}{i_{conv}}$$

$$800 \text{ V} \geq (L_{mag} + L_{cs}) \frac{di_{mag}}{dt} k$$



Integration

Analysis – limitations vs cable length & type

2 conductors of 150mm²,
L=0.6μH/m: 4 conductors of 75mm²,
L=0.26μH/m:




Converters power, volume and cost increase with cable length (analysis considering resistive effects):




Integration

General powering layout




Possibility of deporting pulse transformers of BSW2, 3, & 4 nearer to the magnet:



Integration

Reserved space in **BRF2** (bld. 361) for power conv. racks





- Each converter 3 racks (fighting for 2...)
- Access from front and rear of each rack!
56 racks total
- Existing RF equipment to be moved; renovation/re-installation of RF equipment coordinated with TE-EPC to optimally re-configure the space
- Power distribution/switchgears to be renovated (RF) and extended (strip foil)
- Water cooling probably needed (taps available – should not be an issue)
- False floor to be modified/reinforced

Integration

Evaluated solution for cable length minimization from BRF2 down to magnets


- Cable path studies showed an issue in finding a suitable cable gallery with appropriate length
- The option of a new cable trench/passage from BRF2 down to the injection area (1L1) into the tunnel has been preliminarily investigated
- Very rough cost estimation was made, and a total of ~2 MCHF would be necessary to construct a new cable trench illustrated in green
- Too expensive, other solutions can be found



Integration

Most likely solution – deporting BSW2, 3, & 4 pulse transformers

Identified possible zone for BSW2, 3, & 4 pulse transformers




- Identified old access shaft to the PSB tunnel
- Verifications undergoing DGS/RP for the utilisation of this zone.
- Advantages with this solution:
 - Shortening the secondary cables lengths
 - Equalize the secondary cable length such that the converters current controls algorithms are exactly the same (simplified operation and spares organization).
 - Have a unique pulse transformer spare in the same zone and reduce PSB
 - downtime in case of a pulse transformer or DCCT failure.


Integration

BSW1 pulse transformers

- Shall be placed next to injection region
- Either on concrete slab or false floor reinforcement
- Secondary cables or bus-bars to be selected




Concrete slab ends here






Half Sector Test in a nutshell

- Same power converters to be re-used in PSB (BSW2&4)
- Power converters ready in early 2016!
- 2 x power converters installed in Bldg. 400
- BSW3 & 4 magnets installed in L4-PSB transfer line
- Cable length: 70m. If shorter in PSB, pulse transformers are different
- Pulse transformers installed inside PC racks
- Water cooling and power distribution to be defined






Connections with power converters / summary



BSW1 converters (PSB only)

- AC distribution cables (with neutral)
- Water cooling
- BIS
- Primary DC cables
- Secondary cables/busbars
- DCCTs cabling
- Magnet interlock cable/interface



BSW2,3,4 converters (PSB & HST)

As above with transformer outside tunnel

Pulse transformers either inside power converter rack or in the identified zone of Fig. 10





General development strategy

Reminder:


- HST power converters (PC) ready (before commissioning) by early 2016
- PSB PC ready (before commissioning) by end 2017

Strategy:

- Same PC for BSW1 and BSW2,3, & 4 – only pulse transformer and current measuring system differ
- Re-utilization of existing power stack design-probably no MS-IT procedure!
- 3 PCs ready by early 2016 – 2 x BSW3 & 4, and 1 x BSW1. Power stacks for prototypes via recent contract options
- Reception at CERN of main series components (chargers, capacitors, power stacks, DCCTs) by end 2016
- MS-IT procedures for chargers (~200kCHF), DCCTs (~200kCHF), pulse transformers, and power converters assembly



Activities and priorities





Milestones Schedule

Major milestones and activities

Description	2014	2015			2016			2017		
	Sept-Dec	Jan-Apr	May-Aug	Sept-Dec	Jan-Apr	May-Aug	Sept-Dec	Jan-Apr	May-Aug	Sept-Dec
Eng. design	■	■	■	■						
Parts for HST + BSW1		■	■							
HST PC construction			■	■						
Series prod MS-IT			■	■	■					
Parts 4 series (MS-IT)				■	■	■				
Transfo MS-IT						■	■	■		
Series assembling								■	■	■

Installation and commissioning in 2018





Actions for finalizing functional spec.

Major actions to finalize functional spec. and finalize design / start purchasing

Item #	Objective	who	By date
1	Confirm that 50 ppm 40 kHz current ripple acceptable	TE/ABT	Now
2	Cable length between pulse transformers and magnet	EN/EL	21 st Nov.
3	Cable distance and path for BSW1 DCCTs (current measurement)	EN/EL	21 st Nov.
4	Dimensions of identified zone for pulse transformers	EN/EL – EN/MEF	28 th Nov.
5	Define the interfaces, type and number of cables, for magnet interlock. Actions with	TE/EPC - TE/ABT	5 th Dec.
6	Define timing management solutions.	TE/EPC – BE/OP	12 th Dec.
7	Define BIS current tolerance for safe operation in the PSB and HST.	BE/ABP - BE/OP	12 th Dec.
8	BRF2 global integration studies considering RF renovation + HST global integration study	TE/EPC - BE/RF EN/MEF – EN/EL	Early 2015
9	Water distribution needs and work	TE/EPC – EN/CV	Early 2015



www.cern.ch