# 11 T Dipole Project Status

M. Karppinen on behalf of CERN-FNAL collaboration

"Demonstrate the feasibility of Nb<sub>3</sub>Sn technology for the DS collimation upgrade with an accelerator quality 5.5-m-long twin-aperture 11 T prototype dipole by 2015"







춯

#### FNAL:

N, Andreev, G. Apollinari, E. Barzi, R. Bossert, G. Chlachidze, J. Coghill, J. DiMarco, D. Mitchel, F. Nobrega, I. Novitski, G. Wilson, A. Zlobin,...

#### **CERN:**

B. Auchmann, A. Ballarino, A. Bonasia, S. Bermudez,

N. Bourcey, A. Cherif, S. Clement, A. Gerardin, M. Guinchard, L. Bottura, C. Kokkinos, B. Favrat, L. Favre, C. Fernandes, P. Fessia, R. Gauthier, B. Holzer, S. Izquierdo Bermudez, G. Kirby, F. Lackner, T. Lyon, G. Maury, J. Mazet, N. Mena, R. Moron-Ballester, J-M. Mucher, J. Murtomaki, L. Oberli, J-C. Perez, L. Rossi, T. Sahner, F. Savary, J.-M. Scigliutto, L. Remandet, S. Russenschuck, S. Sgobba, E. Todesco, D.


Tsirigkas,...







- DS upgrade
- Design challenges
- Magnetic design
- Mechanical design
- Pole loading concept and CERN coil design
- Model program status and plans:
  - o **FNAL**
  - o **CERN**
- \* Summary



\* Joint development program between CERN and FNAL underway since Oct-2010.



# 11 T Nb<sub>3</sub>Sn Dipole Design Challenges



#### Iron saturation effects

- o Modified MB Yoke
- o Cross-talk between apertures

#### Transfer function matching with MB

- o More turns (56 vs. 40)
- o Iron saturation

### Dynamic effects

- o Strand development
- o Cored cable

### Coil fabrication

- o Cable development
- o Electrical insulation
- Nb<sub>3</sub>Sn specific tooling and fabrication process
- o Reproducibility & Handling

#### \* Quench protection

- o Heater development
- o Instrumentation

#### Mechanical structure


- o Forces almost 2 X MB
- o First 2-in-1 Nb<sub>3</sub>Sn magnet
- \* Thermal
  - o Resin impregnated coils

### Integration

- o **Optics**
- o Cold-mass
- o **Collimator**
- o Machine systems

# Magnetic design: Coil Optimization





- \* 11.25 T at 11.85 kA with 20% margin at 1.9 K in
- \* 60 mm bore and straight 5.5-m-long coldmass
- **Systematic field errors below the 10<sup>-4</sup> level**
- \* 6-block design, 56 turns (IL 22, OL 34)
- \* 14.85-mm-wide 40-strand Rutherford cable, no internal splice
- Coil ends optimized for low field harmonics and minimum strain in the cable



### 11 T Model Dipole Magnetic Parameters



Parameter	Single-a FN	-	Single-aperture CERN	Twin-aperture				
Aperture (mm)			60					
Yoke outer diameter (mm)	40	0	510	550				
Coil length (m)	1.80	0.88	1.8	0.88 - 1.8 - 5.4				
Nominal bore field @11.85 kA (T)	10.86	11.07	11.25	11.25				
Short-sample bore field at 1.9 K (T)	13.6 <sup>(1</sup>	14.1 <sup>(2</sup>	13.9 <sup>(1</sup>	13.9 <sup>(1</sup>				
Margin B <sub>nom</sub> /B <sub>max</sub> at 1.9 K	0.80 <sup>(1</sup>	<b>0.78</b> <sup>(2</sup>	0.81 <sup>(1</sup>	0.81 <sup>(1</sup>				
Stored energy at 11.85 kA (kJ/m)	473	482	484	969				
F <sub>x</sub> per quadrant at 11.85 kA (MN/m)	2.89	3.11	3.16	3.16				
F <sub>y</sub> per quadrant at 11.85 kA (MN/m)	-1.57	-1.56	-1.59	-1.59				

1) OST Ø0.7 mm RRP-108/127

2) OST Ø0.7 mm RRP-150/169



## Mechanical Design Choices & Goals



#### \* Separate collared coils

- **o** Most of the coil pre-stress obtained by collaring
- o Symmetric loading
- o Better control of pre-stress
- o Testing of collared coils in 1-in-1 structure

### Vertically split yoke

- o Assembly process less influenced by friction (vs. horizontal split)
- Closed gap at RT and up to 12 T to provide rigid support for the collared coil
- o Better controlled (collared) coil deformation
- Welded stainless steel skin

#### Coil pre-stress

- o Within 0..-165 MPa at all times
- o Minimal elliptic deformation
- o Minimal stress gradient in the coils
- o Easy tuning of pre-loading by shimming
- o Minimize discontinuous loading and shear stress (end regions)




## Mechanical Design Concepts



### CERN

**FNAL** 




Pole loading design


Integrated pole design



### **Pole Loading Concept**








Layer-jump region with cable removed




### **CERN 11 T Dipole Coil**











M. Karppinen CERN TE-MSC



### FNAL MBHSP01 1-in-1 Demonstrator (2 m)







40-strand cable produced with FNAL cabling machine




**Coil fabrication** 





Collared coil assembly





Cold mass assembly



Magnet development and fabrication was done in record time - 18 month!



### **MBHSP01 Quench Performance**




#### Design goal:

**B**<sub>nom</sub>=11 T with 20% margin

#### Limited quench performance

- B<sub>max</sub>=10.4 T at 1.9 K and 50 A/s (78% of SSL)
- o long training
- o conductor degradation
- o irregular ramp rate dependence
- Quench performance was limited by conductor degradation in coil OL mid-plane blocks and leads
  - lead damage during reaction confirmed by autopsy
- Appropriate improvements implemented in MBHSP02

A.V. Zlobin et al., ASC2012, Sept 2012






### **MBHSP01** Autopsy



#### Coil #3 Used in MBHSP01





M. Karppinen CERN TE-MSC

# MBHSP02-03 - 1 m Versions of MBHSP01

- Goals: demonstrate new R&D strand, cored cable, improved process and reproducibility
- Strand (ø0.70 mm):
  - o MBHSP02 R&D RRP-150/169 strand
  - o MBHSP03 baseline RRP-108/127
- Cable: both models use 40-strand cable with 12-mm-wide and 0.025-mm-thick stainless steel core
- Coil: optimized end parts and process
- Structure:
  - o MBHSP02 modified MBHSP01 collar
  - o MBHM01 mirror magnet (with bolt on skin)
  - o MBHSP03 new collar (with bolt on skin)
- MBHSP02 fabrication 6 months!





## **MBHSP02 Quench Performance**

13000

12000

₹


B=11 T

4.5K 1.9K



#### **Improved quench performance** •••


- $B_{max}$ = 11.7 T 97.5% of design field 0 B=12 T (78% of SSL at 1.9 K)
- **Issues to be addressed** •••






### **MBHSP02 Quench Locations**





- Quench locations moved to the mid-plane area (block 5) of coil #7 at the end of 4.5 K training
- All holding quenches in outer layer mid-plane area of coil #7
- Practically all quenches in the end regions



23-24 Sep 2013

0.45

0.4

0.35

0.3 0.25

0.2 0.15

0.1 0.05

0

07 LE

07 RE

05 LE

**Quench Locations** 

05 RE

**Normalized Number of Quenches** 


M. Karppinen CERN TE-MSC



### FNAL Short Model Program



- MBHSP01 (2 m) and MBHSP02 (1 m) have been tested.
- Coil #8 will be tested in Mirror, MBHSM01. Assembly in progress. Test Oct-2013
- Assemble and test MBHSP03 (1 m, 1-in-1) using coils #9-10, Dec-2013
- Assemble and test the MBHDP01 (1 m, 2-in-1) using collared coils from MBHSP02 and MBHSP03, Feb-2014
- Assemble and test MBHSP04 (1 m, 1-in-1) using coils #11-12, Apr-2014
- Assemble and test MBHDP02 (1 m, 2-in-1) using collared coils from MBHSP04 and coils #13-14, Jul-2014





# **CERN** Construction Status

#### **Coil fabrication tooling:**

- Winding, curing, and reaction operational 0
- Vacuum impregnation system commissioned 0

#### **Practice coil fabrication** •••


- PC-#1-2 (Cu-cable) reacted and impregnated 0
- PC #3 Nb<sub>3</sub>Sn (low-Jc WST strand) scrapped 0
- Nb<sub>3</sub>Sn (RRP-54-61) CMM done, to instrument 0

#### Magnet R&D:

- Cable insulation (braided S2-glass & Mica) 0
- ODS (oxide dispersion strengthened) wedges 0
- Selective laser sintering (SLS) end spacers 0
- Coil pre-loading concept ("pole-loading") 0
- Magnet protection (inter-layer heater) 0











#### Coil fabrication:

- o MBHSP104 (RRP-108/127 #1) ready to react
- o MBHSP105 (RRP-108/127 #2) wound and cured
- o MBHSP106 (RRP-108/127 #3) wound and cured
- Winding trials underway with trial lengths of cable with reduced keystone angle to assess the mechanical stability.

\* Cold mass:

- o Collars (EDM) for the  $1^{st}$  aperture assembled in packs.
- **o** Fine-blanking of collars for AP-2..5 underway
- **o** Laminations (EDM) for two 1-in-1 yokes in stock
- o Laminations (EDM) for one 2-in-1 yokes in stock
- o End plates for two 1-in-1 magnets in stock
- Welding trials for 1-in-1 cold mass carried out
- 0 12-mm-thick 304 L shells for 1-in-1 models in production
- 15-mm-thick 316 LN shell for 2-in-1 models ordered and welding trials planned.
- o Tooling in commissioning



### CERN Short (2 m) Model Program



Assemble RRP-54/61 coil with RRP-108/127 coil #1 as a practice model to validate the assembly process and tooling. Ideally carry out WMM and short cold test *Dec-13*. This is the present Plan A


#### OR


- Assemble and test the RRP-54/61 (or RRP-108/127 coil #1) coil as single coil assembly (MBHSS101) using existing collars, yoke, welded outer shell, and end plates. Plan B
- \* Two RRP-108/127 coils to assemble and test the 1<sup>st</sup> 1-in-1 model (MBHSP101) Feb-14
- Two RRP-132/169 coils to assemble and test the 2<sup>nd</sup> 1-in-1 model (MBHSP102) May-14
- Collared coils from MBHSP101 & 102 to assemble and test the 1<sup>st</sup> 2-in-1 model (MBHDP101) Aug-14
- Idem for PIT-cable: 2 x 1-in-1 model (MBHSP103-4) to have tested collared coils for the 2nd 2-in-1 model (MBHDP102). Mar-15, May-15, Jul-15




### **CERN Single Coil Assembly**

#### Courtesy of C. Kokkinos & T. Lyon CERN TE-MCS









### **CERN Practice Model Schedule**



ID 1	Task Name	Duration	Start	Finish	2013				2014
					1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter
		025 4	05/02/12	01/05/25	Jan Feb Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar
	CERN Short (2 m) 11 T Dipole Model Program	825 days	05/03/12	01/05/15					
	Trials & Mock-ups	329 days	05/03/12	06/06/13			68888 I		
22 1	1-in-1 Practice Model 1 (RRP-54/61 & 108/127)	449 days?	21/05/12	06/02/14		) <u> </u>			
23	Coil PC2 (RRP 54/61 cored, Mica & 11-TEX)	360 days	21/05/12	04/10/13		$\bigcirc$ $ $			
24	220 m cored RRP 54/61 cable	2 wks	21/05/12	01/06/12	5				
25	Insulated cable (Mica & 11-TEX)	7.2 wks	30/11/12	18/01/13		8 <b>9</b> 8			
26	Wind/cure	17 days	14/02/13	08/03/13	L T C		A CONTRACTOR OF A CONTRACTOR A CONT		
27	React	16 days	13/05/13	03/06/13		i 🚅 🗕 õ		<b>h</b>	
28	Splice	3 days	01/08/13	05/08/13			h Na		
29	Impregnate	13 days	06/08/13	22/08/13	] ["				
30	Inspect	15 days	02/09/13	20/09/13		30		<u>л</u>	
31	Instrument	2 wks	23/09/13	04/10/13		100	) 	<b>F</b>	
32	Coll review at CERN	1 day	23/09/13	23/09/13		1	l b	23/09	
33	Coil 1 (RRP 108/127)	188 days	04/03/13	20/11/13			++		
34	440 m cored RRP 108/127 cable	2 wks	04/03/13	15/03/13	] 🛋	1 1	++	+	
35	Insulated cable (Mica & 11-TEX)	3 wks	23/04/13	13/05/13	1		++	++	
36	wind/cure	14 days	23/05/13	11/06/13		-	+		
37	React	30 days	29/08/13	09/10/13			🐪	■h	
38	Splice	2 days	10/10/13	11/10/13				K.	
39	Impregnate	13 days	14/10/13	30/10/13					
40	Inspect	5 days	31/10/13	06/11/13				<u> </u>	
41	Instrument	2 wks	07/11/13	20/11/13					
42	Magnet assembly readiness review	1 day	24/09/13	24/09/13				24/09	
43	collared coil assembly	3 wks	21/11/13	11/12/13				🍋	
44	1-in-1 cold mass assembly	2 wks	12/12/13	25/12/13				🍅	1
45	Cold test 1-in-1	4 wks	26/12/13	22/01/14					<b>1</b>
46	Disassembly	2 wks	23/01/14	05/02/14					τ,
47	Magnet test review	1 day?	06/02/14	06/02/14	1				¥06/02



### CERN 1<sup>st</sup> 2-in-1 Model Schedule




ID	Task Name	Duration	Start	Finish		2nd Ourseters		th Quarter		2014 1st Quarter			2-10			and Outstand			Arb Oursets
					Jun	3rd Quarter Jul Aug Se	4 Sep	Oct Nov	Dec	1st Quarter Jan	Feb	Mar	2nd Quar Apr	May	Jun	3rd Quarter Jul	Aug	Sep	4th Quarter Oct
1	CERN Short (2 m) 11 T Dipole Model Program	825 days	05/03/12	01/05/15						1									
2	Trials & Mock-ups	329 days	05/03/12	06/06/13	-														
22	1-in-1 Practice Model 1 (RRP-54/61 & 108/127)	449 days?	21/05/12	06/02/14	<u> </u>						- <b>-</b> -								
48	1-in-1 Model 1 (RRP-108/127)	224 days	19/06/13	28/04/14						-		-	-	Ψ					
49	Coil 2 (RRP 108/127)	135 days	19/06/13	24/12/13			-										4		*
50	wind/cure	14 days	19/06/13	08/07/13	-			1											
51	React	24 days	10/10/13	12/11/13	1			<b>*</b> _											
52	Splice	2 days	13/11/13	14/11/13	1		1 L	के के											
53	Impregnate	13 days	15/11/13	03/12/13	1			¥				4							
54	Inspect	5 days	04/12/13	10/12/13	1				🏝										
55	Instrument	2 wks	11/12/13	24/12/13	1				<b>*</b>			20							
56	Coil 3 (RRP 108/127)	156 days	24/06/13	27/01/14	•	₽			-			$\sim$							
57	220 m cored RRP 108/127 cable	2 wks	24/06/13	05/07/13		<b>–</b>						5							
58	wind/cure	14 days	02/09/13	19/09/13	1	L						d							
59	React	24 days	13/11/13	16/12/13	1			*		h		$\triangleleft$							
60	Splice	2 days	17/12/13	18/12/13	1				1 5										
61	Impregnate	13 days	19/12/13	06/01/14	1				1 🎽			Mar							
62	Inspect	5 days	07/01/14	13/01/14	1					1 🏝		Ŭ,							
63	Instrument	2 wks	14/01/14	27/01/14	1					<b>1</b>		4							
64	collared coil assembly	3 wks	28/01/14	17/02/14	1					<b>1</b>	<u> </u>								
65	1-in-1 cold mass assembly	2 wks	18/02/14	03/03/14	1		1				<b>*</b>	h							
66	Cold test 1-in-1	6 wks	04/03/14	14/04/14	11.	-in-1 #1 Test	-					<b>*</b>							
67	Disassembly	2 wks	15/04/14	28/04/14									<b>*</b>						
68	1-in-1 Model 2 (RRP(132/169)	182 days	25/11/13	05/08/14	1								-		+		Ψ		
69	660 m cored RRP (132/169) cable	2 wks	25/11/13	06/12/13	1				ъ						4				
70	Insulated cable (Mica & 11-TEX)	2 wks	09/12/13	27/12/13	1				*										
71	Coil 4 (132/169)	68 days	30/12/13	02/04/14									-		201				
72	wind/cure	14 days	30/12/13	16/01/14	1					<b>*</b>								4	
73	React	24 days	17/01/14	19/02/14	1					<u> </u>								1	
74	Splice	2 days	20/02/14	21/02/14	1						5							201	
75	Impregnate	13 days	24/02/14	12/03/14	1						<b>*</b>				I F			2	
76	Inspect	5 days	13/03/14	19/03/14	1							Δ,							
77	Instrument	2 wks	20/03/14	02/04/14	1							<u> </u>	<b>-</b>		l un			Q	
78	Coil 5 (132/169)	68 days	31/01/14	06/05/14	1										I I			Aug-Sep	
85	collared coil assembly	3 wks	07/05/14	27/05/14	1										⊨\ ===			$\sim$	
86	1-in-1 cold mass assembly	2 wks	28/05/14	10/06/14											<b>*</b>			ы	
87	Cold test 1-in-1	6 wks	11/06/14	22/07/14	1 🗖 -	-in-1 #2 Test	F								<b>&gt; *</b>		<b>ר</b>		
88	Disassembly	2 wks	23/07/14	05/08/14			•									L 👗	h	$\checkmark$	
89	2-in-1 Model 1 (RRP 108/127 & 132/169)	50 days	06/08/14	14/10/14	1												÷—	-	<b>—</b>
90	2-in-1 cold mass assembly	4 wks	06/08/14	02/09/14	1							_					*		
91	Cold test 2-in-1	6 wks	03/09/14	14/10/14	2.	-in-1 #1 Test	-											<b>*</b>	<b></b>
					1														I

#### M. Karppinen CERN TE-MSC



### CERN 2<sup>nd</sup> 2-in-1 Model Schedule









#### **Start with winding trials using Cu-cable:**

- o simplified trials
- o coil with bare cable
- o first practice coil with insulated Cu-cable to react and pot (PC-1).
- First Nb<sub>3</sub>Sn practice coil with possibly low-performance (cheaper) cable (PC-2)
- First "real" coil (PC-3) to cold test as a single coil (mirror?)
- \* Four (or eventually more..) more coils for 2 collared coils to construct the full-scale proto and test it around Mid-2016.
- \* the 5.5 m schedule is compatible with the present LMF plans including the major procurements
- Additional coil production lines will be required for series magnets
- It is also vital to get the industry on board during the prototype construction to be ready for the series units



### **CERN 5.5 m Prototype Schedule**



	ID Task Name	Duration	Start	2014 2015										2016 Ist Quarter 2nd Quarter 3			
				uarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	and Quarter	4th Quarter	1st Quarter	2nd Quarter	3rd Quarter	4th Quarter	1st Quarter	2nd Quarter	
				May Jur	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan   Feb   Mar	Apr May Jun	Jul Aug Sep	Oct Nov Dec	Jan Feb Mar	Apr May Jun	
	5.5 m Prototype	957 days	07/01/13										<u> </u>				
3	Design & Procurement	340 days	07/01/13	<b></b>				<b>_</b>									
4	tooling design	36 wks	07/01/13					-									
5	procurement	36 wks	19/08/13													4	
6	Cu-Cable 1450 m	4 wks	15/11/13	1		_											
7	Winding trial 1 (Simplified)	7 wks	29/11/13	1		9											
8	Winding Trial 2 (Bare cable)	3 wks	03/02/14	1	1												
9	Practice Coil 1 (Cu)	140 days	13/12/13	1		-											
10	Insulated cable (Mica & 11-TEX)	4 wks	13/12/13	1	1	🛎											
11	Wind/cure	4 wks	10/03/14	1			<b>1</b>										
12	React	36 days	07/04/14		I												
13	Splice	3 days	27/05/14					<u> </u>									
14	Impregnate	3 wks	30/05/14					<u> </u>									
15	Inspect	5 days	20/06/14					ð									
16	620 m cored WST cable	2 wks	28/03/14				•										
17	Practice Coil 2 (Low Perf. Nb3Sn)	170 days	11/04/14					1		÷							
18	Insulated cable (Mica & 11-TEX)	4 wks	11/04/14		I			-									
19	Wind/cure	3 wks	11/08/14						_								
20	React	36 days	01/09/14							•							
21	Splice	3 days	21/10/14	-	1					÷							
22	Impregnate	3 wks	24/10/14							-							
23 24	Inspect Instrument	5 days 2 wks	14/11/14 21/11/14							<b>*</b>			$\mathbf{O}$				
								· + ∣									
25 26	1860 m cored RRP 132/169 cable	25 days 195 days	15/05/14 19/06/14										5				
26	Practice Coil 3 (RRP 132/169) 620 m Insulated cable (Mica & 11-TEX)	4 wks	19/06/14					1 😨			r I						
28	Wind/cure	4 wks 3 wks	21/11/14							1							
29	React	36 days	12/12/14										e				
30	Splice	3 days	02/02/15							_			un				
31	Impregnate	3 wks	05/02/15								<u> </u>		2				
32	Inspect	5 days	26/02/15		1						*	′	LÍ.				
33	Instrument	2 wks	05/03/15										ay				
34	Mirror Magnet	80 days	19/03/15	1									0				
35	Mirror Coldmass Assembly	5 wks	19/03/15	1	1						1	_					
36	Cryostat assmebly Mirror	5 wks	23/04/15									<u> </u>					
37	Cold test Mirror	4 wks	28/05/15	Si	ngle co	il Oua	lificati	on Tee					11				
38	Disassembly	2 wks	25/06/15		ingle co		micati	on res					취				
39	Coll 4 (RRP 132/169)	344 days	17/07/14	1										_			
40	620 m Insulated cable (Mica & 11-TEX)	4 wks	17/07/14	1					<b>L</b>				-11				
41	Wind/cure	4 wks	09/07/15	]													
42	React	36 days	06/08/15											L			
43	Splice	3 days	25/09/15											6			
44	Impregnate	3 wks	30/09/15														
45	Inspect	5 days	21/10/15											5_			
46	Instrument	2 wks	28/10/15		1									-			
47	Coll 5 (RRP 132/169)	344 days	14/08/14						•					÷			
55	Collared Coil 1 (RRP 132/169)	30 days	09/12/15											-	÷		
56	Coil assembly	2 wks	09/12/15														
57	Collaring	3 wks	23/12/15		1										T+		
8	Inspection	1 wk	13/01/16										L		•		
9	1860 m cored PIT-114 cable	5 wks	06/08/15														
0	Coll 6 (PIT-114)	104 days	10/09/15										-	-	-		
8	Coll 7 (PIT-114)	104 days	08/10/15											•		Ц.	
76	Collared Coil 2 (PIT-114)	30 days	02/03/16												-	TT .	
7	Coll assembly	2 wks	02/03/16													L	
78	Collaring	3 wks	16/03/16												-		
79 30	Inspection	1 wk 6 wks	06/04/16 13/04/16		1											<b>1</b>	
<i>.</i>	Coldmass assembly Cryostat assembly	6 wks	25/05/16		_												
81							long 2										

23-24 Sep 2013

M. Karppinen CERN TE-MSC



### Summary



- Two 1-in-1 model magnets have been constructed and tested at FNAL reaching 10.5 T and 11.7 T. Reasons for conductor degradation under investigation
- Two 1-m-long 2-in-1 magnets scheduled at FNAL by Mid-14
- FNAL coil fabrication technology has been transferred to CERN and the first Nb<sub>3</sub>Sn coil has been completed
- Commissioning of infrastructure longer than expected
- First CERN 2-m-long 1-in-1 magnet test expected in Mar-13
- Several R&D topics are being investigated as part of CERN 11 T magnet development serving also the interest of other HFM programs
- Two short 2-in-1 magnets scheduled by the end of 2015
- Work on the 5.5-m-long tooling is underway and the first
  5.5-m-long 11 T prototype dipole is expected by Mid-2016

