



Commissioning and initial experience with the ALICE on-line

V. Altini, T. Anticic, F. Carena, W. Carena, S. Chapeland, V. Chibante Barroso, F. Costa, E. Dénes, R. Divià, U. Fuchs, I. Makhlyueva, F. Roukoutakis, K. Schossmaier, C. Soós, T. Kiss, P. Vande Vyvre, B. von Haller

For the ALICE Collaboration



CHEP - Prague March 2009







- •ALICE experiment
- •ALICE online systems
- Detector Commissioning
- •Global Commissioning
- Lessons from 2008
- •Goals for 2009
- Conclusion

ALICE @ LHC Point 2









- General-purpose heavy-ion detector
 - Study of strongly interacting matter and the quark-gluon plasma in nucleus-nucleus collisions at the LHC
 - Detector designed to cope with the highest particle multiplicities anticipated for Pb-Pb reactions
- Complex experiment for online systems
 - •18 detectors (last one being installed now)
 - 10 detectors providing input to the trigger
 - •2 types of beams: pp and Pb-Pb
 - 3-level hardware trigger and 1 High-Level Trigger firmware/software
 - Multiple partitions and multiple detector clusters
- Not surprisingly: complex commissioning !













Data Quality Monitoring

DQM framework is ready. Not yet used routinely by all detectors.





11



Electronics Logbook

Online status display of TRG and DAQ running conditions



Run statistics

eLogBook:

From replacing the paper logbook to a powerfull data mining tool





Detector Commissioning



Standalone commissioning

- Services: cabling, cooling, power supplies, etc
- Detector hardware, firmware, software
- Interfaces to online systems
- Online commissioning process
 - Control procedure up to the state "Ready for Data Taking"
 - Exposed to variety of trigger (cosmic, pulser up to 40 MHz, random)
 - Data taking stability tests
 - Calibration procedure
- Integration to global partition





Global Commissioning



- Exercise stability
 - Detectors
 - Services
 - Online systems
 - •23 systems (18 detectors and 5 online systems) \Rightarrow 0.97 ²³ < 0.5 !
- Measure performance
 - Detector readout time and event size
 - Online systems
- Take data
 - Cosmic data for detector alignment
 - Detector calibration (E.g.: TPC calibration with krypton or laser)
- Organize operation



ALICE Control Room





Cosmic Run I (Dec '07)



Global runs in 2 weeks

14 detectors participating

10-60 hours of data taking $-1-20 \times 10^6$ triggers



ALICE



Cosmic Run I



• TOF

 Comparison of hit time distribution in ACORDE and random triggers

• SPD

 Comparison of number of clusters per event in the 2 SPD layers





```
TOF - 1824 channels - 91793 random triggers - FEA THR = 0.8 V
```



Cosmic Run II (Feb-Mar '08)



Global runs in 5 weeks

13 detectors participating

60-150 hours of data taking $-2-50 \times 10^6$ triggers





Cosmic Run II



- Cluster distribution
- Resolution over drift length
- Muon Tracking
 - Online data monitoring vs offline analysis





Cosmic Run III (May-Oct '08)



Global runs in 23 weeks

16 detectors participating

60-1250 hours of data taking $-5-3500 \times 10^6$ triggers



ALICE









Global runs with all detectors are still difficult to achieve









Stability of global runs has improved substantially during the cosmic runs







Lessons from 2008



- Services
- Detectors:
 - Work in progress for firmware and software \Rightarrow readout time and zero suppression (event size)
 - Noise and grounding
- Online systems:
 - Control scalability: some systems isolated and load distributed
 - CPU needed for data formatting: late decision to format data into reconstruction ready format CPU needed higher than anticipated Price to pay for allowing single pass offline analysis
 - Spurious triggers : fixed during cosmic run
 - Global sequences of detector control still in the phase of being defined \Rightarrow Not yet fully automated
- But a successful commissioning of the whole experiment and ready for startup in September '08







- Ready for a nominal data taking year
 10 months pp + 1 month HI
 - Full deployment of the DAQ system: $40 \Rightarrow 100$ % performance
 - Increase of HLT CPU power
- Improve feedback to shift crew (DQM deployment)
- Reduce the size of shift crews
 - Group of detectors
 - Automation of atomic operations (configuration, calibration)
 - Automation of global planning
- Central system for the configuration/archiving of all the trigger detectors and the corresponding trigger processors







- ALICE became reality after almost 15 years of design and installation
- Commissioning of detectors and online systems lasted from Dec '07 to Sep '08. Work intensive !
- Online systems contributed to the detector commissioning, alignment, and calibration
- Experiment ready to start with beam in September '08
- Will be ready again in September '09 !