

MQXFS Assembly Procedure

J.C Perez

HL-LHC/LARP International Review of the MQXF Design December 10-12, 2014 CERN

N. Bourcey, B. Favrat, P. Ferracin, Ph. Grosclaude, M. Juchno, L. Lambert, P. Moyret, J. Parrilla Leal, N. Peray, T. Sahner, A. Temporal and many others ...



OUTLINE

MQXFS model magnet assembly at CERN

- □ Main assembly steps (Slide 5 to 19)
- □ Status on components and tooling (Slide 20 to 24)
- Possible MQXFB assembly procedure (7 meter long magnet)
- □ 150 mm mechanical model assembly and cooling to 77K
- □ First MQXFS mechanical assembly at CERN using aluminium dummy coils

Conclusions



3

MQXFS cross section

- Coils
- Coils pole keys
- □ Aluminum collars
- □ Iron & stainless steel pads
- □ Iron masters, alignment and loading keys
- Iron yoke
- □ Aluminum shell
- □ Stainless steel shell and welding strip



See detailed presentation on magnet components from Paolo Ferracin and shell welding operation from Herve Prin presentation





4

Shells preparation for vertical assembly



- The shells are instrumented with the strain gauges before starting the assembly sequence
- 4 short alignment pins are inserted and glued in the lower inner shell slots of the first shell to be installed on top of the assembly base plate
- The relative angular alignment between the 2 shells is guaranteed by the use of the 2 long pins





1/4 yoke lifting and preparation for insertion



The yokes are inserted on the shells in vertical position





1/4 yoke insertion



High Luminosity LHC U.S. LARP



J.C. Perez

3rd and 4th ¼ insertion







Bladders support structure for shell loading

A cross-shape support inserted in the structure is used to support the bladders for shell pre-loading







4 bladders 1549 mm * 57 mm will be used during shell pre-loading operation.



Temporary yoke keys are inserted in the yoke gaps

9

Lifting and rotating Yoke and Shell assembly







Coils and collars preparation



 Ground insulation layers (G10 + Kapton) are glued to the aluminum collars inner radius





Coils rotation

An existing assembly table used for the 11 T dipole project has been adapted to rotate and position MQXFS coils.















High L**umi**nosity

HC

U.S. LARP





J.C. Perez

Coil pack assembly: mounting the coils







U.S. LARP

High L**umi**nosity 2 + 2 coils equipped with ground insulation and pole keys are positioned on top of the lower 1/4 pad and collar assembly

Even if such a tool may be not be 100% needed to perform the coil pack assembly on short model magnets, the concept will be tested and proven to be scalable in view of 7 m long magnets assembly.

J.C. Perez

Collars and pads assembly



The same sequence is used to assemble and bolt the iron pads around the collars. The assembly tooling is designed to provide accurate alignment of all components during the assembly process.



Masters and coil pack preparation





Coil-pack insertion concept

Linear guides will be used to slide the coil-pack into the yoke cavity. The heat exchanger holes are used to support and align the linear guides rails





Aluminum profile interface to align the rail into the heat exchanger hole

Linear guides and rails







J.C. Perez

Bladders operation CERN concept





Coil pack inserted in the yoke Master clamps are removed



2 lateral bladders are pressurized to insert the remaining nominal keys





Insertion guiding rails are removed





Lower bladder is

are inserted.

pressurized. Top and bottom nominal keys

4 Bladders operation for final loading

Bladders and slip shims are removed after full loading operation



Longitudinal loading & connexion box

View of the MQXFS Magnet equipped with the longitudinal pre-loading system

- The final assembly geometry will be checked using a Faro arm or/and with a Leica Laser tracker.
- Precise Ø6 H7 holes have been drilled on both magnet extremities (yoke, pads and collars)
- Existing holes in coil poles can be used to install Leica's reflectors





MQXFS model magnet assembly at CERN

□ Main assembly steps (Slide 5 to 19)

□ Status on components and tooling (Slide 20 to 24)

- Possible MQXFB assembly procedure (7 meter long magnet)
- □ 150 mm mechanical model assembly and cooling to 77K
- □ First MQXFS mechanical assembly at CERN using aluminium dummy coils

Conclusions



First batch of aluminium Shell



- 4 shells have been ordered and CMM controlled at CERN and LBNL (cylindricity and pins slots position out of tolerance)
- The shells have been instrumented with strain gauges





New outer aluminium shell configuration



- 4 extra forged-rolled aluminum cylinders have been ordered ad are being machined
- One 774 mm shell and two 387 mm half shells will be used for MQXFS model assembly with real coils
- Using 3 shells instead of 2 for the 1.5 m model will not significantly impact the assembly procedure nor the schedule





Assembly tooling status





for assembly operation





Ground insulation forming tool ready







Bladders, shims and slip-shims ready



Yoke & shell support to flip from vertical to horizontal position ready.





Ground insulation and instrumentation table ready





Lifting tooling status







Components for first assembly using instrumented aluminum coils ready





Collars and Pads







Iron yokes

MQXFS model magnet assembly at CERN

- □ Main assembly steps (Slide 5 to 19)
- □ Status on components and tooling (Slide 20 to 24)

Possible MQXFB assembly procedure (7 meter long magnet)

- □ 150 mm mechanical model assembly and cooling to 77K
- □ First MQXFS mechanical assembly at CERN using aluminium dummy coils

Conclusions



Assembly of LQ structure







MQXFB yoke & shell assembly concept

Modules composed by 2 aluminum cylinders (2 different module lengths) will be assembled on vertical position and then flipped to horizontal position



Each individual subassembly will be positioned on its support structure and assembled with the adjacent one using precision rails and linear guides.





The subassembly rods will be replaced by longer ones using small hydraulic cylinders

See presentation from Dan Cheng



MQXFB assembly concept



- 3 different Bladders length will be required for magnet assembly
- The option to use 0.5 mm SS sheets for bladders production is being investigated and tested (cheaper)
- ≈ 0.8 m long shells seems to be the best compromise (raw material and machining cost, vertical assembly)
- 1.5 m long structure components subassemblies is our preferred solution (see presentation from P. Moyret)



- 7 meters coil-pack assembly and insertion procedure will be scaled-up from model magnet assembly
- No show stoppers have been identified

See presentation from Dan Cheng



J.C. Perez

MQXFS model magnet assembly at CERN

- □ Main assembly steps (Slide 5 to 19)
- □ Status on components and tooling (Slide 20 to 24)
- Possible MQXFB assembly procedure (7 meter long magnet)
- □ 150 mm mechanical model assembly and cooling to 77K
- □ First MQXFS mechanical assembly at CERN using aluminium dummy coils

Conclusions



Mechanical 150 mm mock-up



HC

U.S. LARP

30

MQXFS model magnet assembly at CERN

- □ Main assembly steps (Slide 5 to 19)
- □ Status on components and tooling (Slide 20 to 24)
- Possible MQXFB assembly procedure (7 meter long magnet)
- □ 150 mm mechanical model assembly and cooling to 77K
- □ First MQXFS mechanical assembly at CERN using aluminium dummy coils

Conclusions



First yoke and shell assembly at CERN(1/2)







First yoke and shell assembly at CERN(2/2)







LN₂ tests in SM18



After Xmas brake, 3 cool-down to 77K, with different pre-stress applied to the aluminium dummy coils, are foreseen at CERN in SM18 LN₂ test station





Conclusions

- MQXFS assembly procedure has been defined and partially tested during the assembly of the 150 mm mock-up
- 2 identical structures and 2 sets of assembly tooling are operational (CERN & LBNL)
- CERN assembly tooling (except coil pack assembly & insertion table) has been delivered
- Coil-pack insertion table will be operational by mid December 2014
- Coil-pack assembly tooling is due for April 2015
- CERN team has started the mechanical assembly with instrumented aluminium dummy coils in December
- After Xmas brake, 3 cool-down to 77K, with different pre-stress applied to the dummy coils, are foreseen in CERN SM18 LN₂ test station
- The 150 mm mock-up equipped with segments of coil #101 will be used to better understand the structure behaviour and define shimming values
- Tooling design and assembly procedures are scalable for longer magnets



Thank you for your attention



The HiLumi LHC Design Study is included in the High Luminosity LHC project and is partly funded by the European Commission within the Framework Programme 7 Capacities Specific Programme, Grant Agreement 284404.



36



