

Overview of SciFi Power & Cabling

A. Pellegrino on behalf of SciFi group, 19-2-2015

- o introduction
- o FE Power requirements & cabling
- o SiPM bias
- o data fibers

Introduction to SciFi Talks


- Overview of SciFi Reports:

- power, electronics, cables [*this talk*, A. Pellegrino, Session I]
- cooling, pipes, etc. [B. Verlaat, Session II]
- dismantling, integration, installation [R. Walet, Session III]

Before going into those details, in this 1st talk a short intro

- LHCb SciFi Overview
- SciFi tracking stations
- C-Frames
- Modules
- Read-out Box

SciFi Overview





RE-USE: Bridge

- NEW
- C-Frames
- Detector
- Cable tray
- Etc.


RE-USE: Table

Tracking Stations



3 tracking stations T1, T2, T3


C-Frames



12 C-Frames

(4 C-frames per station,
2 per side A/C)

SciFi Modules





12 modules per C-Frames

Every module contains
two Read-out Boxes (ROB)

Readout Box (ROB)

two ROB's per module



To give you an idea...

- **Module**
 - *Interfaces/boundaries defined and agreed upon*
 - *work on tooling and prototypes (EDR in June)*
- **Read-out Box**
 - *Prototype design ready*
 - *Industry contacted, collecting quoted offers*
 - *Detailed test plan being worked on*
 - *FE electronics prototype ready by June*

We concentrated on this until now

- **Cooling**
 - **Serial vs Parallel cooling analyzed**
 - **Parallel cooling preferred**
 - **New calculations and system design in progress**
- **Cabling**
 - **overview presented at this workshop**
- **Infrastructure**
 - **started working on C-Frame and infrastructure design**

Starting working on this


Power & Cabling

○ Overview of SciFi Reports:

- power, electronics, cables [*this talk*, A. Pellegrino, Session I]
- cooling, pipes, etc. [B. Verlaat, Session II]
- dismantling, integration, installation [R. Walet, Session III]

FE Bias

Several DC-DCs on FE



power consumption per ROB estimated ~90 W
with 10% safety factor : **~100W**

(details on Wilco's presentation 8 Dec 2014)

Power → FE

1 FE : ≈ 90 W

1 Maraton ch. → 2 FEs

200 W including power loss
($\sim 67\%$ of max)

4 cables [$2 \times (0,6V)$] per FE
Total

144 channels V : ~ 30 kW


12 Maraton's

Comparison with OT

of Maraton's : 6 → 12

2× volume of cables in rolling ducts

2.7× volume of cables from distribution box to FEs



12 rectifiers




12 power boxes, 6 per side




Power → SiPM

Caen A1539P Module, DB25 Multipin



16 SiPMs per ROB

supply-to-C-Frame will probably go via multi-wire common-shield cables e.g. SCEM
04.31.52.100.5 - CABLE HT 56X0.14MM2 3KV



4 SiPMs per channel

~55 V × 10 mA

1152 channels + spares

(OT: 224 ch., 8×A1733BPLC, 3 mA)

jumpers to exclude faulty groups of 64 ch

(OT: 1→8 patch, can exclude 32ch groups)





Data Fibers

still under discussion, but it could look something like this
(neglecting control fibers)

- 40 ribbons per C-Frames (10 per quadrant)
- 240 ribbons per side A/C
- # of trunks depends on patching and spares (max 48)

10 ribbons per quadrant
(min. 2 spares per ribbon)



Patch Panels

- OT
- data and control fibers patched 3 times:
 - at **C-Frame**, under the bunker, in counting room
- HV cables only patched in counting house and C-Frame
 - patch panel 1→8 in counting room (with manual jumpers)
- LV only patched at C-Frame (power supply under bunker)



- for SciFi we naively expect
- data and ctrl fibers patched 3 times:
 - at C-Frame, under the bunker, in counting room
- SiPM bias distribution to be defined
 - patch panel 1→4 (with jumpers)
- LV only patched at C-Frame (power supply under bunker)

Outlook & Open Issues

- *wrt OT: more cables to FE, more cables to SiPMs, more data fibers*
- **implications for SciFi C-Frames**
 - **more and/or larger rolling ducts**
 - **larger patch panels on C-Frame**
- **larger amount of long-distance cables**
- **larger amount of racks in D3**
- **define patch panels under the bunker**
- **define patch panels in counting room**
- **define time scale of long-distance wrt rolling ducts filling**
- **cable database?**
 - **ready to use before/during cable installation?**