

<u>Phase 2 silicon pixel-strip</u> <u>thermal mock-up module:</u> <u>building and testing</u>

- The pixel-strip module
- A realistic thermal mock-up
- Simulation and data results
- Conclusions & Outlook


#### Forum on Tracking Detector Mechanics 2015 http://forum2015.nikhef.nl 15 - 17 June 2015 Amsterdam Science Park

G.Bolla, D.Butler, G.Derylo, H.Gonzales S.Gruenendahl, M.Johnson, R.Lipton, S.Timpone (Fermilab) J.Hogan, M.Narain (Brown)

#### Fermilab Andreas Jung, June 16th, 2015


## **HL-LHC:**Silicon detector upgrades

Rebuild silicon detector for high luminosity running of the LHC Less dead material, higher "granularity" & improve resolution by ~1.5




- $\rightarrow$  Innermost **Pixel** detectors
- $\rightarrow$  **Pixel-strip** and outermost **Strip-strip** detectors with intrinsic trigger capabilities at low p<sub>-</sub>

## HL-LHC:Silicon detector upgrades





## Pixel-strip module (PS)



Pixel-strip prototype to answer:


Aluminium Carbon Fibre matches CTE of silicon

Cooled from bottom – thin walled AI-CF structures – sufficient ? Complex module – test assembly ?



## Module prototype

- AI-CF (Metgraf 4-230) has comparable CTE to silicon
  - Carbon fibers are randomly oriented in a plane
  - Test both orientations in terms of thermal performance
  - Machined with wire EDM
    - Precision of first test pieces: 100  $\mu\text{m}$








## Realistic PS module heat loads

Heat source	<u>"CERN"</u> 3 W	<u>"FNAL"</u> 3 W	
<ul> <li>16 Pixel readout chips:</li> <li>16 Strip readout chips:</li> </ul>	0.5 W	0.5 W	<u>Remarks:</u> Leakage currents corresponds to end of life conditions
• GBT:	0.5 W	0.8 W	
<ul> <li>2 Concentrator:</li> </ul>	0.4 W	0.4 W	CONTINUONS
<ul> <li>DC-DC converter:</li> </ul>	2 W	1.2+0.8 W	
<ul> <li>Optical drivers:</li> </ul>	0.3 W	added to GBT	
<ul> <li>2 Leakage current:</li> </ul>	<u>1.0 W</u>	<u>1.0 W</u>	
Total ("Nominal" or "1":	7.7 W	7.7 W	







# Pixel-strip prototype

Complex Pixel-Strip assemply:


- Using AI-CF (good CTE in x-y plane)
- Carbon f ber (3 layers, total is 200  $\mu$ m)
- Raw silicon (2-side polished, 200 μm)
- Added ~880 wire-bonds (reality: 1000)







### PS module & support structure




Custom built support (rod) structure:

- Based on Carbon foam, Rohacell, Carbon fibre sheet
- 3.2mm pipes w TC5022 (1<sup>st</sup> iteration)
  - Future rod will use smaller pipe diameter & Carbon hex-cell or Airex foam since Rohacell is not radiation hard
- PS module mounted with "re-workable" Laird film




## Rod support structure

- Small rod structure to test PS mock-up module
- $\rightarrow$  130 x 200 mm size




#### Remarks:

- $\bullet$  Carbon Fiber sheets are 200  $\mu\text{m}$
- Stress relief for 3.2mm pipes
- For now used Rohacell, needs to replaced (not rad. hard)
- Carbon foam is 25mm wide:
  - Difficult to machine the grooves
  - Use TC5022 in grooves





## Cross section through PS module



Materials used:

- CF sheets 4 layers, 200 mu thick
- Raw silicon, 200 mu thick
- AI-CF spacers
- Heaters
- Kapton representing Flex circuits
- 3mm self-adhesive copper tape


Assembly:

- Laird film between base plate and silicon Pixel sensor
- Silicon "RO chips" glued with "Alcad" to silicon "Pixel" layer
- AI-CF structures glued with Epoxy DP110 (or DP190)
- PS module to support structure: Laird film



## Cross section through PS module

#### Cross section through entire "stack":








### Complete test structure

ANNI

Bottom side "Pixel holes"

Completed setup: 30 RTDs + 18 heaters

Putting down Top side RTDs "Strip"






## CO2 test setup

System modified for Phase II tests and FPIX production system:

- Existing setup allowed for large flows of 3.5g/s at 0.5 bar
  - But difficult to ensure 2-phase
  - Coolant is -20°C presented results are using this setup








#### CO2 test setup

#### $\rightarrow$ Change rod pipe to 2.2mm $\rightarrow$ ensure 2-phase cooling

System modified for Phase II tests and FPIX production system:


- Existing setup allowed for large flows of 3.5g/s at 0.5 bar
  - But difficult to ensure 2-phase
    - $\rightarrow$  Modifications to existing CO2 test setup:
    - More space for at least 2 setups at same time
    - Allow higher pressure drops: Needed to connect similar test systems
    - Allows lower flows 
       → Can now ensure 2-phase cooling






## Simulations


- FEA model uses hexagons (bricks) instead of tetrahedrons (pyramids)
- Meshing is complex use SolidWorks with slightly simplified structure
- Typically model half the module (symmetric along "long axis")
  - In reality slightly asymmetric but very small effect
- Inside of pipes is held at -20 °C
- Most of the losses at epoxy joints !








#### Simulations




# Sensor equipment





## Sensor equipment

#### Pixel-sensor (bottom side):




Sensor spacing on quarter line: 8.5 mm, first one at 7.5mm



 $\Delta T (C)$ 

## Data results & simulations




- Observed 10°C ΔT is according to specifications/design
- Linear response of the PS module: 2x heat load  $\rightarrow$  2x temperature



 $\Delta T (C)$ 

## Data results & simulations




#### Observed 10°C ΔT is according to specifications/design

- Linear response of the PS module: 2x heat load  $\rightarrow 2x$  temperature Simulations (straight lines) by M. Johnson:
- "15.4W Sim" has perfect connection between pipe and foam
- "7.7W Sim" has 50% air bubbles with diameter of 50 I m
- $\rightarrow$  "Shape" is close to data, bad pipe foam connection
- $\rightarrow$  About a constant 2°C offset for pixel and strip, thickness of epoxy layers

A. Jung Phase 2 pixel-strip thermal mock-up module: building & testing



## Temperature difference




Temperature differences of 10 "Pixel" RTDs to 10 "Strip" RTDs:

- Differences of about 1-2 °C, efficient cooling of strip layer
- Optimistic simulation (perfect tube-foam connection) off
- More realistic simulation (50  $\mu m$  air gaps) matches quite well



## Temperature difference



Temperature differences of 10 "Pixel" RTDs to 10 "Strip" RTDs:

- Differences of about 1-2 °C, efficient cooling of strip layer
- More realistic simulation (50  $\mu$ m air gaps) matches quite well
- No significant dependence on heat load




- Built realistic PS modules, good thermal behavior according to specifications
- Simulations are encouraging in their agreement to data
  - Pipe-foam connection crucial (more of a topic with 2mm pipe)





# Summary & Outlook

- Built realistic PS modules, good thermal behavior according to specifications
- Simulations are encouraging in their agreement to data
  - Pipe-foam connection crucial (more of a topic with 2mm pipe)
- Now working on & next steps:
  - Modified CO2 system to reduce flow (ensure 2 phase)
  - Improved rod support structure with 2.2 mm pipes
  - Building more PS modules for other institutes (for Lyon)
  - Test single cooling pipe mounting structures (from CERN)






#### Backup




## HL-LHC upgrades


- Diff cult to project, depends on physics outcome of Run II:
   SM precision tests & BSM scenarios
- SM precision tests & BSM scenarios
   "Koop rupping" doog pot work
- "Keep running" does not work Need improved detectors

 Need very precise information from tracking devices in the trigger












### Effect of "ambient"



February 02/17 data taking:


- Same settings, but with "foil", "noFoil", "foil+preheat"
- Derive "ambient effects" and use as systematic uncertainty in the following
- Differences of 0.5 degree for Pixel and 1.25 degree for strip (sort of expected)

Inside of slot at -20 C

1-3 degree warmer than PS module

# Tilted barrel PS support structure

- Geometry is not symmetric so modeled full structure
- Cooling pipe is at 90 degrees compared to slotted stave
- No pipe and epoxy in slot so not completely comparable to previous plot



29

