


Update on WA105

WA105



Sebastien Murphy

on behalf of the WA105 Collaboration



WA105

22 institutes 122 physicists



ETH
Eidgenössische Technische Hochschule Zürich
Swiss Federal Institute of Technology Zurich



Ciemat
Centro de Investigaciones
Energéticas, Medioambientales
y Tecnológicas



WA105 aims at demonstrating the operation of the novel large liquid argon double-phase time projection chamber (DLAr TPC) and the modern techniques for magnetised MIND detectors.



- * A new concept for an **affordable and underground liquid argon detector** has been proposed, developed over several years, and tested on ever growing prototypes.
- * In the coming years we intend to focus on the realisation and operation of **large-scale demonstrators**, whose technical designs have been presented in a comprehensive “Technical Design Report” (CERN SPSC-2014-013, SPSC-TDR-004).
- * Two independent demonstrators have been approved:
 - 6x6x6m³ DLAr double phase liquid argon TPC
 - BabyMIND magnetised iron neutrino detector
- * Efforts on this scale aimed at **demonstrating novel concepts are best realised on surface** in laboratories. The WA105 demonstrators would be the “**last step**” before an **underground deployment of tens of kton-scale detectors**.
- * **They represent concrete work and achievements upon which contributions to the international LBL programmes will be proposed.**

Build and operate a large scale prototype to demonstrate the feasibility of LAGUNA/LBNO DLAr TPC design for O(10kt) detectors

- * A 1:20-scale of 20kt “demonstrator” & industrial solutions
- * Technical proof-of-principle:

- * Purity in non-evacuated tank
- * Large hanging field cage structure
- * Very high voltage generation
- * Large area charge readout
- * Accessible cold front-end electronics
- * Long term stability of UV scintillation light readout


Compared to LAGUNA/LBNO 20 kton DLAr





Some detector parameters:

- Insulated membrane tank → inner volume 8.3x8.3x8.1 m³
- Active area 36 m²
- Drift length 6 m
- Total LAr mass 705 ton (~300 ton active)
- Hanging field cage & readout plane
- # of signal channels: 7680 in 12 signal FT
- # of PMTs: 36

PMT light readout (APC, Barcelona, CIEMAT, KEK, LAPP)




Electronics and DAQ for charge readout (IPNL, Jyväskylä, Oulu)



SiPM light readout (INR, Genève)

Field cage (Bucarest, Saclay, IFINHH)


membrane tank (ETHZ, CERN)




HV (LPNHE, ETHZ)




anode deck suspension (LAPP)




charge readout sensors (ETHZ, Saclay)



all groups involved in software and data analysis



chimneys and feedthroughs

* Serves as tool to **speed up some of the technical implementation work** needed for the 6x6x6 m³. For example:

- Routine procedure for mass production, QA tests and calibration of the LEMs.
- Similar considerations for cryogenic installation, feedthroughs, thermodynamic conditions of the membrane tank, ...

4.7 m

* Has been very useful to anticipate all the legal and technical aspects related to the contracts for the realisation of a membrane cryostat at CERN under the GTT license. **will allow a much easier and smoother tendering procedure for the 6x6x6 m³**


4.9 m

Outer structure was installed before christmas



click here to download movie:



[outer-structure-construction-time-lapse](#)




and insulation + membrane + top-cap by April

Updated:


- SPFT (preliminary from LAPP)
- SCFT (preliminary from Franco)
- CPFT (CF400)









data collected on a 40x80 cm² DLA_r TPC at CERN

(3) charges **collected** on specially designed two view anode. Both views see the same amount of charge and have **identical signals**



(2) charges **amplified** in Large Electron Multiplier E field of ~ 30 kV/cm




(1) charges **extracted** to vapor phase E field of ~ 2 kV/cm

an important detector component that will be tested in the 3x1x1 is the charge readout plane. The extraction grid LEM and anodes are all combined in one module adjustable to the LAr level: the charge readout plane (CRP)



extraction grid-LEM and anode all in one single module

50x50 cm² LEM+anodes mounted in readout modules of 1m² on a 1x3 m² frame



The same principle will be adapted to the LBNO-DEMO. We will learn from the “prototype” 3x1 m² CRP.



baseline idea is the same.
Fully active but independent **LEM/anode modules of 50x50 cm²**



From the point of view of the readout the goals can be largely summarised as:

- we want to **amplify** the drifting charges by operating **50x50 cm² LEMs** in pure Argon vapor at 87K with the largest possible stable gain
- we want to readout the amplified charges on **meter long strips** with the lowest possible electronic noise.

A. Badertscher et al. JINST 8 (2013)P04012,





From the point of view of the readout the goals can be largely summarised as:

- we want to **amplify** the drifting charges by operating **50x50 cm² LEMs** in pure Argon vapor at 87K with the largest possible stable gain
- we want to readout the amplified charges on **meter long strips** with the lowest possible electronic noise.


a) LEM optimisation

arxiv 1412.4402 Dec. 2014 (accepted in JINST)





b) Anode optimisation


C Cantini et al 2014 JINST 9 P03017




$dC/dl \sim 150 \text{ pF/m}$




Fitting function: $G_{eff}(E, \rho, t) \equiv \mathcal{T} e^{\alpha(\rho, E)x} \times \mathcal{C}(t) \quad \alpha(\rho, E) = A\rho e^{-B\rho/E}$





the LEMs have different charging up characteristics but all could be **operated stably at gains of at least 20.**

[arxiv 1412.4402 Dec. 2014](https://arxiv.org/abs/1412.4402)
(accepted in JINST)




Stainless steel frame

3 individual 1m² modules for anode+LEM

wire holders for extraction grid



SS frame











1m² modules



wire holders

The CRP mechanical frame arrived in the b 182 clean room in January. Was assembled successfully. First check of flatness, uniformity etc.. looks ok.







Charges need to be extracted from the liquid to the Ar vapour. Requires 2 kV/cm in the liquid, larger than the drift field of 500 V/cm.

Extraction grid


- ✓ 100 micron stainless wire with 3 mm pitch in x and y directions
- ✓ effect on gain uniformity tested in LAr on 10x10 cm² readout
- ✓ design has been extensively tested on a 1 m² prototype.




Fully operational with measured better than ISO 8 class.




the clean room inside b. 182



main room with CRP assembling area




view of the 4x1.5 m optical table for the CRP assembly



soldering station with extractors



view of the soldering room




This is the standard procedure that is being also applied to the 6x6m2 CRP.

for the **3x1x1** we have ordered 20 LEMs and 15 anodes from ELTOS. We need 12 of each.


LEMs have started to arrive by batch of 5 every week. We already have 10. Anodes are foreseen to arrive in a few weeks. We already have 2 prototypes.

For the 6x6x6 we will order 150 anodes and 200 LEMs. We need 144 of each. They will arrive by batch of 30 every months.


50x50 cm² LEM




50x50 cm² Anode



production & check of signal continuity
at ELTOS



soldering of connectors
at CERN SMT workshop + check
of connection (~2hrs per anode)



Storage in clean room

CNC drilling

mechanical polishing

permanganate bath +rinse

removes glass fibber from holes

Rims by global etching

acide sulphuric bath

passivation (Chromic acid)

Ni/Au plating

lessive (soap) bath at 68°C

ultrasonic bath DM water

removes grease

high pressure DM water

*removes dust/dirt in holes*baking 4h 180°C (only once)
or 1hr at 80°C (2nd,... iterations)*polymerisation of the glass fibber
(only 1st iteration) or drying*

HV test

goal no discharges at 3.5 kV

HV test not ok

HV test ok

storage + test


- at ELTOS: one machine with 6 independent drills each capable of ~7 holes per second. They can drill 6 50x50 LEM in 24 hours. The timescale for the rest of the procedure depends on the organisation of production line.

- Cleaning is done at CERN. procedure takes about 6hrs per LEM (mainly due to baking time)

each LEM is fixed on its own handling plate.




1) lessive (soap+ water 65 °C)
8 mins



2) Karcher DI water
~3 mins



3) rinse DI water
~1 min





4) U-bath DI Water 10
mins

5) Baking 180 °C 4 hours
(only 1st iteration)

6) HV test




7) Storage




LEM HV testing box.
(no flow of inert gas for the moment)

CAEN N1471H 50 pA current resolution. Labview controllable

before cleaning.





after cleaning.





So far we have a LEM that has been for 48hrs at 4 kV (40 kV/cm field). With few sparks. Sparking rate clearly decreasing with time.




Characterisation of the LEM gain with a ^{55}Fe source in warm gas (Ar:Isobutane 95:5)
 Here example of results on a 10x10 LEM



$E_{\text{LEM}} = 15 \text{ kV/cm}$, $E_d = 500 \text{ V/cm}$




distance between LEM & anode should be kept constant since it affects the gain. Here we had one module surveyed at the metrology lab. Planarity is within ~100 microns which is very acceptable in terms of gain variation (< 5 %).




nominal ~ 2 (LEM-anode) + 1 (LEM thickness) + $\sim .05$ mm \approx **3.05 mm**

camera through LEM hole



We have a range of sensors to be tested and calibrated (Pts, strain-gauge, cryo-cam, heaters, HV etc..). We use the NI compact-RIO system present on already many CERN experiments.



Testing of NI modules has started in collaboration with Gilles Maires (PH-DT)




	Sensor	# Sensors	Range	Res.	# pins on FT flange	Electronic Interface	# NI module	PVSS
Temperature	Pt10K	80	80-300K	0.1 K	256 D-SUB 50	-	28 NI9219	PCS Remote IO
	Pt1K	24						
Pressure	Keller PAA-21Y	8	0-2 bar	10E-05mBar	Dedicated plug	EV 06 Keller Display 4-20 mA	1 NI9208	PCS Remote Monitor
Liquid Argon level	coaxial	2	all the drift length	T.B.T (below 100 um)	26 SMA	Self made electronics 4-20 mA	2 NI9203	PCS
	parallel plate	11	2 cm					
Strain Gauge	350 ohm	24	? To be understood ?	T.B.T	96 D-SUB 50	Full Bridge	6 NI9237	PCS Remote IO
			visible range. 1Pt	few cm	10 pin each	USB	Real Time Controller	PCS
					20	-	3 NI9481+PSU	PCS
					-	-	1 NI9203	PCS





cryo camera +LED to visualise LAr surface






ASIC preamps in cold as close as possible to the anodes (~50 cm cable). fixed on insertable cards thus can be accessed without opening the detector. 1 chimney has 5 cards and reads 320 channels.





5 fake FE boards inserted from top




1st prototype arrived at CERN.
Card insertion tested ok.
Ongoing checks such as contacts, tightness,


“classic” LEM

RP-Well



5 Mohm/sqr Kapton resistive layer. 25 um thick.





Large spread of charge => possible to use resistive layers with larger resistivity





Open issues:

Gain? Resistivity in cold? Outgassing? gain Uniformity? Charge sharing? Is it possible to scale design to large 50x50 area LEM/Anodes?

Extra slides

test reconstruction on **fully contained events** from charged particle beam
(well defined primary particles and energies)

pions, electrons/positrons, protons, muons




- LAr TPC provide a fully active homogeneous medium
- High granularity $3 \times 3 \text{ mm}^2$ ← two orders of magnitude better than most granular calorimeters
 - e.g., CALICE AHCAL prototype has $3 \times 3 \text{ cm}^2$
- Additional handle from dE/dx




Opportunity to provide unprecedented measurements of hadronic shower development to HEP community

Some goals


- * Development of automatic event **reconstruction**
- * **test NC background rejection** algorithms on “ ν_e free” events
- * Charged **pions** and proton **cross-section** on Argon nuclei.




Stainless Steel
Cover?



✓ Following similar design to ArDM's drift-cage.
 ✓ Assembled off-site and delivered to CERN.




- 5 TPB coated Hamamatsu 8" R5912-02MOD PMTs.
- 2 of them serve as test bench for the 6x6x6m³ detector.
 - same mechanical base design that is foreseen in the 6x6x6m³
 - electronic bases that allow propagation of signal + HV through one signal cable (dedicated R&D ongoing in Spanish groups).




Plan to do the coating and QE test of the PMTs around May at CERN. Already have the setup ready and the experience from ArDM.

1. dipping the PMTs in LN2 to test mechanical resistance
2. QE measurement
3. Coating at CERN thin film lab (evaporation)
4. QE measurement after coating
5. test in GAR.



TPB coating



QE measurement




Test in GAR




$$E_{liquid} = \frac{\Delta V}{D \left[\frac{d_l}{D} \left(1 - \frac{\epsilon_l}{\epsilon_g} \right) + \frac{\epsilon_l}{\epsilon_g} \right]}$$

$E_l = E$ in liquid
 $E_g = E$ in gas
 at the interface $E_g \cdot \epsilon_g = E_l \cdot \epsilon_l$




variation of the extraction field in liquid as a function of liquid level.

Important remark: from this plot (and from 3l experience) it is clear the liquid level influences the extraction field very little. main situation to avoid: that the LAr “wets” the LEM.




example on the 10x10 cm² readout where the LEM center is still “wet” after filling.

amplification field (~33 kV/cm)





induction field (5 kV/cm)



to keep gain within +/- 5%
allowed to have E_{extr} between ~1.5 and ~2.5 kV/cm

extraction field (nom. 2kV/cm)




in red: ± 5% variation on the gain


important to keep fix distances between each stage.
=>one single mechanical frame

all plots from electric field scans on the 3I

amplification field (~33 kV/cm)




induction field (5 kV/cm)



in red: ± 5% variation on the gain



to keep gain within +- 5%
allowed to have E_{extr} between ~1.5 and ~2.5 kV/cm

extraction field (nom. 2kV/cm)



	distance [mm]	tolerance [mm]
anode-LEM	2	0.1
LEM thickness	1	0.01
LEM-grid	10	0.5
LEM-LAr	5 (from grid)	0.5
x-y position of the 50 cm ² modules	500	0.1

**Keep constant distances between each stage.
=>one single mechanical frame**




fit all cables in 3 cm diameter crossing pipe. possible to extend diameter for 6x6x6. But then limitation is number of connectors on the flange. Here CF 250 (NB occupancy of connectors not at maximum).

Identified company to provide custom made flanges with weldable connectors. Need to order 1st piece to check design.


CRP suspension feedthrough

design final. Parts ordered.
on schedule for summer 2015 at CERN




Slow control chimney

3 Slow control chimneys. Tailored flange to host a variety of connectors that are needed for all sensors + HV connections. Connectors to be welded on the flange are about to be purchased.



top cap will be positioned next to the detector and lifted to the desired height. A temporary clean-tent will be constructed around.

1. inserting chimneys into top cap crossing pipes
2. installing CRP under top cap (connection to chimneys and signal testing)
3. install drift cage under top cap (including PMTs and connection to chimneys + testing)
4. lift top cap+CRP+drift-cage in tank.
5. welding of top cap and outside connections.



Construction plan constantly checked (here only final assembly section shown).
 Every part is on schedule for the moment. Apart from liquid handling.
 Goal to close and do first gas purge purity test before christmas.

Level	Activity	Responsible institute/person	Dec 14	Jan 15	Feb 15	Mar 15	Apr 15	May 15	Jun 15	July 15	Aug 15	Sep 15	Oct 15	Nov 15	Dec 15	Status
1	FINAL ASSEMBLY	CERN / ETH														
1.01	MILESTONE: conducting GAr purity test	CERN / ETH														
1.02	lifting and welding top cap to outer-structure														X	
1.03	Outside connections (liquid pipes, electronic cables etc.) to tank / cap	CERN technicians / ETH													X X	
1.04	MILESTONE: welding of top cap	CERN / ETH														
1.05	Installing top-cap+CRP+drift-cage in tank	CERN technicians / ETH / Gabadi												X X		
1.06	Installing drift-cage below top-cap	CERN technicians / ETH												X		
1.07	Installing CRP under top-cap	CERN technicians / ETH											X X X			
1.08	Inserting chimneys into top-cap	CERN technicians / ETH										X X				
1.09	Site preparations for final assembly (all components and cranes in place)	CERN technicians / ETH										X X				
2	TANK	CERN / ETH														<i>in progress</i>
3	LIQUID INFRASTRUCTURE (LI)	ETH / CERN														<i>in progress</i>
4	TOP CAP CONSTRUCTION	CERN / ETH														<i>in progress</i>
5	CHIMNEYS & FT	ETH / LAPP														<i>in progress</i>
6	CHARGE READOUT PLANE (CRP)	ETH / ELTOS														<i>in progress</i>
7	DRIFT CAGE +CATHODE + PMT	ETH / KEK														<i>in progress</i>
8	SLOW CONTROL	CERN / ETH														<i>in progress</i>
9	ON-SITE INFRASTRUCTURE	CERN														<i>in progress</i>



Title: WA105 Top Cap Requirements & Crossing Pipes	Page:	1 of 21	
	Rev:	0.3	Date: 16/02/2015
	Author:	Gendotti A.	
	Checked:		

Top Cap is now fully designed on our side. All specifications summarised in a document provided to GTT. Still on schedule to be delivered around June.


WA105 Top Cap Requirements & Crossing Pipes


INDEX

1.0 INTRODUCTION	3
1.1 Document Content	3
1.2 Top Cap Layout	3
2.0 CROSSING PIPES SIZE AND LAYOUT	4
2.1 Manhole	9
2.2 Signal Feedthrough (SGFT)	10
2.3 Slow Control Feedthrough (SCFT)	11
2.4 High Voltage Feedthrough (HVFT)	13
2.5 Cryo Pump Feedthrough (CPFT)	15
2.6 Liquid Handling Feedthrough (LHFT)	16
2.7 Suspension Feedthrough (SPFT)	16
3.0 REINFORCEMENT M10 THREADED RODS	17
4.0 M8 CROSSING RODS FOR DRIFT CAGE HANGING	
5.0 INTERFACE TOP CAP-OUTER STRUCTURE	
6.0 LOADS AT THE TOP CAP	
7.0 ADDITIONAL COMMENTS ON THE TOP CAP	



amount	abrievation	Def.	Flange	chimney ϕ		crossing pipe ϕ	
				internal	external	internal	external
			CUSTOM	-	-	797.16	812.56
			CF 250	-	-	215.1	219.1
			CF 250	250	254	30	32
			CF 250	250	254	105	108
			CF 400	-	-	408	412
			CF 250			250	254
			CF 125	-	-	28	20






- We now concentrate on having the gas purge and purification system ready.
- The goal is to have a first test of GAr purity before christmas of this year.
- Currently designing and procuring material.
- The trace analysers (N₂, O₂ and H₂O) have already been bought. The N₂ has already been tested in cold GAr.
- Regular (bi-weekly) meetings with CERN cryo-group to define the entire layout

~13 days

Nom de l'appareil:		16/02/2015 15:10:36			Page	1/1
Temps du démarrage: 03/02/2015 13:47:39		Minimum	Maximum	Moyenne	Limites	
Temps de l'arrêt: 16/02/2015 15:07:39	no name [%HR]	15.20	34.70	22.044	0.0/100.0	
Canaux de mesure: 2	no name [°C]	19.40	23.40	20.586	-20.0/55.0	
Valeurs: 9401						
SN 40334300						



- * WA105 is a collaboration of 120 physicists with the goal of constructing and operating the 6x6x6 in the North Area.
- * We have alternating bi-weekly meetings dedicated to the 6x6x6 installation. One week on software and the other on technical aspects (integration in NA, ...). We are closely following the progress and schedule update of the EHN1 extension.
- * Construction of the 3x1x1 is progressing well and on schedule.
- * procedure for LEM+anode for the 666 will be adapted from what we learn from the 3x1x1 and adapted to fit larger scale demands.
- * In general a lot of the work that is and has being done for the 3x1x1 is being used for the construction planification of the 6x6x6 (purchase of the tank, light readout, LEMs, slow control....)