


LLRF for SPS CC test

P. Baudrenghien

LLRF HARDWARE

LLRF Hardware design

- Close synergy with the Linac4 352.2 MHz system
- Hardware is **tuned for 400 MHz** and **firmware is developed** to have prototypes ready for the **SM18 test by mid 2015**
- One Technical Eng. ½ FTU per year in 2015,2016,2017
- One fellow (June 2015?)



Crab Cavity Servo Controller. Simplified Block Diagram

Signals:
 Digital: Digital I/Q pair:
 Analog baseband: Analog I/Q pair:
 RF @ 352.2 MHz

Technology:
 DSP
 CPLD or FPGA
 Analog RF

Gain increased on the betatron bands

Field control fully integrated with the rest of the LHC by using standard FGCs

Interconnection with the paired cavity(ies) Coupled feedback

Measurement of bunch phase modulation

For each Crab Cavity we have a Cavity Controller including:

- An RF Feedback Loop for noise and beam loading control
- A TX Polar Loop to reduce the TX noise and stabilize its gain/phase shift
- A Tuner Loop to shift the cavity to a detuned position during filling and ramping. Then smoothly bring the cavity on-tune with beam for physics
- A field Set Point for precise control of the cavity field.

Version: 20111111

SPS 800 MHz TWC prototype


G. Hagmann BE-RF-FB designer

2 x Duplex Optical Serial Links
2 in & 2 out
2Gbits/s
(≤ 3.2 Gbits/s)

SSB Modulator
IF (I & Q) ≈ 25 MHz
Dual Tx/Dac 16 bits

RF Demodulator
RF&LO mixing
IF ≈ 25 MHz
14 bits ADC
 $F_s = 4 \cdot IF \approx 100$ MHz

LO Distribution



SRAM 2x8 Mbyte for diagnostics

Xilinx Virtex 5 SX


VME P1 backplane for slow controls/read out

Dedicated backplane (P2):
• Power Supply
• Clocks
• Interlocks
• ...


PLANNING

Planning

- 2013-2014 Cavity Testing
- 2015-2016 LLRF developments
- 2017-? SPS tests: 2 cavities in one cryostat
- 2015-2017 (LS2?) Prototype Cryomodule
- 2018-2020 (LS3?) Production
- In operation in the LHC after LS3




Proposed SPS cryomodule with 2 Crab Cavities. The cryomodule is designed to accept all three CC makes



Courtesy EN-MME


SPS testbench with 2 Crab cavities in the LSS4. The cryomodule can be moved in and out of the beam line (2016-)

The Crab Cavity systems (IP1 and IP5)



SPACE and INFRASTRUCTURE

LHC: New galleries with LLRF, TX, circulator next to the cavities



Asymmetric architecture:

τ_a is the delay of the local antenna signal $20 \times 3.7 \text{ ns} = 74 \text{ ns}$ rounded to **80 ns** (10 % margin)

τ_b is the delay of the opposite antenna signal $(320+20) \times 3.7 \text{ ns} = 1258 \text{ ns}$ rounded to **1380 ns**

τ_c is the drive path delay, including LLRF, TX, circulator and coax = $300 \text{ ns} + 100 \text{ ns} + 50 \text{ ns} + 20 \times 3.7 \text{ ns} = 524 \text{ ns}$ rounded to **580 ns**

Space and Infrastructure SPS

- One rack per cavity (1 VME crate per cavity), plus space in front of rack for instruments (NWA, oscilloscope), table with PC,...
- In addition space must be provided for the following services: Internet, timing, functions
- The equipment (TX, LLRF) must be **accessible with RF in the cavities**, at least during commissioning. Inaccessible with beam?
- Must be in a radiation-free zone (digital electronics: FPGA)
- **LLRF must be close to TX** (10-20 m as in LHC) but need not be very close to the cavities anymore
- Reasonably comfortable (noise, dirt,...)