



FRIB PLC Testing & Verification Process

Kelly Davidson

Controls Department Deputy Manager

MICHIGAN STATE
UNIVERSITY




U.S. DEPARTMENT OF
ENERGY

Office of
Science

This material is based upon work supported by the U.S. Department of Energy Office of Science under Cooperative Agreement DE-SC0000661, the State of Michigan and Michigan State University. Michigan State University designs and establishes FRIB as a DOE Office of Science National User Facility in support of the mission of the Office of Nuclear Physics.

FRIB Controls Testing and Verification Process

- Hardware for major procurements tested with Bench Test Acceptance Criterial List (ACL) Testing
- Once PLC installation is complete, we perform several levels of testing
 - Installation tests
 - Interface tests
 - Component/Connection including Interlock Tests
 - Integration/Commissioning Tests include test with beam – Controls role is just support
 - Test records are filed with a number and title in our Document Control Center (DCC)
- **Installation Test**
 - Testing the PLC installation using traveler procedure/checklist system
- **Interface Test**
 - Test our outputs and inputs at the point of interface to hardware devices
 - Verify hardware devices have expected interface, i.e. Closed/open contact, 4-20 mA, etc
- **Component/Connection Test**
 - Connect to device hardware and verify I/O interface is working as expected, i.e. On/Off Control, readbacks, interlocks, limit status
 - Verify channels in control screens work as expected
 - Test Interlocks per Interlock and Alarm Document
- **Device Readiness Review (DRR)** reviews that testing and documentation completed, as well as safety and operational concerns before final integrated testing is performed



Acceptance Testing Plans Developed for PLC Hardware

- New hardware tested against ACL verification plan
- The Standard Operating Procedure is referenced by ACL plan and details how the ACL inspections are to be carried out
- The results of the tests are recorded in a separate tab of the ACL verification report document
- The results summary for the lot of modules is entered into the ACL Results section by the verifier and filed into our DCC system

Controllers						
Serial Number	RUN LED	FORCE LED	OK LED	Scrolling Status Display	Tested By	Date
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		
	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> Flashing red	<input type="checkbox"/> Firmware Installation Required		

1756 Ethernet Modules					
Serial Number	LEDs			Alphanumeric Display Status TEST, PASS, OK, REV x.x,	
	OK	LINK	NET		
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	
	<input type="checkbox"/> Flashing green	<input type="checkbox"/> Off	<input type="checkbox"/> Off	<input type="checkbox"/> OK, IP address	

The screenshot shows a technical manual page with the following sections:

- 5 CHASSIS AND POWER SUPPLY**: Includes a diagram of a power supply and chassis, and a test procedure (5.2) for combining the chassis power supply with the chassis.
- 6 CONTROLLER**: Includes a diagram of a controller and a USB programming cable, and a test procedure (6.2) for more information.
- 6.3 Firmware Upgrade**: Lists steps for determining the required controller firmware, upgrading the firmware, and starting the controller.

VERIFICATION PLAN AND TESTING REQUIREMENTS										RESULTS				NON-CONFORMANCE				FAILURE RESOLUTION (choose only one)			
ITEM NO.	REQ ID or DCC doc #	DESCRIPTION OF TEST TO BE CONDUCTED, VERIFIED or WITNESSED	METHOD or TOOL	VERIFYING ENTITY	VP revision used during inspection	Test Conducted by (enter VERIFIER name)	DATE	PASS/FAIL (enter pass or fail)	Next maintenance Report # if FAIL (enter NCR#)	Deviation Request	Work Order	Returns to Vendor or Scrap	Deviation Request	Work Order	Returns to Vendor or Scrap	Deviation Request	Work Order	Returns to Vendor or Scrap			
1		Analog Input, PLC Interface Module																			
1a	N/A	Assign serial number if not previously assigned		VISUAL		OPREJ L.L.C.															
1b	N/A	Check integrity of the assembly for damage and that all components are mounted correctly		VISUAL		OPREJ L.L.C.															
1c	T11301-PB-000118-R000	Bench Test 100% of components received		TEST BENCH		OPREJ L.L.C.															
2		Analog Output, PLC Interface Module																			
2a	N/A	Assign serial number if not previously assigned		VISUAL		OPREJ L.L.C.															
2b	N/A	Check integrity of the assembly for damage and that all components are mounted correctly		VISUAL		OPREJ L.L.C.															
2c	T11301-PB-000118-R000	Bench Test 100% of components received		TEST BENCH		OPREJ L.L.C.															
3		Digital Input, PLC Interface Module																			
3a	N/A	Assign serial number if not previously assigned		VISUAL		OPREJ L.L.C.															
3b	N/A	Check integrity of the assembly for damage and that all components are mounted correctly		VISUAL		OPREJ L.L.C.															
3c	T11301-PB-000118-R000	Bench Test 100% of components received		TEST BENCH		OPREJ L.L.C.															
4		Digital Output, PLC Interface Module																			
4a	N/A	Assign serial number if not previously assigned		VISUAL		OPREJ L.L.C.															
4b	N/A	Check integrity of the assembly for damage and that all components are mounted correctly		VISUAL		OPREJ L.L.C.															
4c	T11301-PB-000118-R000	Bench Test 100% of components received		TEST BENCH		OPREJ L.L.C.															



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

K. Davidson, ICALEPCS 2017 Workshop: PLC Based Control Systems, FRIB Testing & Verification, Slide 3

FRIB Controls Installation/Interface Tests

- Installation testing uses online traveler system or spreadsheet
 - Combination of procedure and checklist
 - Tracks user & history

Traveler title: Controls Rack Installation

Status: submitted

Devices: FE-007-04, RFQ PLC Rack 2

Show validation Hide validation Show notes Hide notes Details

PLC Installation

Enter PLC Name
history: changed to PLC 1008 by mujtaba Monday, December 19th 2016, 10:11:46 am;
notes: 0

Enter PLC Drop Number
history: changed to 2 by mujtaba Monday, December 19th 2016, 10:11:57 am;
notes: 0

Enter PLC Firmware Revision
history: changed to 10.001 by mujtaba Monday, December 19th 2016, 10:12:45 am;
notes: 0

Enter PLC Software Version
history: changed to 28.012 by mujtaba Monday, December 19th 2016, 10:13:35 am;
notes: 0

PLC Drop installed
history: changed to true by mujtaba Monday, December 19th 2016, 10:13:43 am;
notes: 0

PLC Installation

- 24 VDC Power Drop Installation
- 5 VDC Power Drop Installation (check all if no 5V PS used)
- IFM Installation
- PLC to IFM Initial Setup
- PLC to IFM Connections
- Ethernet Information

PLC to IFM Initial Setup

Turn Off all Circuit Breakers
history: changed to true by mujtaba Monday, December 19th 2016, 10:15:10 am;
notes: 0

Turn Off all Circuit Breakers
history: changed to true by mujtaba Monday, December 19th 2016, 10:15:16 am;
notes: 0

Equipment Cord Installed on PLC power supply
history: changed to true by mujtaba Monday, December 19th 2016, 10:15:25 am;
notes: 0

Unplug all PL1 connectors from IFMs
history: changed to true by mujtaba Monday, December 19th 2016, 10:15:30 am;
notes: 0

Turn On 120V circuit breakers for IO drops and 24V power supply
history: changed to true by mujtaba Monday, December 19th 2016, 10:15:38 am;
notes: 0

Verify voltage to power supply and PLC drop is 120V +/- 10%
history: changed to true by mujtaba Monday, December 19th 2016, 10:15:47 am;
notes: 0

Verify voltage from power supply is 24V +/- 10%
history: changed to true by mujtaba Monday, December 19th 2016, 10:16:09 am;
notes: 0



FRIB Controls Component/Connection Tests[1]

- Component/Connection testing is tracked in spreadsheet and filed in DCC
 - Testing verified installation/interface wiring and control connections through control screens
 - Tracked by each hardwired I/O point and filed in Document Control Center

Facility for Rare Isotope Beams
Front End Controls Installation and Interlock Test Records

FRIB-T30506-RC-002608-R001 Page 7 of 38
Issued Draft 26 July 2017

			Controls Rack	Rack Termination Complete	Device Location	Device Termination Complete	Cable Number	Installation Test			Component Test					
								Result	Tested On	Tested By	Result	Tested On	Tested By	Representative	Notes	
Slot 1	4	FE_LEBT:IP_D0912:OK_RSTS	FE-001.03	YES	FE-001.02	YES		PASS	7/20/2017	LH	PASS	5/16/2017	LH	AW		
	5	FE_LEBT:IP_D0977:OK_RSTS	FE-001.03	YES	FE-001.02	YES		PASS	7/20/2017	LH	PASS	5/16/2017	LH	AW		
	6	FE_MEBT:IP_D1053:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	7	FE_MEBT:IP_D1066:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	8	FE_MEBT:IP_D1070:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	9	FE_MEBT:IP_D1092:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	10	FE_MEBT:IP_D1102:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	11	FE_MEBT:IP_D1109:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	12	FE_MEBT:IP_D1121:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	13	FE_BTS:IP_D1098:OK_RSTS	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	14	RFQ VAC STATUS TO FE	FE-001.03	YES	FE-007.04	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
	15		FE-001.03													
	Slot 2		DIGITAL OUTPUT	FE-001.03												
	Slot 2	0	FE_LEBT:NEGP_D0955:ON_RCMD	FE-001.03	YES	FE-001.02	YES		PASS			PASS				
		1	FE_LEBT:NEGP_D0987:ON_RCMD	FE-001.03	YES	FE-001.02	YES		PASS			PASS				
2		FE_LEBT:TMP_D0833:ON_RCMD	FE-001.03	YES	FE-001.02	YES		PASS	8/24/2017	LH	PASS	5/16/2017	LH	AW		
3		FE_LEBT:TMP_D0833:SFTS_RCMD	FE-001.03	YES	FE-001.02	YES	84F000053	PASS	8/24/2017	LH	PASS	5/16/2017	LH	AW		
4		FE_LEBT:IP_D0912:ON_RCMD	FE-001.03	YES	FE-001.02	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
5		FE_LEBT:IP_D0977:ON_RCMD	FE-001.03	YES	FE-001.02	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
6		FE_MEBT:IP_D1053:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
7		FE_MEBT:IP_D1066:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
8		FE_MEBT:IP_D1070:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
9		FE_MEBT:IP_D1092:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
10		FE_MEBT:IP_D1102:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
11		FE_MEBT:IP_D1109:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
12		FE_MEBT:IP_D1121:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
13		FE_BTS:IP_D1098:ON_RCMD	FE-001.03	YES	FE-001.01	YES		PASS	7/20/2017	LH	PASS	7/24/2017	LH	AW		
14		FE VAC STATUS TO RFQ	FE-001.03													
15		FE-001.03														
Slot 3		DIGITAL INPUT	FE-001.03													
Slot 3	0	FE_SCS1:PG_D0707:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/20/2017	LH	PG		
	1	FE_SCS1:RPG_D0707:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/20/2017	LH	PG		
	2	FE_SCS1:CCG_D0707:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/17/2017	LH	PG		
	3	FE_LEBT:CCG_D0795:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES	84F000002	PASS	3/9/2017	LH						
	4	FE_SCS1:RPG_D0717:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/20/2017	LH	PG		
	5	FE_SCS2:RPG_D0701:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH						
	6	FE_SCS1:CCG_D0717:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH						
	7	FE_SCS2:CCG_D0701:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES	84F000003	PASS	3/9/2017	LH						
	8	FE_SCS1:PG_D0739:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/20/2017	LH	PG		
	9	FE_SCS1:RPG_D0739:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/20/2017	LH	PG		
	10	FE_SCS1:CCG_D0739:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES		PASS	3/9/2017	LH	PASS	3/17/2017	LH	PG		
11	FE_LEBT:CCG_D0814:OK_RSTS_VP	FE-001.03	YES	FE-001.02	YES	84F000004	PASS	3/9/2017	LH							



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

K. Davidson, ICALEPCS 2017 Workshop: PLC Based
Control Systems, FRIB Testing & Verification, Slide 5

FRIB Controls Component/Connection Tests[2]

- Checklists for component/connection test filed in DCC
 - Alarms and Interlocks documented and signed off in DCC
 - Interlocks tested per area's Alarm and Interlocks document and results filed in Document Control Center

Facility for Rare Isotope Beams
FRIB Front End Alarms and Interlocks

FRIB-T30506-TD-001036-R002 Page 5 of 18
Issued 14 April 2017

Table 4: High Voltage Power Supply Interlocks

Interlocked Device Channel	Interlocked Device	Interlocked State	Interlocked By	Device Description	Signal/Limit	Delay	Notes
FE_ISRC1:PSEL_D0698:EN_RCMD	Acceleration Column Electrode Enable	0 - "OFF"	FE_PS:LT_N0001:ON_RCMD	Power Supply Warning Light	0 - "Not On"	None	
			FE_SCS1:VAC_D0739:BYP_RCMD	Charge Selection Vacuum Pumpdown Bypass	1 - "Bypass ON"	None	
			FE_SCS1:CCG_D0707:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	See Note 1
			FE_SCS1:CCG_D0739:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	
			FE_ISRC1:IG_D0679:OK_RSTS_VP1	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	See Note 1
FE_PSCD1:PSMC_N0101:EN_RCMD	Diagnostic Device Bias Power Supply Enable	0 - "OFF"	FE_SCS1:CCG_D0707:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>10 ⁻⁵ Torr)	1 s	See Note 1
			FE_SCS1:CCG_D0739:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>10 ⁻⁵ Torr)	1 s	
			FE_LEBT:CCG_D0783:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	See Note 1
			FE_LEBT:CCG_D0808:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	
			FE_PS:LT_N0001:ON_RCMD	Power Supply Warning Light	0 - "Not On"	None	
FE_SCS1:QET_D0730	E-Quad Triplet Power Supplies Enable	0 - "OFF"	FE_SCS1:VAC_D0739:BYP_RCMD	Charge Selection Vacuum Pumpdown Bypass	1 - "Bypass ON"	None	
FE_SCS1:PSQ1_D0726:EN_RCMD			FE_SCS1:CCG_D0707:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁻⁵ Torr)	1 s	See Note 1
FE_SCS1:PSQ2_D0726:EN_RCMD							
FE_SCS1:PSQ1_D0730:EN_RCMD							
FE_SCS1:PSQ1_D0733:EN_RCMD							

Facility for Rare Isotope Beams
Front End Controls Installation and Interlock Test Records

FRIB-T30506-RC-002608-R001 Page 27 of 38
Issued Draft 26 July 2017

Interlocked Device Channel	Interlocked Device	Interlocked State	Interlocked By	Device Description	Signal/Limit	Delay	Notes	Test Results	Tested By	Date Tested
FE_ISRC1:PSEL_D0698:EN_RCMD	Acceleration Column Electrode Enable	0 - "OFF"	FE_PS:LT_N0001:ON_RCMD	Upper FE Power Supply Warning Light	0 - "Not On"	None		PASS	LH	
			FE_SCS1:VAC_D0739:BYP_RCMD	Charge Selection Vacuum Pumpdown Bypass	1 - "Bypass ON"	None		PASS	LH	
			FE_SCS1:CCG_D0707:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	See Note 1	PASS	LH	
			FE_SCS1:CCG_D0739:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s		PASS	LH	
			FE_ISRC1:IG_D0679:OK_RSTS_VP1	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	See Note 1	PASS	LH	
FE_PSCD1:PSMC_N0101:EN_RCMD	Diagnostic Device Bias Power Supply Enable	0 - "OFF"	FE_SCS1:CCG_D0707:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>10 ⁻⁵ Torr)	1 s	See Note 1	PASS	LH	
			FE_SCS1:CCG_D0739:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>10 ⁻⁵ Torr)	1 s		PASS	LH	
			FE_LEBT:CCG_D0783:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s	See Note 1	PASS	LH	
			FE_LEBT:CCG_D0808:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁵ Torr)	1 s		PASS	LH	
			FE_PS:LT_N0001:ON_RCMD	Upper FE Power Supply Warning Light	0 - "Not On"	None		PASS	LH	
FE_SCS1:QET_D0730	E-Quad Triplet Power Supplies Enable	0 - "OFF"	FE_SCS1:VAC_D0739:BYP_RCMD	Charge Selection Vacuum Pumpdown Bypass	1 - "Bypass ON"	None		PASS	LH	
FE_SCS1:PSQ1_D0726:EN_RCMD			FE_SCS1:CCG_D0707:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁻⁵ Torr)	1 s	See Note 1	PASS	LH	
FE_SCS1:PSQ2_D0726:EN_RCMD										
FE_SCS1:PSQ1_D0730:EN_RCMD										
FE_SCS1:PSQ2_D0730:EN_RCMD										
FE_SCS1:PSQ1_D0733:EN_RCMD	FE_SCS1:CCG_D0739:OK_RSTS_VP	Cold Cathode Gauge Digital Setpoint	0 - "Not Okay" (>2x10 ⁻⁵ Torr)	1 s		PASS	LH			

Facility for Rare Isotope Beams
FRIB Front End Alarms and Interlocks

FRIB-T30506-TD-001036-R002
Issued 14 April 2017

Prepared by: *[Signature]* 4/11/2017
Reviewed by: *[Signature]* 4/14/2017

Reviewed by: *[Signature]* 4/20/2017
Reviewed by: *[Signature]* 4/20/2017

Reviewed by: *[Signature]* 4/19/2017
Reviewed by: *[Signature]* 4/20/2017

Reviewed by: *[Signature]* 4/21/2017
Reviewed by: *[Signature]* 4/21/2017



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

K. Davidson, ICALEPCS 2017 Workshop: PLC Based Control Systems, FRIB Testing & Verification, Slide 6

Summary

- Testing completed at each level ensures quality installation and reduces engineers time troubleshooting at the final level
- Beamline performs as intended on first commissioning/integration tests – reducing calls for support



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

K. Davidson, ICALEPCS 2017 Workshop: PLC Based
Control Systems, FRIB Testing & Verification, Slide 7

Backup Slides




Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University

K. Davidson, ICALEPCS 2017 Workshop: PLC Based
Control Systems, FRIB Testing & Verification, Slide 8

Quality Assurance - Acceptance Testing Plans Developed for PLC Hardware

- Acceptance and SOP Test documents developed for PLC components and Interface Modules (IFMs),
 - Allen Bradley Hardware ACL Plan (T31207-VP-000354)
 - FRIB Allen Bradley Hardware Acceptance Standard Operating Procedure (T31207-PR-000322)
 - Programmable Logic Controller (PLC) Interface Modules Acceptance Criteria Listing (ACL) Plan (T31207-VP-000378)
 - Interface Module Acceptance Standard Operating Procedure (T3107-PR-000338)
- Acceptance testing is performed once parts are received and documented in a verification report (VR)



VERIFICATION PLAN and TESTING REQUIREMENTS				
ITEM NO.	REQ ID or DCC doc #	DESCRIPTION OF TEST TO BE CONDUCTED, VERIFIED or WITNESSED	METHOD or TOOL	VERIFYING ENTITY
1	[1] frib-ctrl_5.4-1	CHASSIS(BACKPLANE): Verify quantity for applicable P/Ns; 1756-A10, 1756-A7	VISUAL	(FRIB) LLC
1a	N/A	Visual inspection for shipping damage	VISUAL	(FRIB) LLC
1b	T31207-PR-000322-R001	Bench test 5% of components received	TEST BENCH	(FRIB) LLC
2	[1] frib-ctrl_5.4-1	POWER SUPPLIES: Verify quantity for applicable P/Ns; 1756-PA72, 1734-EP24DC, 1606-XLE240EN	VISUAL	(FRIB) LLC
2a	N/A	Visual inspection for shipping damage	VISUAL	(FRIB) LLC
VERIFICATION PLAN and TESTING REQUIREMENTS				
ITEM NO.	REQ ID or DCC doc #	DESCRIPTION OF TEST TO BE CONDUCTED, VERIFIED or WITNESSED	METHOD or TOOL	VERIFYING ENTITY
1		Analog Input, PLC Interface Module		
1a	N/A	Assign serial number if not previously assigned	VISUAL	(FRIB) LLC
1b	N/A	Check integrity of the assembly for damage and that all components are mounted securely.	VISUAL	(FRIB) LLC
1c	T31207-PR-000338-R001	Bench Test 100% of components received	TEST BENCH	(FRIB) LLC
2		Analog Output, PLC Interface Module		
2a	N/A	Assign serial number if not previously assigned	VISUAL	(FRIB) LLC
2b	N/A	Check integrity of the assembly for damage and that all components are mounted securely.	VISUAL	(FRIB) LLC
2c	T31207-PR-000338-R001	Bench Test 100% of components received	TEST BENCH	(FRIB) LLC



Facility for Rare Isotope Beams
U.S. Department of Energy Office of Science
Michigan State University