

COUPLER DEVELOPMENTS AT CEA- SACLAY

G. Devanz

- 704 MHz FPC
 - HIPPI
 - ESS

- IFMIF 175 MHz CW FPC



HIPPI FPC

HIPPI = High Intensity Pulsed Proton Injector (part of FP6-CARE EU R&D programme)

Goal of programme was :


- Develop a 1 MW power coupler at 10% duty cycle
- Test it on a low beta multicell SRF cavity

CRYHOLAB Test cryostat requires horizontal orientation of the FPC
→ Mechanical assembly and Conditioning test stand were designed to mimick horizontal setup of FPC





704 MHz -1 MW power coupler

100 mm diameter
50 Ω



704 MHz FPC components



Coupler – window (1)



Matching calculations (HFSS)

Starting from KEK-B / SNS geometry with double chokes


⇒ 100 mm diameter, 50 Ω

⇒ 704.42 MHz center frequency


Large bandwidth design




Coupler – window manufacturing prototypes



- 2 prototypes build by Toshiba (IPNO & Saclay)
- Antenna supposed to be welded later on but it was considered too difficult by the manufacturer
- Was used for RF measurements, leak test and pressure test of water cooling channels



Coupler cooling




Air side

- ❖ blown air on the ceramic
- ❖ Internal conductor (IC) water cooled

Vacuum side

- ❖ Outer conductor (OC) He cooled
- ❖ IC water cooled
- ❖ ceramic outer water cooling channel

He cooling channel capable of up to 100 W extraction (3 spiral channels)



RF power test stand at 704 MHz

Running since 2008:


Nominal parameters :

- Peak power : 1MW (1.2 MW for a short period)
- Repetition rate : 50 Hz
- RF pulse length : 2 ms



Updated for ESS tests :

- Peak power : 1MW (1.2 MW for a short period)
- Repetition rate up to : 25 Hz
- RF pulse length : 3 ms



1 MW 704 MHz klystron

110 kV Power Supply

HV Pulse Power generator


Coupler test stand with HIPPI couplers

Travelling wave and standing wave processing are performed sequentially



Here in SW
configuration

HIPPI test stand




Coupling waveguide:

- Electrolytic copper coating was very difficult to achieve due to the poor access from the two 100 mm ports only
- Difficult to control the quality of the Cu layer, and clean

Coupler preparation in clean room




HIPPI couplers high power tests main results




TW on conditioning test stand

1 pair tested up to 1.2 MW, 10% duty factor



Test of the HIPPI power coupler on the HIPPI cavity at 1.8 K, full reflection

100 mm outer conductor



10 μm Cu layer

Magnetron Sputtering performed at CERN (S. Calatroni)


HIPPI coupler after 4-5 years storage

Example of special tapered 100-80 mm outer conductor for use with a INFN

- conditioned only in SW (single item available)
- Run on a 5-cell SRF cavity
- Stored under N₂ gaz since 2011
- Opened in may 2015



This large discoloration was already present before conditioning





No impact observed during cavity operation

~1mm sized spot discolorations more visible after 5 years





Single FPC conditioning setup for the tapered outer conductor



Large optical window

The antenna and RF window had previously been conditioned



Looking towards the RF window




RF window vacuum side

Cu layer and antenna aspect is unchanged since clean room assembly in 2008


Vacuum side of ceramic disk is now gray with spared rectangle areas



Consequence of wrong assembly of air part



Misalignment of (1) window IC and (2) dooknob IC → water leak at an early stage of RF conditioning. Arcing occurred at O-ring gasket location (and destroyed it)
Only repair was hand polishing of copper surfaces. TW and SW 1MW conditioning was performed afterwards.



Air side arcing



Picture shows the effect of several tens of arcs (sorry for the wrong white balance).
Cleaning of the sputtered copper was performed in-situ using diluted Nitric acid using swabs.

Air side arcing occurred when running at full reflection on SC cavity 1MW forward power, 50 Hz, 2ms.


No arc detector on the air side at that time

Window was protected by the vacuum-side arc detector

Window was cooled with dry N₂ stream blowing on its air side.

Arcing stopped immediately when this forced cooling was disabled.

After cleaning




FPC was operated again after cleaning, arcs did not re-appear

HIPPI conclusion


What we tested that generally cause worries :

- Assembly on the cavity from the top in the clean room. No particle counting was performed in the 2009 assemblies but FE was not enhanced on the two test SRF cavities
- Massive antenna resting for years in horizontal position: no deflection observed
- More recently a new clean room test assembly of 1 HIPPI coupler was carried out in the new ISO5 clean room succesfully with particle counting
- The coupling waveguide aspect indicates it may have been the most difficult part to condition (Cu particulates were present inside)



The European Spallation Source linac

Beam power (MW)	5
beam current (mA)	62.5
Linac energy (GeV)	2
Beam pulse length (ms)	2.86
Repetition rate (Hz)	14




Segmented, superconducting proton linac, with RT focusing elements

	Num. of CMs	Num. of cavities
Spoke	13	26
6-cell medium β	9	36
5-cell high β	21	84


4-cavity cryomodules

Irfu Similarity with SNS in size and purpose : reuse the same concepts

- Common design for medium and high beta
 - made sensible thanks to the small length difference between 6-cell medium and 5-cell high beta cavities
 - Main components are identical : vacuum vessels, thermal shield, supports, alignment system, etc.
 - Only few elements differ : details in cryo piping, beam pipe bellows



CM cross-section




ESS 704 MHz power coupler peak power



	Optimus	Unit
$E_{\text{acc Spoke}}$	9	MV/m
V_{Spoke}	5.74 ($L = 3 \beta \lambda / 2$)	MV
$P_{\text{coupler Spoke}}$	330	kW
$N_{\text{Spoke modules}}$	13	—
$E_{\text{acc M}\beta}$	16.79	MV/m
$V_{\text{M}\beta}$	14.36 ($L = 6 \beta' \lambda' / 2$)	MV
$P_{\text{coupler M}\beta}$	860	kW
$N_{\text{M}\beta \text{ modules}}$	9	—
$E_{\text{acc H}\beta}$	19.94	MV/m
$V_{\text{H}\beta}$	18.24 ($L = 5 \beta'' \lambda' / 2$)	MV
$P_{\text{coupler H}\beta}$	1100	kW
$N_{\text{H}\beta \text{ modules}}$	21	—


D. Mc Ginnis

ESS Fundamental power coupler




HIPPI coupler



- CM integration
- Inner conductor, below is New range, below is part of vacuum vessel
 - Conical tip for stronger coupling
 - Diagnostic ports
 - Improved water cooling distribution channels
 - VCRs



HV bias with RF trap




Doorknob transition



5 RF gaskets are required for the assembly

We use RF Spring-type gaskets





Gasket assembly mock-up of the RF trap



Checked :




- Gasket groove geometry in all configurations (coaxial inner groove and outer groove, flange type)
- Assembly/disassembly multiple times
- Wear caused by assembly is not significant



Mock-up with all 5 RF gaskets

Coupler/vessel interface

- Large flange due to vacuum gauge footprint
→ 10kN force due to atmospheric pressure needs to be compensated
→ Adjustable springs+stops. The FPC is stiff, vertical flange motion must be possible to accomodate thermal shrinkage of coupler and cavity
- The coupler remains at a fixed longitudinal position at all times using two blades





A mock-up with the nominal bellow and flange dimension has been built to check the concept of pressure compensation and choose the proper springs


Conditioning waveguide

- Full stainless steel designed (no copper coating). Dismountable (as Eric's 700 MHz test box). Top cover can be Cu deposited if first tests prove it is necessary
- Air cooling designed accordingly ;
 - heat sinks + fans on bottom plate
 - Channeled air flow with push-pull fans on the top
- Arc detector added in order to have the opportunity to distinguish between window arcs and waveguide arcs.

Fans






Arc detector





ESS FPC test box design


- Full stainless steel design
- Maximum access with two-part construction
- Seal : aluminum wire
- Air cooling on top and bottom




Linear IFMIF Prototype Accelerator to be tested in Rokkasho - Japan



SRF-LINAC



IFMIF Power Coupler



Power Coupler Specifications for LIPAC:


- Frequency: **175MHz**
- Qext: **6.5×10^4**
- Maximum nominal operating RF power: **70 kW CW**
- RF power validation needs : **100 kW CW in Travelling Wave (TW) and Standing Wave (SW)**

Power Coupler Assembly at Saclay






Transportation

Power Coupler Assembly on Test Box at Madrid



- Prototype Power Coupler Pair manufactured
- Test box manufactured and qualified
- Assembly operations performed in ISO5 clean rooms
- Particle counting check performed before each critical assembly operation

- **In-situ baking** :170°C
- **Water Cooling** : 27°C
- **Diagnostics**: E-currents / Vacuum / Light / Temperature





RF Power Validation Criteria:

- 1) **TW CW** power up to **100 kW**.
- 2) **SW CW** power up to **100 kW** with RF field configuration giving a maximum electrical field on ceramic window for PC Proto-1, then PC Proto-2.

RF Power Conditioning Steps :

- **TW pulsed RF processing** (0 → 100 kW) :
From 20μs (2 Hz) to 400 ms (2Hz)
- **TW CW RF** processing up to 100 kW
- **SW RF processing (from pulsed to CW)** (0 → 100 kW) :
 - With max E field on the upstream ceramic window
 - With max E field on the downstream ceramic window
 - With max E field on six other intermediate positions.



TW CW RF Power Validation Result (1)



Vacuum increase due to Multipacting

Vacuum increase correlated with the test box temperature increase


SW CW RF Power Validation Result (2)



Pressure less than 2×10^{-7} mbar for all the power ranges from 0 to 100 kW CW SW.

Test Results:

- Power validation objective has been reached: **100 kW CW (TW/SW)**
- Power Coupler behavior satisfactory : Smooth and easy power increase, in general.
- Low vacuum and no e-current measured for the Coupler operating power ranges at the end of the RF processing





Temperature sensor positions corresponds to the hottest locations found experimentally

TW_CW_First Pass: MP for Power between 12 kW and 18 kW:

- ➔ Vacuum interlocks.
- ➔ Low current signal are measured.
- ➔ Temperature increase : Max located on the cooling outer conductor (up to 82°C).
- ➔ MP effect is more important in the upstream coupler.

Additional RF processing of the MP was performed after the RF power validation (TW&SW):

- ➔ MP on the downstream coupler almost totally processed.
- ➔ MP on the upstream coupler is limited to a narrow power range (13 to 14 kW), but generates important temperature increase at this power level.
- ➔ No interlock is generated and power can be increased to avoid this region.




Summary:

- Two (IFMIF/LIPAc) Power Coupler Prototypes were manufactured and RF power tested @ RT
 → **Validation for RF power operation up to 100 kW CW in TW & SW configurations**
- Manufacturing of **8 Series Power Couplers** for LIPAc is on going
- MP around 13 kW RF power level is not limiting for the Coupler operation and it has been partially processed: More investigation is planned.

Next stages:

- Complementary tests **up to 200 kW** (in pulsed mode)
- Cold test** of one of the validated **Prototype Couplers + HWR cavity** (Extension of the existing Cryostat (CRYHOLAB) to make the test possible)
- First pair of the Series Power Couplers expected for May 2015



Thank you

Thanks to my CEA colleagues :

C. Arcambal,

G. Ferrand,

X. Hanus,

H. Jenhani,

for their contribution