### Gap Cleaning **ADT Transverse Feedbac Readiness for MJ Beams** June 2015

Wolfgang Hofle, CERN BE-RF for ADT Team

### **Overview of ADT System**



Bpos – Beam Position Module DSPU – Digital Signal Processing Unit

3

-

### Status of changes with respect to Run 1

#### • Power system (increased reliability and availability)

- Maintenance of tetrode power amplifiers (16 + 4 spares)
- Maintenance of 32 driver amplifiers (200 W)
- Improvement of amplifier to kicker connection and new loads
- Vacuum interlocks (to minimize risk of false interlocks)
- Exchange of flow meters for water cooling interlocks
- Installation of HV switches in power converters to take one amplifier off if needed, and HV maintenance (done)





**Tetrode amplifier** 



eady for Mibea

Migrate controls of power system to FESA3 (to be done)

# ADT kicker (16 x)

HOM port 1 (H front) (V top)



#### tank: 1.6 m length

electrodes: 1.5 m length, supported by 3 ceramic rings centering is achieved by accurately machines tank and ceramic rings longitudinal expansion of electrodes possible by design

HOM port 2 (H back) (V bottom)

## Beam induced signal on kicker



Resonance: close to 40 MHz Q = 600, tau = 210 ns ~ 200 V induced by nominal beam

100 ns / div [10 div] end of batch of 36 bunches @50 ns 15.04.2011; ok for next intensity step Watch this for Intensity increase with 25 ns

### Status of changes with respect to Run 1

- Lowlevel System (increased performance, flexibility)
  - X-change of cables (8 pick-ups plus 8 new pick-ups) → done, but electronics for new pick-ups deferred to YETS 2015/2016
  - New cables for 8 drive signals from surface (SR4) to UX45 (better pulse for AGC)
    → done
  - New VME electronics for beam position detection → deferred to YETS 2015/2016 following experience in SPS with new mixers, production of hardware ongoing
  - New VME mDSPU (signal processing) with independent gain control functions for cleaning and damping (4 independent DACs, analog outputs combined)
     → done
  - Number of FGC functions increased → done
  - Diagnostics: Instability trigger network → deployed, working on "last mile" to ADT
  - Observation BOX → under development, first roll-out for long. plane
  - New developments are in FESA 3 (e.g. abort gap and injection gap cleaning)

### Pickups available for ADT after LS1 effectively no change in 2015 with respect to Run 1

| B1<br>horizontal | Q10L      | Q9L       | Q7L       | Q7R       | Q9R            | Q10R      |
|------------------|-----------|-----------|-----------|-----------|----------------|-----------|
|                  | β = 28 m  | β = 127 m | β = 112 m | β = 78 m  | $\beta$ = 16 m | β = 158 m |
|                  |           | existing  | existing  | new       |                | new       |
| B1 vertical      | Q10L      | Q9L       | Q7L       | Q7R       | Q9R            | Q10R      |
|                  | β = 172 m | β = 25 m  | β = 52 m  | β = 127 m | β = 138 m      | β = 38 m  |
|                  | new       |           | new       | existing  | existing       |           |
|                  |           |           |           |           |                |           |
| B2<br>horizontal | Q10L      | Q9L       | Q7L       | Q7R       | Q9R            | Q10R      |
|                  | β = 164 m | β = 17 m  | β = 60 m  | β = 173 m | β = 106 m      | β = 30 m  |
|                  | new       |           | new       | existing  | existing       |           |
| B2 vertical      | Q10L      | Q9L       | Q7L       | Q7R       | Q9R            | Q10R      |
|                  | β = 36 m  | β = 140 m | β = 169 m | β = 23 m  | β = 34 m       | β = 181 m |
|                  |           | existing  | existing  | new       |                | new       |

New pick-ups to be made operational in YETS 2015/2016

### Reasons for change: "DSPU"



- need to combine four pick-ups
- Separate control for all features with high resolution calls for independent output DACs
- digital links to future diagnostics HW
- adequate number of spares missing

### New VME mDSPU for ADT signal processing



#### Status:

- Installed and operational
- New LSA functions for control operational
- New firmware, FESA classes, including for cleaning and blow-up

#### SPS as testbed:

Board is also in use in SPS since 2014 run

G. Kotzian, T. Levens, D. Valuch

### ADT during the cycle

#### Run 1 damping times:



Run 2: We can increase FB gain at flat-top (witness bunches with low gain)

### Commissioning status: Done

- Set-up for probe, nominal and 50 ns trains
- Transverse blow-up (loss maps etc.)
- Functions in ramp: values programmed
- Cohabitation with BBQ with low gain on witness bunches
- Link for chirp sent from BI
- Abort Gap cleaning: Basic set-up for 450 GeV
- Injection Oscillation display
- Logging (under verification, some issues)
- Damping gain measurement and optimization, calibrations
  - < 50 turns at 450 GeV, single bunch</p>
  - < 100 turns at 6.5 TeV, single bunch ?</pre>

### Run 1 performance with 50 ns trains (1<sup>st</sup> bunch of injected train)

Need to recover this



A. Macpherson CERN BE-OP & BE-RF

(first bunch of train)

5 Feb 2014

LMC

### Commissioning status: To do (musts for MJ in red)

- Injection gap cleaning (needed to inject long bunch trains)
- Abort gap cleaning at 6.5 TeV
  - Commission procedures linking abort gap cleaning to abort gap monitor (automatic switch-on was planned)
  - Pulse shape is bipolar, optimization of edges to limit effect outside gap
- 50 ns trains: frequency response and hold algorithm to push gain
- Bunch trains 25 ns  $\rightarrow$  full set-up of fine delay
  - > 20 MHz BW commissioning, frequency response optimization
  - 25 ns trains can be injected with the 50 ns basic settings (bandwidth will be limited to 10 MHz)
- verify post mortem
  - concurrent use of post mortem buffer for observation during scrubbing run

### Commissioning status: To do (including "exotics")

- Settings switching between probe and nominal
  - joint development between OP and RF (Daniel, Reyes)
- Flat frequency response in squeeze and collide Beam Process
- Scrubbing doublet beam set-up and commissioning
  - first test with trains during first scrubbing run
- Deployment of "observation box" to collect ADT data for studies and potentially tune feedback
- Connect, configure and commission triggering via the instability trigger network
  - First application of instability trigger network in BI: connection of headtail monitor and BBQ

### State Machine for Intensity Switching



- will be extremely useful to have probes visible
- can be extended to automatic switching between settings for bunch spacing
- needs thorough check before roll-out

R. Alemany, D. Valuch

### Towards 25 ns operation in 2015



LHC ADT 2012 performance

IPAC'13, WEPME43

### LHC ADT BPOS: Readiness for scrubbing beam



→ current and future LHC ADT HW ready for 5 ns bunchlets requires separate set-up (fine delays for clocks)

### Conclusions

- ADT hardware and software for power and lowlevel are ready for MJ beams
- Commissioning is well advanced
- Abort gap and injection gap cleaning a must for MJ beams, need commissioning time, commissioning of abort gap cleaning started with 450 GeV, to do 6.5 TeV
- Bunch trains at 25 ns and 50 ns as well as doublet beams need set-up time
- Recovering Run 1 performance and reacting to requirements from tune feedback and to fight instabilities is an iterative optimization process