

HL_LHC, WP9

Update of Cryogenic Baseline P4-RF, IR1/5 and SPS-BA6



**High
Luminosity
LHC**



S. Claudet, 27 Oct'15


On behalf of Cryo team involved in HL_LHC activities

Content

- *Baseline Autumn 2014 and evolution since*
- *IR 1/5, evolution and perspectives*
+ Talk Rob van Weelderen @ WP3 Wed. pm
- *P4-RF, evolution and perspectives*
- *SPS-BA6, new baseline*
+ Talk L. Delprat @ WP6 Friday am
- *Complementary items*
- *Summary*

Overall HL-LHC cryogenic layout

- HL-LHC cryo-upgrade:
 - 2 new cryoplants at P1 and P5 for high luminosity insertions
 - 1 new cryoplant at P4 for SRF cryomodules *Alternative under study?*
 - New cooling circuits at P7 for SC links and deported current feed boxes
 - Cryogenic design support for cryo-collimators and 11 T dipoles at P1, P3, P5 and P7



Some changes in HL-LHC baseline since:

- No sc links at P7
- 11T dipoles + collimators: 1 or 2 pairs + P1/P5 as options
- Crab cavities @SPS-BA6


- Existing cryoplant
- New HL-LHC cryoplant
- Cryo-collimator

HL-LHC, Cryo general schedule *C&S Review March'15*

To be updated by end 2015

New dates for
Crab Cavities @ SPS


Global shift,
Now to be controlled



▼ : decision/freeze of heat-loads to specify refrigerator and distribution


+ possible work on some Q5@P6
+ LSS2-LSS8 beam-screens ?

P1/P5 Cryogenic architecture



Flow diagram IT+D1 - R5


Preliminary 2015, exists as well for SAM's, not yet for Crab Cavities



P1/P5 Main evolutions of the baseline

- General lay-out and integration:
 - Current leads (DFH) in underground area
 - Efforts towards integration and definition for Civil Eng. Works
 - Flow diagrams now prepared for LSS
- Others:
 - Validation of cooling scenario for new triplets and D1 magnets
 - Safety/risk analysis for sc links (MCI) initiated, to be continued
 - Availability studies: always 8 sectors, but with 2x2 new LSS and 10/11 w.r.t 8 refrigerators, with challenge to keep global target availability of 95%
 - Preliminary studies for routing back-up lines for detectors cryogenic
- Next (2016):
 - From known heat loads, definition of P, T, m' for each circuit, and then sizing of process pipe and major components
 - Complete distribution scheme with overall Process & Flow diagram
 - Cooling scenario for transients, including quenches and degraded vacuum
 - Iterate on heat loads, integration, process optimisation

P4 - RF Status and perspectives



Original baseline: dedicated 4.5K Refrigerator for RF

(with in mind relative independence from magnets operation/constraints)

But:

- + It does not work so bad for time being (RF never really late for beam commissioning)
- Availability for HL beam operation would be reduced with increased number of cryoplants to be operated simultaneously
 - ideas summer 2014 to propose an upgradable refrigerator to match the RF needs (400MHz, then 800MHz as harmonic, switch to 200MHz with 400MHz as harmonic)
 - Clear understanding at [4th_LARP_KEK_Nov'14](#) meeting that real gain for RF would be to test a module anytime during a LS, while Cryo would do maintenance

=> Proposal of alternative: Upgrade + corresponding distribution + mobile Refrigerator Concept !
How much ? Anyway !

Evaluation of capacity per level of temperature



- Heat load management tool considering:
 - LHC heat load data
 - scaling laws (beam parameters)
 - configuration w.r.t time
- Conversion for static and dynamic heat loads into cooling capacity requirements based on an "LHC like" approach for capacity margins at nominal and ultimate

Conclusions

- The design capacity of *LHC Refr. S4-5* presents a cooling deficit of **≈2.5 kW @4.5 K** w.r.t the required specification for HL-LHC (Run5). This is equivalent to a massflow deficit of **≈118 g/s** on Line C.

Studies to be done:

- Clarify the technological & economical impact of an upgrade of *LHC Refr. S4-5* to cover the refrigeration demands for RUN5. The study of 3 different scenarios are suggested:

upgrade of **2.5 kW +/- 500 W @4.5 K**

- The cryo-refrigeration margin at the other LHC Refrigerators (specially S3-4) has to be analysed as well, in order to ensure that all HL-LHC sectors have a similar margin.

Refr. Specification for RUN5 HL-LHC

In Sector Refrigeration							
Heat Load [W]	50-75 K	4.5-20 K	4.5 K	1.8 K	3-4 K	20-290 K	
LHC design	33000	7700	300	2400	430	55416	
HL-LHC (Run5)	23070	8444	2721	1645	305	35246	
Margin	9930	-744	-2421	755	125	20169	
Refrigerator Interface							
Massflow in [g/s]	Line F	Line E	Line D	Line C	Line B	Line LC	
LHC design	251.3	251.3	194.4	255.1	-	41.0	
HL-LHC (Run5)	175.7	175.7	328.2	352.3	-	24.1	
Margin	75.6	75.6	-133.8	-117.2	-	16.9	


Upgrade of
2.5 kW +/- 500 W @4.5 K
for *LHC Refr. S4-5* required!

(+14% on 18kW)



Presently under
feasibility evaluation
(internally at CERN,
possibly with industry)

Sector 45 w.r.t other sectors

Margin at refrigerator level for Run5 => HL_Ultimate



P4-RF distribution line




Connection to QRL and distribution along the existing and “future” RF zone (+e-lens!) to be looked at for present baseline and alternative scenario

RF tests refrigeration concept

Simplified infrastructure w.r.t baseline



LHC-P4 during Long Shutdowns




Cryo infrastructure for Crab Cavities

- Change of Baseline SPS-BA4 to SPS-BA6 June'15, with completely new cryogenic infrastructure required (considered during decision process)
- Studies started for new refrigerator, distribution line, gas storage, valve boxes, ...
- But before that, technology validation is required at SM18, with specific interface required towards cryo distribution line in bunker M7 (1st on schedule!)
- Basic (re-)scheduling to be made considering installation/connection windows (shut-downs at SM18 and E-YETS at SPS)

RF tests refrigeration concept

SPS-BA6 during beam Runs




Specific
meetings/studies/reviews
on the subject
(including Friday morning)


Locating the cold box
underground would really
simplify cryo-distribution

RF tests refrigeration concept

SPS-BA6 during beam Runs



LHC-P4 during Long Shutdowns




“mobile” concept validated by industry

Summary for WP9-Cryogenics

- Studies for P1/P5 have progressed for:
 - Heat transfer in cold masses (steady state confirmed, to be done for transients)
 - First overall integration scenario completed (double-decker), incl. infrastructure
 - Flow diagrams, global process schemes and 1st sizing of components started
- P4-RF alternative scenario defined:
 - Required upgrade quantified, under feasibility evaluation before baseline change
 - Distribution scheme to be re-evaluated accordingly
- Crab cavities test areas: should be looked at with more priority/resources
 - Cryo infrastructure for technology tests at SM18 (from definition to procurement)
 - Completely new Cryo infrastructure for SPS-BA6 to be provided, with long lead items like refrigerator now to be specified (2015-Q4) and orderered (2016_Q1)
- Various alternative or long-term studies initiated (safety, availability, modifications of existing equipment, Beam Screens for LSS @ P2/P8, Q6@P1/P5, back-up detectors)

=> 2016: many fronts now opened, increased resources required to achieve results

Towards an update of Cryo baseline




Few hints for sc links safety aspects

He inventory: LHC 800 kg per sectorised_volume, sc link 50 kg (300 Nm3)

LHe160l-GHe160l-100mDiam100+shield


Sectorisation: Valves from QRL/QXL to close on triggers to prevent He supply to damaged area

=> Should not be a major issue, and without specific requirements for additional volume and infrastructure




Extra cooling capacity needed

Estimation of HL-LHC heat loads





For completeness, brief description of the model/methodology





Operation Parameters*					
E [TeV]	$L \times 10^{31}$ [Hz/cm ²]	Nb [$\times 10^{11}$]	nb [f]	σ_z [m]	
4	0.77	1.5	1380	0.7	LHC 4 TeV
6.5	1.5	1.15	2808	1.06	LHC 6.5 TeV
7	2.3	1.7	2808	1.06	LHC Ultimate
7	5.1	2.2	2748	1.08	HL-LHC Nominal
7	5.1	2.2	2748	1.08	HL-LHC Nominal
7	7.6	2.2	2748	1.08	HL-LHC Ultimate

orange values to be confirmed!

Heat loads* sector 4-5 (on "LHC nominal")



* Reference documents: LHC Design Report and CERN-ACC-NOTE-2015-0009



Global equivalence would tell that there is sufficient margin