


BIS installation in Linac4

For 50 MeV operation

Stéphane Gabourin
on behalf of TE/MPE-EP

MPP Linac4 – 9th July 2015

- For the 50MeV phase, the beam is stopped in the Chopper
- The BICs “Source RF”, “Choppers” and “L4” are used.
- Modifications have to be implemented into both masters



Modifications for the Master BIC “Source RF”

Define a suitable BIC equation for the source start procedure:

“During a source start-up the nominal conditions are very different from those during standard operation; the beam stopper is “in” and no BIS signal or interlock software should interfere with source operation until the completion of conditioning” (J.Letry)

Solution:

- 1) Install a new CIBU near the source

This CIBU named *Source Start* will be installed inside the source rack and will be manually controlled by a switch. The cable is already pulled; this solution will be operational for the 50MeV phase.

- 2) Add a new equation for the “Source RF” BIC

0	1	2	3	4	5	6	7	8	9	10	11	12	13
SIS	Source Start	Source Internal	Source HV	Pre-chopper	Source Beam Stoppers Out/Moving	Source Beam Stoppers In	Chopper	L4 Low-Energy Watchdog	L4 Low-Energy Vacuum Valves	L4L-ChopperQuads	RFQ	Commissioning Dump status	L4 Operator Veto
1	0	1	1	1	1	0	1	1	1	1	1	1	1
1	0	1	1	x	0	1	x	x	1	x	x	x	x
1	1	x	x	x	0	1	x	x	x	x	x	x	x

➤ 3) Add a new condition in the SIS

Some signals are monitored by the **SIS**; during the source start these signals must be forced to **TRUE**.

Important:


While the *Source Start* gives a user permit to **TRUE**, the BIS is not responsible for the safety of the Source (*Source Internal* and *Source HV* are ignored).

50 MeV implementation:

0	1	2	3	4	5	6	7	8	9	10	11	12	13
SIS	Source Start	Source Internal	Source HV	Pre-chopper	Source Beam Stoppers Out/Moving	Source Beam Stoppers In	Chopper	L4 Low-Energy Watchdog	L4 Low-Energy Vacuum Valves	L4L.ChopperQuads	RFQ	CCC Operator Veto	L4 Operator Veto
1	0	1	1	1	1	0	1	1	1	1	1	1	1
1	0	1	1	x	0	1	x	x	x	x	x	x	x
1	1	x	x	x	0	1	x	x	x	x	x	x	x


Modifications for the BIC “Choppers”

Issue with the Beam Permit redundancy on the Pre-chopper:



- In normal operating conditions the Pre-chopper receives 2 Beam Permit signals for redundancy reasons
- When downstream elements (like *Valve 1&2*) provide a User Permit to **TRUE**, the Beam Permit signals are both **TRUE** (all other User Permit signals must also be **TRUE** ...)
- ✓ The BIS functionality is as expected in the Engineering specification

If the Stopper is "IN" position :




	1	2
SOFTWARE INPUT	TRUE	TRUE
1 Source Internal	TRUE	TRUE
2 Source HV (masked!)	TRUE	TRUE
3 Pre-chopper	TRUE	
4 Source BeamStopper...	TRUE	FALSE
5 Source BeamStopper...	FALSE	TRUE
6 Chopper	TRUE	
7 L4 Watchdog	TRUE	
8 L4 Low-Energy Vacuu...	TRUE	
9 AQN L4L-QUADS (bou...	TRUE	
10 RFQ	TRUE	
11 Commissioning Dump	TRUE	
12 L4 Operator Veto	TRUE	

Master BIC RF₈


- The second equation of the BIC RF is selected (Beam Stopper IN), Valve 1 is not taken into account
- If the Valve 2 gives a User Permit to **TRUE**, The functionality is as expected, the beam is sent to the stopper (stability of the source)

If the Stopper is “IN” position but *Valve 2* gives a FALSE:



- The Pre-chopper is “stopped” and the beam is “diluted” at 45 KeV in the line.
- In these conditions the beam never reaches the faraday cup nor the stopper.

- The problem is the same with all other BICs + downstream elements (except the Ejection BIC). If one of the User permit goes to FALSE, the beam is diluted at 45KeV as the source is not stopped.



What we want:

- Keep redundancy on “Pre Chopper” for safety reason
- When the *Beam Stopper In* is **TRUE**,
the Beam Permit “Pre Chopper” must be **TRUE**
- When the *Beam Stopper Out/Moving* is **TRUE**,
the Beam Permit “Pre Chopper” must be **TRUE** only if all others users are **TRUE** for the required destination
- => The User permits *Beam Stopper In* and *Beam Stopper Out/Moving* have to be considered by the BIC “Choppers”

50 MeV implementation:

- Master Chopper to install (before was only the L4 slave BIC)
- Two out of the Four equations will be used
- Two **new connections** for the Beam Stoppers
- L4 slave BIC is now only **one of the inputs**
- 3 CIBUs to install for inputs 4, 5 & 6 => **forced permits** (bouchon/strap)
- All other inputs not considered

Linac 4	
0	SIS
1	External Conditions (full pulse)
2	L4 Vacuum Valves + (L4T.VVGS.0101)
3	BLM s L4+L4Z
4	<i>not used</i>
5	WIC L4
6	Diamond Detector Test
7	<i>not used</i>
8	L4 RF
9	<i>not used</i>
10	<i>not used</i>
11	<i>not used</i>
12	<i>not used</i>
13	<i>not used</i>
14	<i>not used</i>
OUT	Linac4 OK

Linac 4 Choppers					
0	SIS	1	1	1	1
1	Source Beam Stoppers Out/Moving	0	1	1	1
2	Source Beam Stoppers In	1	0	0	0
3	Linac4 OK	x	1	1	1
4	AQN L4T.MBH_DUMP	x	1	0	0
5	L4Z OK	x	1	x	x
6	AQN L4T.MBH_LT	x	0	1	1
7	Linac4 Transfer OK	x	x	1	1
8	AQN LTB.BHZ40_LBE	x	x	1	0
9	LBE OK	x	x	1	x
10	AQN LTB.BHZ40_PSB	x	x	0	1
11	PSB Injection 1 OK	x	x	x	1
12	PSB Injection 2 OK	x	x	x	1
13	PSB OK	x	x	x	1
14	<i>not used</i>	x	x	x	x

Beam to Stopper

Beam to Dump

Beam to LBE

Beam to PSB

} new connections

} forced permits

not considered