



LHC Accelerator *Status and Plans*

Frank Zimmermann,
CERN, AB Department

17 September 2008

finally there!

1983 LEP Note 440 - S. Myers and W. Schnell propose twin-ring pp collider in LEP tunnel with 9-T dipole field; idea stimulated by G. Brianti

> 25 years ago

1991 CERN Council: LHC approval in principle

1992 Eol, Lol of experiments

1993 SSC termination


1994 CERN Council: LHC approval

1995-98 cooperation w. Japan, India, Russia, Canada, & US

2000 LEP completion

2006 last s.c. dipole delivered

2008 first beam



design parameters

c.m. energy = 14 TeV
 luminosity = $10^{34} \text{ cm}^{-2}\text{s}^{-1}$

1.15×10^{11} p/bunch
 2808 bunches/beam

360 kJ/beam


$\gamma\epsilon = 3.75 \text{ } \mu\text{m}$
 $\beta^* = 0.55 \text{ m}$
 $\theta_c = 285 \text{ } \mu\text{rad}$
 $\sigma_z = 7.55 \text{ cm}$
 $\sigma^* = 16.6 \text{ } \mu\text{m}$

$\Phi = 0.64$ (Piwinski angle)

LHC s.c. dipole magnet – 8.33 T




LHC DIPOLE : STANDARD CROSS-SECTION



all s.c. magnets were tested in “SM18”



Cumulative Cold Tested Magnets





L. Evans

L. Rossi

LHC tunnel 2002




L. Rossi

LHC tunnel 2006

L. Rossi




ring is cooled down to 1.9 K



15 Sep 2008


LHC powering in 8 sectors



P.Proudlock, R. Schmidt, K.-H. Mess


**1720 circuits (1695 cold,
217 with current >4000A)**
for comparison - HERA: 1 main circuit, 90
cold corrector circuits, 20 times "easier"

ramping current in string of dipole magnets




- LHC **powered in eight sectors** (154 dipole magnets each)
- Time for energy **ramp**: **~20-30 min** (energy from the grid)
- Time for discharge: **~the same** (energy back to the grid)

LHC magnetic cycle



LHC quench protection

R. Schmidt




- when one magnet quenches, **quench heaters** are fired for this magnet
- current in quenched magnet decays in about 200 ms
- the current in all other magnets flows through the **bypass diode** that can stand the current for about 100-200 seconds; **resistors** are switched in series

bypass diode

energy extraction system in LHC tunnel



LHC/ICP



resistors absorbing the energy

switches - for switching resistors into series with magnets

Extraction facilities in the OA's in Dipole and QF/QD circuits


F.Rodriguez-Mateos, K.Dahlerup-Petersen, R. Schmidt


F.Rodriguez-Mateos, D.Hagedorn, R. Schmidt

training quench example at 9859 A


- ❑ Natural quench in A22R4 (magnet name 3176)
- ❑ 4 magnets quenched (3 after quench propagation)
- ❑ Sequence of events:

Magnet	Cryogenic cell	Local time	t quench [s]	I quench [kA]	E [MJ]
A22R4	21R4	16:50:34.947	0	9.859	4.957
B22R4	21R4	16:51:24.679	49.732	6.011	1.843
C22R4	21R4	16:52:07.532	92.589	3.829	0.748
C21R4	19R4	16:52:41.798	126.855	2.644	0.357
Total					7.905






first beam induced quench at injection with $< 4 \cdot 10^9$ protons ($\sim 10^{-5}$ of design intensity)



B. Jeanneret et al, LHC Project Report 44 (1996)
"The intensity of the bunch shall therefore not be much larger than $3 \cdot 10^9$ protons."


First Beam Induced Quench

B. Dehning



hardware commissioning in 2008

successful test steps (total #tests > 10000)



start up 10 September “D-Day”

08.30 Beam to TEDS both lines. Interleaved injection beam 1 & 2.

09.00 Switch to beam 1 only. Kickers executing soft start.

09.30 Beam to TDI. Kickers on.

09.40 TDI out. Beam to collimators point 3.

09.45 Collimators IP3 out. Beam to left of point 5.

09.55 Collimators point 5 out, beam ~to point 6 but not to extr. line.

10.00 Beam to dump block (steered with DC bump). **Half way round!**


10.08 Beam to collimators in point 7.

10.12 Beam to point 8 collimators.

10.30 Beam 1 round > 1 turn (image on screen showing beam on first and second turns, image of trajectory – next slides)


With a bit of correction - beam makes 3 turns (next slides)

beam 1 around ring in less <1 hour (12 h's in LEP!)





10 Sep 2008 15:02

Updated by Roberto Saban




1st turn trajectory beam 1






High point of the day was to have made *Google!*





images from ATLAS with beam on collimator in front of them



“D-Day” afternoon – beam 2

non-serious cryogenics problem delays beam 2 inj. until 13:30

Switch to beam 2 only.

13.30 onto the TDI

13.40 TDI out, beam to point 3.

Cryogenic instability needs a little more time

13.55 Beam to 6, steered into start of dump line

14.05 Beam to left of 6. Lost. Investigating.

14.25 Problem understood. Beam to right of 5. 20 shots for CMS.

14.40 Beam round to 3 (after one correction in 4). Few corrections.


14.45 Beam to ALICE.

14.50 Beam to ATLAS. Few shots for them.

Few minutes no beam. Reboot for screen server.

15.00 Beam > 1 turn

*beam 2 around the ring in 1 .5 hours; longer than beam 1
(no beam, corr. problem pt 6, shots for CMS, ALICE & ATLAS)*



Run 62063, Event 2433, Orbit 15231634, BX 680

One of the first image from CMS when the beam hitting the collimators at Point 5

“D-Day” evening

16.00 Beam 2 to collimators ATLAS

Dispersion data

Kick response data

In parallel BI looking at BPM acquisition for >1 turn

18.00 Inject and dump commissioning (all collimators out)

Inject and dump up to 9 turns OK.

20.00 BPM acquisition for multiple turns sorted out

Trimming Q_h , Q_v , Q'


21.30 Beam 2 makes at least 300 turns!

Fast BCT data and tune measurements - Q_h .31 Q_v .23

23.00 Start systematic polarity checks of orbit correctors

LHC Longitudinal Bunch Profile Beam2

➤ 300 turns, D-Day, 21:30
(beam is debunching, not lost)





C1 200mV/div 50Ω BW:2.5G

A C1 172mV

3.2ms 2.5GS/s 400ps/pt

Run Sample
24 acqs RL:80.0M
Mon September 10, 2008 21:46:01

Views [10/09/08 21:39:36]



Acquisition Configuration

Capture Settings

B 1 B 2

Bunch selection

Continuous Individual

3500-3510

Turns: 144

Turn Increment: 2

Trigger Condition

GMT

RF Injection Prepulse

Software

Get Set

Console Running tasks

```
captureSettingTime (String:1) --> Wed Sep 10 21:29:21 2008
```

21:39:36 - Ready.

Tune Viewer - LHC - On-demand FFT system B2

File Run Configure Help

RBAC User: LHC LHC.BQBBQ.UA47.FFT2_B2 LHC.BQPLL.UA43.PLL_B2 LHC.OFSU

Info FFT PLL Data Sets Feedback

Q-FPGA

Tune Measurements

LHC - B2 - Fill#830
 2008-09-10 21:38:52
 RAW&FFT: 256 turns@1.0Hz
 no excitation
 Q1 = .3092 Qx = .3089
 Q2 = .2333 Qy = .2337
 |C-| = .0106
 Q'x = ???
 Q'y = ???
 Comments:
 no comment

Spawn TuneViewer Display

⏪
▶
⏩
⏸
■

21.38.57 - <4> Start multiple monitoring on user LHC

Graph Mag H || ACQ# 0 Scale

LHC - B2 - fill #830 - no comment - LHC.BQBBQ.UA47.FFT2_B2 - 2008-09-10 2...

horizontal amplitude [dB]

frequency [frev]

Graph RAW V || ACQ# 0 Scale

LHC - B2 - fill #830 - no comment - LHC.BQBBQ.UA47.FFT2_B2 - 2008-09-10 2...



vertical amplitude [a.u.]

turn

other findings from “D-Day”



- **rms orbit < 1.5 mm rms**, for beam 2 in both planes
< 1mm with 2.5 mm peak should easily be possible
(4 mm peak is LHC design value)
- **250 of 1000 orbit correctors were tested** with beam 2 – **all**
responded with **correct sign, and within 5%** of expectation
- tunes set to 0.4, 0.2-0.3 in vertical
tune trims of order 0.4 in vertical, less horizontally
- chromaticity yet to be measured (cannot be too bad; from
detuning)
- a little bit of coupling
- BPMs work, FBCT work, screens work, BLMs work,...
- **energy of both beams within 1 per mill of SPS**
- **<15 mm error in circumference w.r.t. design for beam 2**

very first look at dispersion



“ring dispersion” after correcting for incoming dispersion oscillation; error in IR3 and perhaps IR6

vertical dispersion ~zero within noise



Thursday & Friday, 11-12 Sept.'08

R. Bailey

“Inject and dump”

“Circulate and dump after 50 ms”

“Circulate - dump request”

RF capture working – for beam 2 !

Integer tunes OK

Longitudinal pickup & mountain range display working

Systematic polarity checks

Circulating beam

Beta-beat measurement


Wire scan H and V works

Friday ~23:30 high-V transformer fault in pt 8

Name	Type and Value	Axis
acqTypeMaxNumber	(short[]):5 -> 0, 0, 1, 0, 0	


Active keys : [X] -> x axis, [Y] -> y axis, [Z] -> z axis (image), [D] -> display line, [H]->display histogram, [SPACE] -> clear, [T] -> time/numbers on x axis

Data for Cycle: -



Point # 31852 X -58.354400000000005 Y -62.7396 Z 461.0

J. Wenninger




tunes 64 and 59 as design (vertical FFT has second peak!?)

A. Butterworth, RF Group

longitudinal
mountain
range
recorded
~5 minutes
after
rf capture

beam lifetime
~infinite
(too good to be
measured;
many hours)



DC-lifetime B1:

-1.31e+00 s

DC-lifetime B2:


1.60e+00 s

12-09-2008 02:36:28

LHC-BCT R1

BCT Ring 1

Updated: 02:36:29




BCT Ring 1

LHC-BCT R2

BCT Ring 2

Updated: 02:36:28




BCT Ring 2

LHC-BCT Lifetimes

BCT Lifetimes

Updated: 02:36:29



BCT LIFETIME Beam 1 BCT LIFETIME Beam 2

No Overflow Detected

- Scaling
- Aggressive
 - Manual
 - Auto

Fixed Error:


- Select Fit Type
- 5 param gauss
 - 3 param gauss
 - RMS Width Calc
 - Show Front End Fit
 - Percent Peak Elimination

- Data Smoothing
- None
 - 3-pt
 - 5-pt

- Select Profiles
-
- Hover over box to see bunch #
Update: Now Later


Views Ignoring Stale Data

Bunch no. 1 [12/09/08 13:37:19]




very first look at beat beating



LHCb2, 90 turns (12/09/08 12:38:16)



LHCb2, 90 turns (12/09/08 12:38:16)



data over 90 turns
taken during
vertical
orbit correction



R. Tomas, M. Aiba

commissioning so far superfast

but challenges ahead:

- ramping in energy (up to 5 TeV)
- higher intensity
- squeeze
- 7 TeV

tentative plan

when beam is back (Thursday), **continue commissioning:**
beam 1, rf capture, correct optics, chromaticity etc


first attempts to **ramp to ~600 GeV** over the weekend or
during next week


a few shifts with **collisions at 450 GeV**

~1 week stop to complete hardware commissioning and
qualify interlock systems before going to higher intensity
and/or higher energy


then ramp to **5 GeV, squeeze, and physics run** through end of
the year

machine protection system





First collisions – 2 on 2, clean collisions everywhere



$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$


4 10^{10} per bunch
450 GeV 11m
 $\sim 10^{27} \text{ cm}^{-2} \text{ s}^{-1}$

ATLAS sees **11**
CMS sees **11**
ALICE sees **32**
LHCb sees **12**


Beam - gas
Both beams


lower commissioning energy ~ 5 TeV

- no quenches up to 5 TeV
(based on SM18 & S45)
- quench recovery much faster below
9 kA (~ 5 TeV) magnet current
- saving in powering tests (200-300 A
sufficient for most 600 A circuits)
- beam operation easier at 5 TeV
(magnets much farther away
from quench limit)





Strategy for 2008 and 2009





Stage A: routes through the commissioning phases






Stage A: 5TeV collisions

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$\text{Eventrate / Cross} = \frac{L \sigma_{TOT}}{k_b f}$$

- Approx 30 days of beam to establish first collisions
- Approx 2 months elapsed
 - Given optimistic machine availability
 - Un-squeezed
 - Low intensity
- Continue commissioning thereafter
 - Increased intensity
 - Squeeze

Parameters			Rates in 1 and 5	
k_b	N	β^* 1,5 (m)	Luminosity (cm ⁻² s ⁻¹)	Events/crossing
1 (3)	10 ¹⁰	11	1.1 10 ²⁷	<< 1
4	10 ¹⁰	11	4.5 10 ²⁷	<< 1
43	10 ¹⁰	11	5.0 10 ²⁸	<< 1
43	4 10 ¹⁰	11	8.0 10 ²⁹	<< 1
43	4 10 ¹⁰	3	2.9 10 ³⁰	0.36
156	4 10 ¹⁰	3	1.0 10 ³¹	0.36
156	9 10 ¹⁰	3	5.4 10 ³¹	1.8



Parameter evolution and rates


$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$\text{Eventrate / Cross} = \frac{L \sigma_{TOT}}{k_b f}$$

All values for nominal emittance, 10m β^* in points 2 and 8

All values for 936 or 2808 bunches colliding in 2 and 8 (not quite right)

Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8		
k_b	N	β^* 1,5 (m)	I_{beam} proton	E_{beam} (MJ)	Luminosity ($cm^{-2}s^{-1}$)	Events/crossing	Luminosity ($cm^{-2}s^{-1}$)	Events/crossing	
5 TeV	43	4 10^{10}	11	1.7 10^{12}	1.4	8.0 10^{29}	<< 1	Depend on the configuration of collision pattern	
	43	4 10^{10}	3	1.7 10^{12}	1.4	2.9 10^{30}	0.36		
	156	4 10^{10}	3	6.2 10^{12}	5	1.0 10^{31}	0.36		
	156	9 10^{10}	3	1.4 10^{13}	11	5.4 10^{31}	1.8		
7 TeV	936	4 10^{10}	11	3.7 10^{13}	42	2.4 10^{31}	<< 1	2.6 10^{31}	0.15
	936	4 10^{10}	2	3.7 10^{13}	42	1.3 10^{32}	0.73	2.6 10^{31}	0.15
	936	6 10^{10}	2	5.6 10^{13}	63	2.9 10^{32}	1.6	6.0 10^{31}	0.34
	936	9 10^{10}	1	8.4 10^{13}	94	1.2 10^{33}	7	1.3 10^{32}	0.76
	2808	4 10^{10}	11	1.1 10^{14}	126	7.2 10^{31}	<< 1	7.9 10^{31}	0.15
	2808	4 10^{10}	2	1.1 10^{14}	126	3.8 10^{32}	0.72	7.9 10^{31}	0.15
	2808	5 10^{10}	1	1.4 10^{14}	157	1.1 10^{33}	2.1	1.2 10^{32}	0.24
	2808	5 10^{10}	0.55	1.4 10^{14}	157	1.9 10^{33}	3.6	1.2 10^{32}	0.24



Configuration of collision pattern

- **25ns and 75ns operation**

- Nothing to do
- Collisions determined by bunch pattern

- **43 or 156 bunch operation**

- Can optimise according to needs
- Previously thought to displace bunches in one beam (asym)
- Can do better (symmetrically displace bunches in both beams)
- Allows to adjust luminosity sharing between 2 and 8 while keeping maximum number of collisions in 1 and 5

	75ns	25ns
IP 1	936	2808
IP 2	912	2736
IP 5	936	2808
IP 8	874	2622

Displaced	0	4 asym	4 sym	11 sym	19 sym	0	36 sym	68 sym
IP 1	43	39	43	43	43	156	156	156
IP 2	42	38	34	21	4	152	76	16
IP 5	43	39	43	43	43	156	156	156
IP 8	0	4	4	11	19	0	36	68


LHC Upgrade

Unlike the Tevatron or LEP, the LHC already has all the attributes to go very quickly to design luminosity .

It is reasonable to assume that the machine will reach $10^{34} \text{ cm}^{-2} \text{ s}^{-1}$ on a 5-year timescale.

It is therefore necessary to plan an upgrade path now in order to be able to open the door to a factor of 4-5 improvement on the same timescale.

Two Strong Reasons for LHC Upgrade



- 1) after few years, **statistical error** hardly decreases
- 2) radiation damage limit of **IR quadrupoles** ($\sim 700 \text{ fb}^{-1}$) reached by ~ 2016
 \Rightarrow time for an upgrade!
- 3) **extending physics potential!**

staged approach to LHC upgrade

“phase-1” 2013:

new triplets, D1, TAS, $\beta^*=0.25$ m in IP1 & 5,
reliable LHC operation at $\sim 2\text{-}3\times$ luminosity;
beam from new Linac4

“phase-2” 2017:

target luminosity $10\times$ nominal,
possibly Nb₃Sn triplet & $\beta^*\sim 0.15$ m

***+ injector
upgrade***

complementary measures 2010-2017:

e.g. long-range beam-beam compensation,
crab cavities, new/upgraded injectors, advanced
collimators, coherent e- cooling??, e- lenses??


phase-2 might be just phase-1 plus complementary measures

longer term (2020?): energy upgrade, LHeC,...

LHC upgrade paths for IP1 & 5

early separation (ES)


J.-P. Koutchouk



- ultimate beam (1.7×10^{11} protons/bunch, 25 spacing), $\beta^* \sim 10$ cm
- early-separation dipoles in side detectors, crab cavities
→ hardware inside ATLAS & CMS detectors, first hadron crab cavities; off- δ β

full crab crossing (FCC)


L. Evans,
W. Scandale,
F. Zimmermann



- ultimate LHC beam (1.7×10^{11} protons/bunch, 25 spacing)
- $\beta^* \sim 10$ cm
- crab cavities with 60% higher voltage
→ first hadron crab cavities, off- δ β -beat

large Piwinski angle (LPA)

larger-aperture triplet magnets



F. Ruggiero,
W. Scandale,
F. Zimmermann


- 50 ns spacing, longer & more intense bunches (5×10^{11} protons/bunch)
- $\beta^* \sim 25$ cm, no elements inside detectors
long-range beam-beam wire compensation
→ novel operating regime for hadron colliders, beam generation

parameter	symbol	nominal	ultimate	Early Sep.	Full Crab Xing	L. Piw Angle
transverse emittance	ϵ [μm]	3.75	3.75	3.75	3.75	3.75
protons per bunch	N_b [10^{11}]	1.15	1.7	1.7	1.7	4.9
bunch spacing	Δt [ns]	25	25	25	25	50
beam current	I [A]	0.58	0.86	0.86	0.86	1.22
longitudinal profile		Gauss	Gauss	Gauss	Gauss	Flat
rms bunch length	σ_z [cm]	7.55	7.55	7.55	7.55	11.8
beta* at IP1&5	β^* [m]	0.55	0.5	0.08	0.08	0.25
full crossing angle	θ_c [μrad]	285	315	0	0	381
Piwinski parameter	$\phi = \theta_c \sigma_z / (2 * \sigma_x^*)$	0.64	0.75	0	0	2.0
hourglass reduction		1.0	1.0	0.86	0.86	0.99
peak luminosity	L [$10^{34} \text{ cm}^{-2}\text{s}^{-1}$]	1	2.3	15.5	15.5	10.7
peak events per #ing		19	44	294	294	403
initial lumi lifetime	τ_L [h]	22	14	2.2	2.2	4.5
effective luminosity ($T_{\text{turnaround}}=10 \text{ h}$)	L_{eff} [$10^{34} \text{ cm}^{-2}\text{s}^{-1}$]	0.46	0.91	2.4	2.4	2.5
	$T_{\text{run,opt}}$ [h]	21.2	17.0	6.6	6.6	9.5
effective luminosity ($T_{\text{turnaround}}=5 \text{ h}$)	L_{eff} [$10^{34} \text{ cm}^{-2}\text{s}^{-1}$]	0.56	1.15	3.6	3.6	3.5
	$T_{\text{run,opt}}$ [h]	15.0	12.0	4.6	4.6	6.7
e-c heat SEY=1.4(1.3)	P [W/m]	1.07 (0.44)	1.04 (0.59)	1.04 (0.59)	1.04 (0.59)	0.36 (0.1)
SR heat load 4.6-20 K	P_{SR} [W/m]	0.17	0.25	0.25	0.25	0.36
image current heat	P_{IC} [W/m]	0.15	0.33	0.33	0.33	0.78
gas-s. 100 h (10 h) τ_b	P_{gas} [W/m]	0.04 (0.38)	0.06 (0.56)	0.06 (0.56)	0.06 (0.56)	0.09 (0.9)
extent luminous region	σ_l [cm]	4.5	4.3	3.7	3.7	5.3
comment		nominal	ultimate	D0 + crab	crab	wire comp.

luminosity leveling

initial luminosity peak may not be useful for physics (set up & tuning?)

experiments prefer ~constant luminosity, less pile up at start of run, higher luminosity at end




how can we achieve this?


ES or FCC: dynamic β squeeze, or dynamic θ change (either IP angle bumps or varying crab voltage)

LPA: dynamic β squeeze, or dynamic change of bunch length

IP1 & 5 event pile up for 25 & 50-ns spacing w/o leveling



upgrade bunch structures





HHH →

experimenters' choice (LHCC July 2008)

- ✓ no accelerator components inside detector
- ✓ lowest possible event pile up
- ✓ possibility of easy luminosity levelling

→ **full crab crossing upgrade**

New!







crab cavity motivation



$$R_\phi = \frac{1}{\sqrt{1 + \phi^2}}; \quad \phi \equiv \frac{\theta_c \sigma_z}{2\sigma_x} \text{ "Piwinski angle"}$$



effective beam size $\sigma \rightarrow \sigma/R_\phi$




CARE-HHH

LHC Crab Cavity Validation ~~HHH~~ →

Mini-Workshop, 21 August 2008




New!



Bob Palmer

invention
1988

first use in operating
ring collider 2007



- KEKB experience
- R&D plan
- phased approach:
 - (1) prototype
 - (2) "global" crab cavity test in IR4,
 - (3) "local" crab cavities in IR1 & 5
- EuCARD, US-LARP & international collaboration

global & local schemes considered for LHC



tentative schedule for crab-cavity prototype & first beam tests

HHH →
New!

Schedule T. Linnear, HHH Crab-Cavity Validation Workshop August 2009

		2008	2009	2010	2011	2012
R & D and test stand work	Cavity					
	Vertical test					
	HOM couplers					
	LOM coupler					
	Main coupler					
	Tuner					
	Cryostat					
Confirmation main parameters						
Full Prototype Design for installation	Cryostat plus cavity					
	Personnel / Hardware safety					
	Tunnel layout, cryogenics interface					
	Survey / Alignment					
	Radiation Issues					
	Cavity servo-control control					
	Synchronisation control					
	Slow controls					
	RF power source					
Paperwork for review						
Design validation review						
Construction & Installation	Construction cryomodules					
	Full bunker tests					
	Construction power source					
	Construction electronics					
	System tests					
	Tunnel mods.					
	Installation					
	Beam tests					


local crab cavities together with IR phase-2 ~2017 ?

LHC injector upgrade


Reasons:

- need for **reliability**:
 - accelerators are old [Linac2: 1978, PSB: 1975, PS: 1959, SPS: 1976]
 - they operate far from their design parameters and close to hardware limits
 - the infrastructure has suffered from the concentration of resources on LHC during the past 10 years
- need for **better beam characteristics**


present and future injectors





layout of the new injectors



upgrade planning ...



forecast peak & integrated luminosity evolution



Collimation phase 2

Linac4 + IR upgrade phase 1

Goal for ATLAS Upgrade:
 3000 fb⁻¹ recorded
 cope with ~400 pile-up events each BC



Questions?