

- Introduction
- The TESLA Challenge
- Status of SRF Cavities
- Status of Others SC Linac Components
- Ongoing R&D and Perspectives
- Concluding Remarks

Next e+e- collider must be linear

- Synchrotron Radiation (SR) becomes prohibitive for electrons in a circular machine above LEP energies:

$$U_{SR} [\text{GeV}] = 6 \cdot 10^{-21} \cdot \gamma^4 \cdot \frac{1}{r[\text{km}]}$$


U_{SR} = energy loss per turn
 γ = relativistic factor
 r = machine radius

- RF system must replace this loss, and r scale as E^2
- LEP @ 100 GeV/beam: 27 km around, 2 GeV/turn lost
- Possible scale to 250 GeV/beam i.e. $E_{cm} = 500 \text{ GeV}$:
 - 170 km around
 - 13 GeV/turn lost

$$\gamma_{250\text{GeV}} = 4.9 \cdot 10^5$$


- Consider also the luminosity
 - For a **luminosity of $\sim 10^{34}/\text{cm}^2/\text{second}$** , scaling from b-factories gives ~ 1 Ampere of beam current
 - 13 GeV/turn x 2 amperes = **26 GW RF power**
 - Because of conversion efficiency, this collider would consume more power than the state of **California in summer: $\sim 45 \text{ GW}$**
- Both size and power seem excessive

Circulating beam power = 500 GW




TESLA

Competing technologies




TESLA

1.3 GHz - Cold




30 GHz - Warm



11.4 GHz - Warm

What to do for Luminosity?

$$L \propto \frac{N_e^2}{\sigma_x \sigma_y}$$



$$L \propto n_b \times f_{rep}$$

L = Luminosity

N_e = # of electron per bunch

$\sigma_{x,y}$ = beam sizes at IP

IP = interaction point

n_b = # of bunches per pulse

f_{rep} = pulse repetition rate

P_b = beam power

$E_{c.m.}$ = center of mass energy

$$L \propto \frac{P_b}{E_{c.m.}} \times \frac{N_e}{\sigma_x \sigma_y}$$


Parameters to play with

- ↓ Reduce **beam emittance** ($\epsilon_x \cdot \epsilon_y$) for smaller beam size ($\sigma_x \cdot \sigma_y$)
- ↑ Increase bunch population (N_e)
- ↑ Increase beam power ($P_b \propto N_e \times n_b \times f_{rep}$)
- ↑ Increase **beam to-plug power efficiency** for cost

Linear Colliders are pulsed

LCs are pulsed machines to improve efficiency. As a result:

- duty factors are small
- pulse peak powers can be very large



The TESLA challenge


Use **Superconducting RF**:

Higher Conversion Efficiency
Smaller Emittance Dilution

Physical limit at 50 MV/m

≥25 MV/m should be possible


Common R&D effort for TESLA




Held at Cornell University
July 23-26, 1990




1992 - TESLA Collaboration set up at DESY




SRF before TESLA



Carlo Pagani




Total >1000 meters
> 5 GV



LCWS 2004
Paris, 19 April 2004

1984/85: First great success

- A pair of 1.5 GHz cavities developed and tested (in CESR) at Cornell
- > 300 cavities produced for CEBAF at TJNAF for a nominal $E_{acc} = 5$ MV/m



32 bulk niobium cavities


- Limited to 5 MV/m
- Poor material and inclusions

256 sputtered cavities

- Magnetron-sputtering of Nb on Cu
- Completely done by industry
- **Field improved with time** $\langle E_{acc} \rangle = 7.8$ MV/m (Cryo-limited)

16 bulk niobium cavities

- Limited to 5 MV/m
- Poor material and inclusions
- Q-disease for slow cooldown



Poor material properties


- Moderate Nb purity (Niobium from the Tantalum production)
- Low Residual Resistance Ratio, RRR \longrightarrow Low thermal conductivity
- Normal Conducting inclusions \longrightarrow Quench at moderate field

Poor cavity treatments and cleanness

- Cavity preparation procedure at the R&D stage
- High Pressure rinsing and clean room assembly not yet established


Quenches/Thermal breakdown

- Low RRR and NC inclusions




Field Emission

- Poor cleaning procedures and material



Multipactoring

- Simulation codes not sufficiently performing



Q-drop at moderate field

When not limited by a hard quench (material defect)

Accelerating field improves with time

Large cryo-plants are highly reliable


Negligible lost time for cryo and SRF

Once dark current is set to be negligible


No beam effect on cavity performance

Once procedures are understood and well specified

Industry can produce status of art cavities and cryo-plants




Evolution of the Accelerating Field



Major contributions from: CERN, Cornell, DESY, CEA-Saclay

- 9-cell, 1.3 GHz



TESLA cavity parameters

R/Q	1036	Ω
E_{peak}/E_{acc}	2.0	
B_{peak}/E_{acc}	4.26	mT/(MV/m)
$\Delta f/\Delta l$	315	kHz/mm
$K_{Lorentz}$	≈ -1	Hz/(MV/m) ²



Eddy-current scanning system for niobium sheets




Cleanroom handling of niobium cavities

Preparation Sequence



- Niobium sheets (RRR=300) are scanned by eddy-currents to detect avoid foreign material inclusions like tantalum and iron
- Industrial production of full nine-cell cavities:
 - Deep-drawing of subunits (half-cells, etc.) from niobium sheets
 - Chemical preparation for welding, cleanroom preparation
 - Electron-beam welding according to detailed specification
- 800 °C high temperature heat treatment to stress anneal the Nb and to remove hydrogen from the Nb
- 1400 °C high temperature heat treatment with titanium getter layer to increase the thermal conductivity (RRR=500)
- Cleanroom handling:
 - Chemical etching to remove damage layer and titanium getter layer
 - High pressure water rinsing as final treatment to avoid particle contamination

- **February 1992** - 1° TESLA Collaboration Board Meeting @ DESY
- **March 1993** - "A Proposal to Construct and Test Prototype Superconducting RF Structures for Linear Colliders"
- **1995** - 25 MV/m in multi-cell cavity
- **May 1996** - First beam at TTF
- **March 2001** - First SASE-FEL Saturation at TTF
- **March 2001** - TESLA Technical Design Report
- **February 2003** - TESLA X-FEL proposed as an European Facility, 50% funding from Germany
- **2004** - TTF II Commissioning
- **April 2004** - 35 MV/m with beam


Infrastructure @ DESY in Hall 3



TTF I



TTF II



LCWS 2004

Paris, 19 April 2004

Learning curve with BCP



BCP = Buffered Chemical Polishing


3 cavity productions from 4 European industries: Accel, Cerca, Dornier, Zanon

Cornell ●
1995




5-cell







EP (Electro-Polishing) developed at KEK by Kenji Saito (originally by Siemens)
 Coordinated R&D effort: DESY, KEK, CERN and Saclay



Cavity Vertical Test



- The naked cavity is immersed in a super-fluid He bath.
- High power coupler, He vessel and tuner are not installed
- RF test are performed in CW with a moderate power (< 300W)




Horizontal tests in "Chechia"

Chechia is a horizontal cryostat to test fully equipped cavities



- Cavity is fully assembled
- It includes all the ancillaries:
 - Power Coupler
 - Helium vessel
 - Tuner (...and piezo)
- RF Power is fed by a Klystron through the main coupler
- Pulsed RF operation using the same pulse shape foreseen for TESLA



- Long Term (> 1000 h) Horizontal Test
- In Chechia the cavity has all its ancillaries
- Chechia behaves as 1/8th (1/12th) of a TESLA cryomodule




- To compensate for Lorentz force detuning during the 1 ms RF pulse
Feed-Forward
- To counteract mechanical noise, "microphonics"
Feed-Back




Cavity detuning induced by Lorentz force during the tests performed in Chechia at **TESLA-800 specs**

- Piezo-compensation on: just feed-forward resonant compensation
- Piezo-compensation off



DESY EP Infrastructure fully operational


- outstanding results recently obtained
- 1400°C treatment not required



EP at the new DESY plan


800°C annealing

120°C Backing



Very low residual resistance

Negligible Field Emission



EP & 120°C backing are the key steps of the recipe

Field Emission and Q-drop cured

- Maximum field is still slowly improving
- Negligible Field Emission detected, that is
- Negligible dark current expected at this field level
- Cavity can be operated close to its quench limit
- Induced quenches are not affecting cavity performances

String Assembly



The assembly of a string of 8 cavities

- is a standard procedure
- is done by technicians from the TESLA Collaboration
- is well documented using the cavity database as well as an Engineering Data Management System
- was the basis for two industrial studies.

We are ready to transfer this well known and complete procedure to industry.



The inter-cavity connection is done in class 10 cleanrooms




Three generations of the cryomodule design, with **improving simplicity and performances**, while **decreasing costs**


Cryomodule Characteristics

Length	12 m
# cavities	8
# doublets	1
Static Losses	@ 2 K 1.5 W
	@ 5 K 8 W
	@ 50 K 70 W


Required plug power < **6 kW**




Sliding Fixtures @ 2 K



"Finger Welded" Shields



Reliable Alignment Strategy








The module assembly is a well defined and **standard procedure**.

- **experience of 10 modules** exists
- the latest generation (type III) will be used for series production (XFEL requires 120 modules)
- **several cryogenic cycles as well as long time operation were studied**
- the assembly problems occurred are well understood and cured



The TTF I Linac - 6 Year exp.







VUV FEL User Facility

- Linac Commissioning under way
- SASE FEL Commissioning by September this year




- 50% funded by the German Government - European consensus growing
- Great opportunity for TESLA
 - Machine reliability according to SRL standards
 - Industrial mass production of cavities (~ 1000) and modules (> 120)






cavity / quad string alignment is measured using a stretched wire system

at **warm** and at **cold** temperature



corresponds to a perfectly aligned cavity / quad string



TDR specifications (rms):

cavities x/y: +/- 0.5 mm
 z: +/- 1 mm
 quad/dip x/y: +/- 0.3 mm
 z: +/- 1 mm
 roll: +/- 0.1 mrad

Results (peak):


cavities x: +/- 0.35 mm
 y: +/- 0.25 mm
 quad/dip x: +0.1 / -0.4 mm
 y: +0.2 / -0.5 mm
 overall module tilt ≈ 0.1 mrad

- 20-Jun-03 300 K
- △ 22-Jul-03 2 K
- 06-Oct-03 300 K
- 31-Mar-04 2 K



RF results in module # 5

BCP Cavities


- 6 cavities exceed 30 MV/m (single cavity test)
- 1 cavity shows field emission at high field
- 1 cavity is quenching at 25 MV/m
- 5 Hz Test to demonstrate a 25 MV/m module with equal power feeding



- Industry is being producing 30 new cavities for extensive tests
- Cavity delivery will start end of May
- Cavities will follow the standard preparation procedure at DESY to further define protocols for industry. This includes:
 - 800 °C annealing, no 1400 °C firing is foreseen
 - ElectroPolishing (EP)
 - High Pressure Rinsing (HPR)
 - Clean Room handling and assembling
- Because of conflict with TTF II operation as VUV-FEL test Facility a Module test stand has been designed and will be in operation by 2005. **The 35 MV/m module test is expected by end 2005.**
- Meanwhile tests of fully equipped cavities will continue into the horizontal cryostat "Chechia".
- **The worst of the 35 MV/m cavities has been scarified for a test in module ACC 1**, which will be operated in the VUV-FEL Test Facility with an accelerating voltage below 20 MV/m (Injector issues)




- Very fast conditioning of cavity and coupler
- Full pulse length (800 μ s flat top) and 5 Hz repetition rate easily achieved
- Quenches easily detected and recovered
- With just feedforward for Lorentz force detuning compensation AC 72 was stably operated for several hours
- Feedback successfully tested




AC72 inside ACC1 Results

- No field degradation from Vertical, Horizontal, Module and Beam
- No radiation detected up to 35 MV/m. Negligible field emission and dark current




- One of the Electropolished cavities (AC72) was installed into the module ACC 1 for the VUV-FEL
- Cooldown of the LINAC finished on March 31st
- Cavity was individually tested in the accelerator with high power RF
- **Result:**
 - **35 MV/m** in the accelerator!
- Calibration has been confirmed with beam and spectrometer
- No field emission detected
- Preliminary good results with LLRF and Piezo-tuner
- No degradation, neither the cavity nor the coupler, as is expected for SRF cavities.




- TTF III Coupler has a robust and reliable design.
- Extensively power tested with significant margin
- New Coupler Test Stand at LAL, Orsay


frequency	1.3 GHz
operation	pulsed: 500 μ sec rise time, 800 μ sec flat top with beam
two windows, TiN coated	<ul style="list-style-type: none"> • safe operation • clean cavity assembly for high Eacc
2 K heat load	0.06 W
4 K heat load	0.5 W
70 K heat load	6 W
isolated inner conductor	bias voltage, suppressing multipacting
diagnostic	sufficient for safe operation and monitoring





10 + 30 New Couplers in construction by industry

1 klystron for 3 accelerating modules, 12 nine-cell cavities each





Operation with Final State Machine



Adaptive Feedforward

Microphonics

Contributions to Energy Fluctuations

1. Lorentz Force
2. Microphonics
3. Bunch-to-Bunch Charge Fluctuations
4. Calibration error of the vector-sum
5. Phase noise from master oscillator
6. Non-linearity of field detector
7. Klystron Saturation
8. RF curvature (finite bunch length)
9. Wakefield and HOMs




Figure 2: Fluctuation of the cavity resonance frequency at slow drifts over a period of one hour and by probability density of the cavity resonance frequency with an rms width of 2Hz.

Lorentz Force Detuning






Figure 3: Influence of radiation pressure on the resonance curve of a cavity. a) Static detuning during cw operation and b) dynamical detuning during nominal TESLA pulse.



Adaptive Feed Forward can handle nonlinear systems through linearisation around the operating point.


The calculation of a new feed forward table needs only a few seconds.




LLRF: Operation Example

Phase Adjustment Using Beam Transients

before adjustment



after adjustment






RF vectors during
800 μ s flat top

LLRF: Operation Example

Operation of a Module (# 1*) above its Quench limit

Cavity quench detection algorithms and exception handling procedures analyze the probe signals...




Stable Module #1* operation with slowly but steadily increased gradient

1st quench: **Cavity 2**
 $E_{acc} = 19 \text{ MV/m}$

2nd quench: **Cavity 6**
 $E_{acc} = 21 \text{ MV/m}$

3rd quench: **Cavity 1**
 $E_{acc} = 24 \text{ MV/m}$

Three **Thales** TH1801 Multi Beam Klystrons produced and tested



Indipendent beam design proposed and built by **CPI**. Tests just started.



Achieved efficiency	65%
RF pulse width	1.5 ms
Repetition rate	5 Hz
Operation experience	> 5000 h
10% of operation time at full spec's	

A new design proposed by **Toshiba** looks robust and should reach 75% efficiency



First prototype tests are starting - Cathode loading < 2.1 A/cm²

FNAL Modulator at TTF



- 10 Modulators have been built, 3 by FNAL and 7 by industry
- 7 modulators are in operation
- 10 years operation experience

- Work towards a more cost efficient and effective design started
- Hazardous components minimized
- Most components are standard
- Industry is ready to built turn key modulators fulfilling the specs



All standard components - Technology well established - Produced by Industry

3 Stub Tuner (IHEP, Beijing, China)



E and H Bends (Spinner)



Circulator (Ferrite)




Hybrid Coupler (RFT, Spinner)




RF Load (Ferrite)



RF Load (Ferrite)





- Production of TESLA Cavities with accelerating field exceeding **35 MV/m has been proven.**
- All the previous limiting factors, including **Q-drop and dark current** have been **understood and cured**,
- TESLA Technology is widely distributed and on hands
- **Industry has already most of the required know-how** and technology transfer is under way.
- **The costing process for the TESLA TDR has been based on industrial studies** for mass production. All the fabrication steps have been analyzed and reviewed by industry.
- **16 major Industries participated** with representatives and posters to the ITRP visit to DESY on April 5th.
- **Detailed Engineering** of major components for a further reduction of costs and improvement of component MTBF **has started**. On this subject **5 M€ have been allocated by EU on the framework of ESGARD/CARE**


ESGARD

European
Steering
Group on
Accelerator
R&D

(...) the directors of CCLRC, CERN, DAPNIA/CEA, DESY, LNF, Orsay/IN2P3, and PSI in consultation with ECFA have decided to form a **European Steering Group on Accelerator RD (ESGARD)**, coordinated by Roy Aleksan with the administrative support of the CEA



ECFA has given CARE a very high priority



- The program was considered essential to:
 - particle physics, synchrotron light sources, high intensity protons and ion beam facilities and operation of accelerators
- Network activities approved on:
 - Electron linacs, neutrino beams and proton machines
- 4 Joint Research Activities approved on:
 - **Superconducting RF cavities, controls and ancillaries**
 - Photo Injectors for high charge and high brightness electrons
 - High Intensity Proton Pulsed Injectors
 - Next European Dipoles



Projects and TESLA Technology

A Few Examples

US Labs in the TESLA Collaboration

SRF Unit to DESY, 17th April 2004

Argonne-Atlas on linac, RIA	Comell-CESR, ERL
Fermilab	Jefferson Lab-CEBAF, FEL
MIT-Bates	UCLA

US Labs that have SRF activities synergistic with TESLA

SRF Unit to DESY, 17th April 2004

Brookhaven	Los Alamos
Lawrence Berkeley-LUX	Michigan State-RIA
Oakridge-SNS	Stanford-HEPL

Upcoming CW Applications with TESLA Technology - USA

SRF Unit to DESY, 17th April 2004

- LEPP** (Linac Coherent Light Source)
- BROOKHAVEN** (Free Electron Laser)
- LUX** (Linac Coherent Light Source)
- MIT X-ray Laser R&D Program**

Upcoming CW Applications With TESLA Technology - Europe and Japan

SRF Unit to DESY, 17th April 2004

- Forschungszentrum Rossendorf** (Free Electron Laser)
- BESSY in Berlin** (Free Electron Laser)
- 4GLS Daresbury** (Free Electron Laser)
- KEK** (Free Electron Laser)

Superconductivity at Daresbury

SRF Unit to DESY, 17th April 2004

2010

2004

4GLS DARESBUY

AS7ec

Superconducting RF Systems in The Proposed LUX Ultraviolet X-Ray Facility

SRF Unit to DESY, 17th April 2004

LUX Machine Parameters

Beam Energy	10-200 MeV
Beam Current	100-1000 nA
Beam Spot Size	10-100 micrometers
Beam Lifetime	10-100 hours
Beam Quality	10^-4 emittance
Beam Stability	10^-4 relative
Beam Position	10^-4 mm
Beam Size	10^-4 mm
Beam Energy Spread	10^-4
Beam Energy Spread	10^-4
Beam Energy Spread	10^-4

CEBAF Operational Experience: 2000+ Cavity-Years cw at 2 K

SRF Unit to DESY, 17th April 2004

SC Damped Cavity in KEKB

SRF Unit to DESY, 17th April 2004

KEKB achieved the luminosity of 10³¹ cm⁻²s⁻¹

RF system for an ampere-class beam

SC operation under the beam of 1 A

- Most of the new accelerator based projects, in construction or just proposed, are widely using Superconducting RF technology.
- The worldwide coordinated effort behind the TESLA project to demonstrate the feasibility of a TeV linear collider based on SRF has been the driving force in the past ten years to reach a new level of understanding of the past limiting factors.
- The concrete possibility of building a 30 Km linear collider convinced industry to invest for higher quality niobium material and for a complete understanding of the fabrication process at an industrial large scale.
- At present the SRF technology is considered in hand and industry is producing turn-key reliable systems that include SRF cavities and cryo-ancillaries.

- A number of SRF infrastructures, sustained by expert people, are distributed worldwide. Their outcomes are still dominated by the past experience and their control on all the critical process parameters is not fully satisfactory. **A large global SRF based project would update this distributed expertise, opening the way for further applications.**
- Once all the design and fabrication steps are fully under control, for cavities, ancillaries and cryomodules, **an SRF system is a cheap and reliable transformer that, with more than 50% efficiency at relativistic energies, can convert plug to beam power.** And it can do so with high duty factor, representing a near-DC current source.
- That means that **many applications beyond fundamental science can be conceived**, ranging from **nuclear waste transmutations** to the industrial production of **photon beams for electronics, food or chemistry.**

- **TESLA Technology** has been developed and **is now ready** to be chosen as the basic technology **for the Global Linear Collider**.
- **Industry is ready** to produce all the major components at a well **defined cost** and with a well **defined reliability**.
- Should the Technology recommendation being for Cold, **margins** have been already recognized both
 - to **improve performances** (as new cavity shape for > 40 MV/m)
 - to **reduce cost**
- **The European X-FEL to be built at DESY** will represent the first large scale application among the many proposed that are based on the TESLA Technology. Its realization **will be naturally synergic** with the Linear Collider **if the Technology choice will be for cold**.
- **The future of TESLA Technology is sure** and somehow LC independent, but it would be **faster** and **cheaper** if a cold Linear Collider is going to be built.