



MTF – Manufacturing and Test Folder

## **Large Scale Deployment of MTF**

Sonia Mallón Américo   Elena Manola-Poggioli  
on behalf of the EDMS Team, TS-CSE

---

- Manufacturing follow-up with MTF
- MTF in the installation phase
- Scaling-up of the service

- MTF is the tool for manufacturing and installation follow-up within the LHC project:
  - It contains today the descriptions of more than 120.000 equipment: mainly magnet, QRL and interconnection components
  - It allows traceability of components and follow-up of non-conformities
  - It allows an integrated information flow:
    - status of tests, manufacturing and assembly operations
    - access to the related documents
  - Contains links to external databases: LHC reference database, cables, magnetic measurements etc
- It is an integral part of CERN's Engineering and Equipment Management System (EDMS)
- MTF is based on a commercial product – MP5 of DataStream – and is using Oracle+Web technology

# MTF – Manufacturing and Test Folder




MTF

## EDMS Web


## MTF- Travellers



# EDMS Common Layer



A dipole in MTF



The screenshot displays the MTF Equipment Management Folder interface. The main content area shows the 'Top Assembly Folder: Properties' for the assembly 'HCLBARA000-IN001013'. The properties are as follows:

- Top Assembly Identifier:** HCLBARA000-IN001013
- Other Identifier:** None
- Description:** Arc Dipole LBARA

The interface includes a navigation bar with 'Home', 'Help', and 'EDMS site' links, and a search bar. The 'Equipment data' tab is active, showing a table of property values:

Property	Nominal Value	Unit
Assigned LHC Slot	LBARA.13R7	

The 'Assigned LHC Slot' value 'LBARA.13R7' is circled in red. Below the table, there are sections for 'External Links' (No external data link exists) and 'Extremities setup' (Line M1 ref., Line M2 ref., Line M3 ref., Line X ref., Line C' ref., w bellow ref.). The 'Types A,C,D,E' are listed at the bottom.

The left sidebar shows a tree view of the equipment structure, including 'Arc Dipole LBARA', 'Cryo Dipole LBAR', 'Cold Mass MBAR', 'Collared Coil', 'Collars A Type 1', 'Collars A Type 2', 'Collars B Type 1', 'Collars B Type 2', 'Collars C Type 1', 'Collars C Type 2', 'Aperture (A1)', 'Aperture (A2)', 'MCS Magnet Assembly (A1)', 'MCS Magnet Assembly (A2)', 'MCDO Magnet Assembly (A1)', 'MCDO Magnet Assembly (A2)', 'Yoke assembly, type A', 'Helium Shell Assembly Type A', 'Dipole Diode Stack, Polarity type', 'Cryostat Assembly', 'Assembled beam screen - R', 'Long Nested bellows (M1)', and 'Long Nested bellows'.

## Assigned LHC slots for Cryo Dipoles








Equipment Id	Slot Id
HCLBARA000-IN001013	LBARA.13R7
HCLBARA000-IN001014	LBARA.12R7
HCLBARA000-IN003006	LBARA.18R7
HCLBARA000-IN003007	LBARA.22R7
HCLBARA000-IN003054	LBARA.20R7
HCLBARA000-IN003055	LBARA.17R7
HCLBARB000-IN003043	LBARB.20R7
HCLBBRA000-IN001008	LBBRA.16R7
HCLBBRA000-IN001009	LBBRA.15R7
HCLBBRA000-IN001021	LBBRA.18R7
HCLBBRA000-IN002008	LBBRA.17R7
HCLBBRA000-IN003041	LBBRA.13R7
HCLBBRB000-IN001031	LBBRB.8R7
HCLBBRC000-IN001035	LBBRC.17R7
HCLBBRC000-IN002009	LBBRC.19R7
HCLBBRC000-IN003011	LBBRC.13R7
HCLBBRD000-IN003034	LBBRD.12L8

17 reserved slots found.

- Procedure for reporting of non-conformities and follow-up of corrective actions: LHC-PM-QA-0611.

Magnet Id	NCR	Equipment	Workflow Step
<a href="#">HMBALA001-01000090</a>	▶ 462362 (ver.1) QN-1090-CDW1-1	<a href="#">HCLBAL_000-IN001090</a> Cryo Dipole LBAL	CDW1 Warm Electrical Tests
<a href="#">HMBALA001-01000090</a>	▶ 461610 (ver.1) LHC-MB-QN-IN-01090-WP02-CRY-01	<a href="#">HCQBAGA101-IN001090</a> Cryostat Assembly	WP02 Cryostat Assembly and relevant tests
<a href="#">HMBALA001-01000090</a>	▶ 434327 (ver.1) NCR_04LHCA120	<a href="#">HCMBA_A101-01000090</a> Yoke assembly, type A	
<a href="#">HMBALA001-01000090</a>	▶ 374312 (ver.1) NCR_009-03 Flange item 10 (h11). From n° 1 to 52	<a href="#">HCQBAVV101-FC000057</a> Vacuum Vessel	Dimensional Check
<a href="#">HMBALA001-01000090</a>	▶ 408184 (ver.1) Charpy test at 0°C for HCQBAVV101-FC000001 to FC000238	<a href="#">HCQBAVV101-FC000057</a> Vacuum Vessel	Dimensional Check
<a href="#">HMBALA001-01000090</a>	▶ 408187 (ver.1) Dimension out of tolerances at points 75 and 4 of the Dimensional Control for HCQBAVV101-FC000057	<a href="#">HCQBAVV101-FC000057</a> Vacuum Vessel	Dimensional Check
<a href="#">HMBALA001-01000090</a>	▶ 374310 (ver.1) NCR_007-03 with FCM O-rings	<a href="#">HCQBAVV101-FC000057</a> Vacuum Vessel	Vacuum Leak Check

- **Example: Comments on corrective actions.**

	Jean-Philippe <b>TOCK</b> on 2004-02-17, 08:40 said: OK after line N is put in conformity	Accept 
	Jos <b>VLOGAERT</b> on 2004-02-17, 09:10 said: ok	Seen 
	Marta <b>BAJKO</b> on 2004-02-17, 09:29 said: Regarding the tolerances of the shape: the actual tolerance is not anymore applied in the industry on the radial deviation but separately in the vertical and horizontal plane. Vertically is +/-0.85mm and +/-1.5mm horizontally. At WP08 ( in MTF) the vertical shape has its max. error of 0.74mm for the 0.75mm tolerance and the horizontal less than 1mm. Regardin the N line: on WP01( MTF) the dimension of 310mm was within the tolerance of +/-2mm and after WP08 the end cover moved max. 0.3mm horizontally on the Lyra side and only on the Lyra side, which is not explaining the dimension of 315mm.	Accept 
	Patrick <b>LEPEULE</b> on 2004-02-17, 12:03 said: OK for vac components integration. Comment/proposal: would it be possible to bring back the 2 "out of tolerance" points within the race track tolerance with a dedicated alignment from extremities?	Seen 
	Dominique <b>MISSIAEN</b> on 2004-02-23, 10:01 said: I don't agree with the comment of Marta telling us that the tolerance of hor. and vert are completely decoupled. This is not what was decided in the WGA. We will continue opening NC when the r_body values will exceed 0.75 mm as decided by WGA. This value is also useb by MEB	Seen 



Equipment Id	Step Description	Result	Completion Date	Test Report	NCRs
<a href="#">HCLBAR_000-CR001013</a>	Transportation SMA18-Preveessin	Ok	2003-09-02	▶ 404465 (ver.1)	
<a href="#">HCLBBR_000-CR001006</a>	Transportation SMA18-Preveessin	Not Ok	2003-09-08		▶ 402691 (ver.1) LHC-MB-QN-CR-01006-TRANS-01 Closed
<a href="#">HCLBBR_000-IN001035</a>	Transportation SMA18-Preveessin	Ok	2003-09-09	▶ 404425 (ver.1)	
<a href="#">HCLBBR_000-IN002008</a>	Transportation SMA18-Preveessin	Ok	2003-09-17	▶ 404469 (ver.1)	
<a href="#">HCLBBR_000-IN002009</a>	Transportation SMA18-Preveessin	Ok	2003-09-24		
<a href="#">HCLBBR_000-CR001023</a>	Transportation SMA18-Preveessin	Ok	2003-09-29	▶ 406845 (ver.1)	
<a href="#">HCLBBR_000-CR001004</a>	Transportation SMA18-Preveessin	Ok	2003-10-13	▶ 408589 (ver.1)	
<a href="#">HCLBBR_000-CR001024</a>	Transportation SMA18-Preveessin	Ok	2003-10-14	▶ 408610 (ver.1)	

Dear Sirs,

Please be informed that preparation for storage operations of the cryodipole [HCLBAR\_000-IN003028] is completed.

This is an automatic notification sent by the MTF System upon closing of the step Preparation for Storage by Olivier Housiaux

For any question, please contact [Mailto:cryodip@cern.ch](mailto:Mailto:cryodip@cern.ch)

Best regards,  
EDMS Team

- Closing of a step can trigger e-mail notifications
- Under study – automatic generation of EDH transport requests


- First application for installation follow-up: Tracking of non-conformities related to general services (LHC-PM-QA-0612).

Location	NCR document	Doc title	Doc keywords	NCR status	Document description
<a href="#">RI12</a>	464329 (ver. 1)	INC Fibre optique RI12	critical	Initiated	Terminer tubes fibres optiques aux positions 25780 et 25781
<a href="#">RE12</a>	464326 (ver. 1)	INC Fibre Optique RE12	critical	Initiated	Reprendre la dérivation du tube diamètre 40 pour les fibres
<a href="#">RE12</a>	464328 (ver. 1)	INC Telephone rouge RE12	critical	Initiated	Déplacer le téléphone rouge vers l'extérieur de l'alvéole
<a href="#">RI12</a>	450984 (ver. 1)	INC Tuyauterie RI12	critical	Initiated	Vérifier les supports de la Warm Recovery Line avec gabarit
<a href="#">RI12</a>	450985 (ver. 1)	INC Electricité	use as is	Initiated	Echelle DS prévue initialement sous tuyauterie eau déminéralisée
<a href="#">RI12</a>	450998 (ver. 1)	INC Tuyauterie RI12	critical	Initiated	Manque isolation sur Warm Recovery Line (pas de caniveau)
<a href="#">RI12</a>	450999 (ver. 1)	INC Tuyauterie	use as is	Initiated	Tuyauterie incendie sort du sol. Non présent dans modèle
<a href="#">RI12</a>	451000 (ver. 1)	INC Electricité	use as is	Initiated	Echelle à cables plus étroite que dans le modèle 3D. Support
<a href="#">RI12</a>	451001 (ver. 1)	INC Electricité	use as is	Initiated	Pendants d'échelle à cables non conforme au modèle 3D
<a href="#">UJ12</a>	451002 (ver. 1)	INC Cable rayonnant UJ12	critical	Initiated	Manque un cable rayonnant : de coffret de dérivation à l'échelle
<a href="#">UJ12</a>	451003 (ver. 1)	INC Tuyauterie UJ12	critical	Initiated	Manque isolation sur Warm Recovery Line (pas de caniveau)
<a href="#">UJ12</a>	451004 (ver. 1)	INC Tuyauterie	use as is	Initiated	Dans modèle 3D, manque supports tuyauteries en tête de dérivation
<a href="#">UJ12</a>	451005 (ver. 1)	INC Tuyauterie	use as is	Initiated	Des équipements LEP ont été démontés. Ils apparaissent dans le modèle 3D
<a href="#">UJ12</a>	451006 (ver. 1)	INC Electricité	use as is	Initiated	3 coffrets sous échelle à cables (entre échelle et charpente)
<a href="#">UJ12</a>	451007 (ver. 1)	INC Electricité	use as is	Initiated	Echelle à cables en tête de voute non conforme au modèle 3D

# MTF – Manufacturing and Test Folder

## QRL Installation follow-up

- Service module installed in the slot QRLAB.15R7



The screenshot displays the EDMS software interface. On the left, a 3D assembly tree is visible, with an orange arrow pointing from a specific component to the main info panel. The main info panel is titled "Top Assembly Folder : Main Info" and contains the following information:

- Top Assembly Identifier:** HCQRLAB000-SI000004
- Other Identifier:** None
- Description:** Service module type QRLAB

Below this information, there are tabs for "Main", "Made of", "Equipment data", "Workflow", and "Documents". The "Main" tab is active, showing a "View summary" button and a table of physical properties:


Physical	
Manufacturer	Simic Spa
Project Engineer	
Status	Accepted
Other Identifier	
Parent Slot	<u>QRLAB.15R7</u>
Location	<u>R78</u>

On the right side of the main info panel, there is an "Assembly Tree" section. It lists the "Service module type QRLAB" and its sub-components:

- Cryo Thermometer (TT947)
- Cryo Thermometer (TT948)
- Cryo Thermometer (TT943)
- Cryo Thermometer (TT944)
- Cryo Thermometer (TT911)

- Collection of the data in the tunnel will be done by using the MTF data transfer file:
  - Reporting on completed step
  - Attaching measurement files
  - Referencing used components (already registered in MTF)
- Uploading of data in the MTF database after each working day:
  - Compressing of the MTF transfer file and all related documents
  - Submitting the data to the MTF Import Queue – data will be imported during the night

## Scaling-up of the service



- Information campaigns and user training
- Promotion of the direct use of MTF Web by suppliers
- New data import mechanism (MICADO – MTF Import Chain to Avoid Data Overdose)

- **MTF Workshop:**
  - Definition of minimum data required in MTF
  - Procedures to ensure data quality
- **Training:**
  - 22 half-day sessions, 204 persons trained
  - Good collaboration with CERN Technical Training Service
- **Collection of data as close as possible to where it is generated**
- **LHCQA WG 2004:**
  - Reinforcement of the role of LHC quality representatives
  - Review of the QAP implementation group by group

- The large scale deployment of MTF is both an organizational and technical challenge.
- It requires QA coordination and close collaboration between different equipment groups.
- Acquired experience provides a solid basis for new developments of additional system functionality and the formalization of QA procedures.