



Technical Support 2004 Workshop

# Managing the Detector Fixed Gas Distribution Contracts

David McFarlane (TS-LEA-DES)

David McFarlane



# Contents

- Why do we need a fixed gas system?
- What gases do we use?
- Where are these systems located?
- Gas systems in an experimental hall
- Gas system in the LHC
- Contracts in place
- What is involved in the M & O?
- History of the Contracts
- Key points to manage
- Problems and difficulties
- Concluding points




# Why do we need a fixed gas system?

- Specific gaseous atmospheres are required by the detectors in order to carry out physics experiments.
- Due to safety reasons this gas can not be stored close to the detector.
- An infrastructure of pipes and control panels are required to supply these gases to the proximity of the detector.

# CERN EXPERIMENTAL AREAS

TS-LEA-DES  
Gas distribution from  
dewars and cylinders  
up to the control  
panels



**Operation**  
PS (East, South, AD)  
SPS (North & West)

**Preparation**  
LHC (P1, P2, P5, P8)

Services

**EP/TA1-GS**

**INTERFACE**  
Contact Persons EAC \* & GLIMOS  
GLIMOS EP Division

**RESPONSIBILITY**

\* EAC Experimental Area Coordinator  
Revised : 23 May 1998  
D.Lacarrère 20 February 1998

SYNOPSIS 2 : Visualisation of the Gas Distribution & Supply (GDS) SERVICE Responsibilities



# What gases do we use?

## ➤ Neutral Gases

- $\text{N}_2$ ,  $\text{CO}_2$ , Ar,  $\text{CF}_4$ ,  $\text{C}_2\text{H}_2\text{F}_4$ ,  $\text{SF}_6$ , He, Xe, Ne

## ➤ Flammable Gases

- Ar/ $\text{H}_2$ , i- $\text{C}_4\text{H}_{10}$ ,  $\text{CH}_4$




# Where are these systems located?

- **LHC**
  - **SPS Area**
    - Point 1 (ATLAS)
    - Point 2 (ALICE)
    - Point 5 (CMS)
    - Point 8 (LHCb)
  - **SPS Area**
    - EHN1 (907 / 909)
    - ENH2 (908)
    - ECN3 (920)
    - West Hall (297 / 182)
  - **PS Area**
    - AD Hall (193)
    - East Hall (157)
    - South Hall (150)
- **Equipment in operation**
  - 70 Km of stainless steel pipes (6mm to 118mm)
  - 20 km of copper pipes (6mm to 28mm)
  - 50 Neutral gas control panels
  - 60 Flammable gas control panels
  - 21 Dewars (320 litres to 11m<sup>3</sup>)
  - 81 Patch panels





# Gas systems in an experimental hall





# Gas system in the LHC

LHCb FACILITIES AT POINT 8







# Contracts in place

## ➤ **F-447**

- The design, supply, installation and commissioning of distribution systems for clean gases that are required for the operation of particle detectors at Points 1 & 5 of the LHC.

## ➤ **E-070**

- The technical support required for Maintenance and Operation (M & O) of the Gas Distribution Systems (G.D.S.) for particle detectors in all the existing and future experimental areas of CERN. This includes the modifications required to the existing systems at Points 2 & 8 of the LHC.



# What is involved in the M & O?

## ➤ **Maintenance and Operation**

- Daily inspection of the Gas Distribution Networks at CERN
- Ordering of gases
- Replacing gas cylinders or batteries of cylinders
- Supervising filling of cryogenic storage tanks (Dewars)
- Checking working pressures of the different Gas Distribution Networks
- Replacing failed or damaged gas handling equipment and instrumentation
- Minor pipe modifications
- Responding to and correcting reported faults of the Gas Distribution System
- Logging of “Maintenance and Operation” events and activities

## ➤ **Safety Aspects**

- Removing, calibrating and re-installing safety valves
- Checking tightness of gas regulation units
- Checking safety devices of cryogenic storage tanks
- Purging all flammable Gas Distribution Networks
- Reception tests and safety inspections



# History of the Contracts

- **F-447**
  - Signed October 2001 (Value = 3.6 MChf)
  - Point 1 completed September 2004
  - Point 5 completed December 2005
- **E-070**
  - Signed Sept 2002 (Value = 2.7 MChf)
  - M & O ongoing on a daily basis
  - Point 2 completed December 2005
  - Point 8 completed Spring 2006



# Key points to manage

- Schedule conflicts
- Cleaning of pipes / analysis
- Payment schedule
- Fire permits
- A.O.C.
- I.C.
- P.P.S.P.S
- Permits for working in Switzerland
- Regular planning meetings



# Concluding points

- The installation work for all 4 points of the LHC are on schedule and within budget.
- As each area is upgraded, remote monitoring systems are being installed to improve the service we currently offer to the experiments
- DES communicates closely with the experiments and the Gas Coordination Panel to make sure every needs of the experiments are being met.