

CONTROLS FOR LHC CRYOGENICS



AT-ACR and AT-ECR

Outline

- ✦ Experiments cryogenic system overview
- ✦ Overview of the LHC machine cryogenic system
- ✦ The LHC cryogenic system status
- ✦ Requirements and expected AB/CO support:
 - ✦ 1st phase: hardware installation and software production
 - ✦ 2nd phase: commissioning
 - ✦ Commissioning of individual sub-systems
 - ✦ Global system commissioning, upgrades and consolidations
 - ✦ 3rd phase: operation and system upgrade / improvement
- ✦ Experiments cryogenics special needs
- ✦ What should be improved or does not work as expected

AT-ECR control equipments

AT/ECR equipment overview

ATLAS

- * Helium external cryogenics (2 cryoplants, 2 OWS) - **Operation**
- * Helium proximity cryogenics (barrel toroids, end-cap toroids and central solenoid, 2 OWS) - **Commissioning**
- * Argon external cryogenics (1 cryoplant, 1 OWS)
- * Argon proximity/internal cryogenics (barrel, end-cap A and end-cap C calorimeters, 2 OWS) - **Commissioning**

CMS



- * Helium external cryogenics (1 cryoplant, 1 OWS)
- * Helium proximity cryogenics (1 OWS) - **Commissioning**

NA48

- * Krypton calorimeter - **to be transferred to UNICOS end 06**


J. Bremer and M. Pezzetti


Cryogenic system layout 1/2



- ✦ 5 cryogenic islands
- ✦ 5 local and 1 central control room
- ✦ 8 refrigerators
 - ✦ 2 at P4, 6 and 8,
 - ✦ 1 at P2
 - ✦ 1 at P1.8
- ✦ 1 refrigerator serves 1 sector (18 kW @ 4.5 K, 600 kW precooler)
- ✦ possibility to couple two refrigerators via the interconnection box → 2 refrigerators for 1 sector

Cryogenic system layout 2/2





Legend

 	QSC_(A,B,C): Warm Compressor Station	Electrical Feed Box
	QSR_(A,B): Surface 4.5 K Refrigerator Cold Box	Superconducting Link
	QURA: Underground 4.5 K Refrigerator Cold Box	
	QURC: 1.8 K Refrigeration Unit Cold Box	
QUI_(A,B,C): Cryogenic Interconnection Box		

Commissioned & accepted	Delivered / Under installation	Ordered (Contract placed)
Under commissioning	Under fabrication	Under definition

1st phase HW and SW production

- ✦ First time (new controls):
 - ✦ All tunnel cryogenic system (ACR/IN with AB/CO support) - 2006-07
 - ✦ QRL sect. 8-1 - 4th quarter 2005
 - ✦ LSS8L - 4th quarter 2005
 - ✦ QRL and magnet systems 4-5 & 3-4 - 1st semester 2006
 - ✦ QRL and magnet systems all - 2nd semester 2006
 - ✦ SM 18 cryo infra and 6 kW Linde ABB -> UNICOS - 1st semester 07
 - ✦ Ex-LEP refrigerator upgrade to UNICOS (Pt. 4 and 6) - early 06
 - ✦ Precoolers and upgrade (all pts) - 4th quarter 05 - 1st semester 06
 - ✦ QURC Pt. 1.8, 2, 6 - end 05 - 1st quarter 06
- ✦ Already performed in other LHC points (duplication):
 - ✦ QUI Pt.1.8 but need upgrade for all points- 1st semester 06
 - ✦ Pt. 1.8 18 kW refr. ABB -> UNICOS - SD 06-07
 - ✦ Dryers pt 2, 4, 6, 8 - end 2005 - beginning 06
- ✦ SW production verification and debugging prior to cold commissioning !
- ✦ Participation to the CFAWG to define the cryogenic system functional analysis and write the engineering specifications for the controls of the overall system


2nd phase commissioning

- ✦ Commissioning of individual sub-systems
 - ✦ Tunnel cryogenics, ex-LEP refrigerators, QUI, QURC's, dryers, pre-coolers, SM18 infra and refr.
 - ✦ All on critical path for hardware commissioning
 - ✦ Requires presence of AB-CO software specialist at start-up (no on-call support) to shorten, optimize and make safe and reliable tests (first few days are sufficient)
 - ✦ SW verification prior to cooldown to minimize on-line modifications during runs
 - ✦ Maintain and ensure SW modification consistency and up-to-date version
- ✦ Global system commissioning, upgrades and consolidations
 - ✦ Require presence of AB-CO software specialist at start-up
 - ✦ Software verification prior to cooldown
 - ✦ QA and logging of SW modifications
 - ✦ Participation of AB-CO to the commissioning activities to optimize collective behavior of sub-systems and optimize general process during the tests at least during first sectors and systems testing
 - ✦ Cryogenics and HC will work on 2x8 shift; any stop will delay the HC and disrupt the work of up to 10 persons / day -> it requires fast troubleshooting -> on-call service 24h/24h
- ✦ Participate to Monday morning ACR commissioning meeting in order to review commissioning activities and set priorities
- ✦ Participation to the CFAWG to revise and improve the controls of the overall system

3rd operation and consolidation

- 24 h/ 24h on-call support for installation in operation (ABB installations prior to transfer to UNICOS ?)
- Ensure control system improvements and modifications are correctly tracked and updated in default SW version
- Support for GTPM applications necessary for fast re-start after major stop
- Support for supervision screens and fixed displays production, maintenance and upgrade
- Availability of AB-CO specialist for controls improvement and upgrade during the first years of operation

Recovery time to nominal operation after a failure



➤ Controls :

? Complete new control system

? Ethernet dependent (control loops, PLC communication)

➤ Required performances, reliability and robustness of the control system is not "yet" up to requirements

The cryogenic recovery acts as a **time amplifier**

- utility stop: rec. time=6 hours + 3 x "utility stop length"

- bad insulation vacuum or leaking QRV: rec. time = 15 x "utility stop length"

AT-ECR control equipments

Special needs for AT/ECR cryogenic installations:

- PLC and Data Server shall be running (almost) non-stop for argon calorimeters
- Only short « Shut Down » period for ATLAS and CMS magnets

Consequence for control system:

- 2nd line control support (ECR/CE 1st line support)
 - Network performance
 - Centralized data server (including support)
- 365 j/365 j
(24h/24h)
Starting Dec 05

J. Bremer and M. Pezzetti

What should be improved or does not work as expected (and NEED to be solved before HC!)

✦ Resources:

- ✦ No sufficient support from AB-CO to cover the commissioning of more than 1 - 2 subsystems at the time
 - ✦ -> 4 sectors in parallel -> ?
- ✦ No on-call support during non-working hours for urgent troubleshooting of controls
- ✦ Mainly "call centre" type technical support (we need AB-CO support in the control room during machines start-up) to improve efficiency, share of responsibility and achievements, better understanding of problems, team work !

What should be improved or does not work as expected (and NEED to be solved before HC!)

➤ Hardware/Software:

- Ethernet and communication problems (loss of time, data, configuration) -how safe and reliable ?
- Quality control on software and modifications
 - Update of version without loss of configuration and parameters, ...
 - Checks before hand-over for commissioning
- Slow response and "load" of the control system
- Continuous evolution of HW/SW versions
 - The change is not transparent as it should be
- User interfaces
 - Trends: still progress needs to be made
 - Data logging: data extraction without formatting and ready to analyse
 - Data logging: continuous change of naming in DB makes difficult the creation of automatic routines for data collection and analysis
 - Diagnostics info: not always available or difficult to implement
 - PVSSIII: on-line modification not possible