

HERA Operation and Prospects



HERA-LHC Workshop Final Meeting

March 22-24 2005

F. Willeke, DESY

- *HERA overview*
- *HERA I summary*
- *HERA luminosity Upgrade and 2004 proton -e⁺*
- *HERA improvement program*
- *present performance*
- *Outlook and conclusions*


Lepton-Proton Collider with 320 GeV center of mass Energy

HERA Double Ring Collider


820 GeV Protons (actual 920 GeV)

30 GeV Leptons e^+ or e^- (actual 27.5 GeV)


Spatial resolution 10^{-18}m



Björn Wiik (1937-1999)



HERA Footprint



Milestones

1981 Proposal

1984 Start Construction

1991 Commissioning, first Collisions

1 Start Operations for H1 and ZEUS,

1st Exciting Results with low Luminosity

1994 Install East spin Rotators → longitudinal polarized leptons for HERMES

1996 Install 4th Interaction region for HERA-B

1998 Install NEG pumps against dust problem, Reliability Upgrade

2000 High efficient Luminosity production: $100\text{pb}^{-1}\text{y}^{-1}$

HERA I: $180\text{pb}^{-1} e^+p$ → Precision Measurement on proton structure

HERA I




The building, commissioning and efficient operation of the complex HERA accelerator represented a major challenge for DESY, which required a large and continuous effort


This effort allowed eventually to exceed the planned peak performance with a peak luminosity

$$L_{\text{peak}} = 2 \cdot 10^{31} \text{ cm}^{-2} \text{ s}^{-1}$$

and a Production of 67pb^{-1} in the 200 days of running in 2000.


For more luminosity, a upgrade was performed in 2000-2001 for an increase of a factor of three in peak performance






Superconducting Magnets GO/GG


Designed + built in collaboration with BNL



- cryostat-wall
- He-vessel
- coil
- Beam pipe
- support tube
- insulating vacuum,
- He-supply




90mm




serpentine_movie.mov

Superconducting Magnets in the Detectors



Courtesy ZEUS Collaboration



HERA II Luminosity Parameters

$$L = \frac{N_p \cdot I_e}{4 \hat{I} \epsilon \cdot \hat{I}_N \cdot \sqrt{\hat{I}_{xp}^2 \hat{I}_{yp}^2}}$$

UPGRADE

Beam Energies

$$E_e = 920\text{GeV} / 27.5\text{GeV}$$

Proton Beam current

$$I_p = 100\text{mA}$$

leptons current

$$I_e = 50\text{mA}$$

number of protons per bunch

$$N_p = 1 \times 10^{11}$$

normalized emittance

$$\epsilon_N = 20 \mu\text{m} \quad \text{Proton}$$

beta functions

$$\beta_{y,x}^* = 18\text{cm}$$

2.45m lepton emittance

$$\epsilon_e = 20\text{nm}$$

number of coll. bunches

$$n_b = 174$$

lepton vert. b.-b. tune shift par.

$$\Delta\nu_{y,x e} = 0.045, 0.025$$


hor./vert. beam size at IP

$$\sigma_{x,y,p,e} = 114\mu\text{m} / 30\mu\text{m}$$

luminosity



$$L = 5 \times 10^{31} \text{cm}^{-2} \text{sec}^{-1}$$

Recommissioning: High Luminosity Demonstrated




Record Luminosity
 120 Bunches
 $I_p < 70 \text{ mA}$
 $I_e < 35 \text{ mA}$

$L_{\text{peak}} > 2.7 \times 10^{31} \text{ cm}^{-2}\text{s}^{-1}$



Conclusion: HERA is able to deliver luminosity as advertised

HERA Longitudinal Polarization



Polarization in collisions: 30-40%
Polarization without collisions up to 50%

Further improvement plans:


Dedicated 2 Polarization Studies

Beam Based alignment
(suffers from lack of resources)

Need better polarization measurement for fast tuning!!

Regular Rotator Flip

Polarization after p-
Beam Loss on Feb. 12,





Backgrounds after Luminosity upgrade:


This looked very serious in the beginning and required time to gain understanding and implement counter measures

- Direct Synchrotron Radiation: solved by IR design, SR collimation and sophisticated beam steering procedures
- Indirect (backscattered) synchrotron radiation required improved masking in ZEUS
- e^+ particle backgrounds improved with improving vacuum (beam conditioning) and the addition of a pump in a critical location
- proton backgrounds improved with regular beam operation and we are at the point, were this is no issues for ZEUS anymore and almost no issue for H1 anymore

Improvement of synchrotron radiation mask system





before




after

Improvement of synchrotron radiation mask system



before



after

2004 Running Overview

Promising luminosity production in the 2003/2004 Positron Proton run




- Peak luminosity L_{peak} up to $3.8 \cdot 10^{31} \text{ cm}^{-2}\text{s}^{-1}$
- Production rate of up to $0.8 \text{ pb}^{-1} \text{ d}^{-1}$
- Shortcoming of specific luminosity well understood and improvements underway

Polarization Satisfactory with up to 50%


Overall Efficiency of operations unsatisfactory, only 40%

→ more efforts are needed

- Better Support of critical components
- Rigorous exchange program for aging and failing components
- Redesign of unsatisfactory components
- Improved operator training program




2004 Luminosity Accumulation



Peak luminosity $\rightarrow 1.2 \text{ pb}^{-1} \text{ d}^{-1}$
 Best week $0.9 \text{ pb}^{-1} \text{ d}^{-1}$ 2004
 Average $0.4 \text{ pb}^{-1} \text{ d}^{-1}$


~ 50 days of operations lost

Due to major technical failures




Improving Design Weakness:

Troublesome Flange Connection NR Replaced by Welded Connection




γ
p
e



HERA Electron Proton Running

- Switching to Electrons done in several steps starting with recovering from shutdown with positrons ... this saved time in the end
- Careful beam based alignment
- Adjusting magnets and H1 detector positions
- Slow start due to problem with 2 GN-type magnets
- Luminosity runs started with 60 bunches in December
- Careful adjustments of files to avoid heating of vacuum components due to increased synchrotron radiation power
- After short holiday break restart with 120 bunches




Electron-Proton Run

- Specific Luminosity exceeds design with values of around $2 \times 10^{30} \text{ mA}^{-2}\text{cm}^{-2}\text{s}^{-1}$
- Absolute luminosities comparable with 2004 positron-proton run despite lower beam currents
- Luminosity production rate reaches $1\text{pb}^{-1}\text{d}^{-1}$
- Vacuum in North IR slowly recovering, now $\sim 1\text{ntorr}$ with beam, H1 cannot turn on with full current
- Additional problem spiky backgrounds ...

Example: HERA Week #6

Feb 8-14, 2005




Luminosity production $\int Ldt = 6.4 \text{ pb}^{-1}$

Polarization tuning disappointing: 30%

Backgrounds: still critical but somewhat better

Monday: Number of bunches increased from 120 to 150

Polarization 2005




Polarization ~50% but only for non-colliding bunches

Colliding bunches only 30 % → Strong beam-beam effects

Alternative working point under consideration



Strong synchro-betatron resonances



Mirror
Tunes

HERA I and HERA II Luminosity

Peak luminosity
so far $4.5 \cdot 10^{31} \text{ cm}^{-2} \text{ sec}^{-2}$



HERA Improvement Program:

rich program with 70 items defined in 2003, program well underway, the most important ones being:

BU Magnet Refurbishing			1.0 M€
Proton RF Systems	Improved low-level controls Suppression of long. Instability	2/2/.5 PJ	0.55 M€
Diagnostics Systems	improved monitors (BPM, SR)	1./0.3/0.1 PJ	0.15 M€
Vacuum System	better pumping in RF sections	0/0.5/1.0PJ	0.5 M€
Power Supply Systems	add'1 Ps for spin matching	0 /0.3/0.2 PJ	0.2 M€
e-RF Systems	RF Modulator upgrade	0/0.5/.95 PJ	0.13 M€
Cryogenic Systems	compressor and controls upgr.	0 /0.5/1.5 PJ	0.45 M€

Summe:

14.6 PJ @ 0.605 M€ (add'l only)

1.13 M€

Coil Refurbishing Vertical n.c. BU Dipole Magnet in HERA p

- Needed to bend proton beam upwards at both ends of the IR
- There are 3 Magnets on both sides of the IP in the three IR-s
= 18Magnets
- Magnets develop ground faults because of water leaks of the brazed Cu conductor
- All coils tested so far
~8 have leaks



Low p-Energy Running

Experience: 500GeV p on 27.5GeV e running in 1991 with very low luminosity

→ Not really an existence proof

Proton energies in the range 400GeV-920GeV should be not problem

Luminosity scales (presumably) as $L \sim E_p^2$

Accelerator Preparation time: 2-3 weeks

Conclusions

- HERA has always been a challenging project which required the full attention of the DESY laboratory. Thanks to the support in the 90-ties, HERA I running was turned into a respectable success and delivered the data for important physics results
- After the luminosity upgrade the background conditions were intolerable, but HERA has now overcome these problems and performed a promising luminosity run in 2004
- The peak luminosity in 2004 was twice as large as in Y 2000
- No unpleasant surprises with 2005 electron proton run, luminosity very good despite reduced intensity
- Longitudinal polarized positrons are delivered routinely to the experiments in 3 IPs
- The challenge is to achieve the Y1999/2000 operational efficiency
- There are good chances that HERA can reach its luminosity goal of 1fb^{-1}
However this requires increased efforts and continuous support of the HERA program by qualified personnel and by the implementation of an ongoing maintenance and improvement program

