

HERA Operation and Prospects



HERA-LHC Workshop Final Meeting

March 22-24 2005

F. Willeke, DESY

- HERA overview
- HERA I summary
- HERA luminosity Upgrade and 2004 proton $-e^+$
- HERA improvement program
- present performance
- Outlook and conclusions


Lepton-Proton Collider with
320 GeV center of mass Energy

HERA Double Ring Collider



820 GeV Protons (actual 920 GeV)

30 GeV Leptons e^+ or e^- (actual 27.5 GeV)


Spatial resolution 10^{-18}m




Björn Wiik (1937-1999)



HERA Footprint



Milestones

- 
- 1981 Proposal
- 1984 Start Construction
- 1991 Commissioning, first Collisions
- 5 Start Operations for H1 and ZEUS,
1st Exciting Results with low Luminosity
- 1994 Install East spin Rotators longitudinal polarized leptons for HERMES
- 1996 Install 4th Interaction region for HERA-B
- 1998 Install NEG pumps against dust problem, Reliability Upgrade
- 2000 High efficient Luminosity production: $100\text{pb}^{-1}\text{y}^{-1}$
HERA I: $180\text{pb}^{-1} e^+p$ Precision Measurement on proton structure
- 2001 Install HERA Luminosity Upgrade, Spin Rotators for H1 and ZEUS
- 2001/2 Recommissioning, HERA-B physics Run
- 14 1st longitudinal polarization in high energy ep collisions
- 2003/4 Start-up of the HERA II Run

HERA I




The building, commissioning and efficient operation of the complex HERA accelerator represented a major challenge for DESY, which required a large and continuous effort


This effort allowed eventually to exceed the planned peak performance with a peak luminosity

$$L_{\text{peak}} = 2 \cdot 10^{31} \text{ cm}^{-2} \text{ s}^{-1}$$

and a Production of 67pb^{-1} in the 200 days of running in 2000.

For more luminosity, a upgrade was performed in 2000-2001 for an increase of a factor of three in peak performance









Superconducting Magnets

GO/GG


Designed + built in collaboration with BNL




- cryostat-wall
- He-vessel
- coil
- Beam pipe
- support tube
- insulating vacuum,
- He-supply



Superconducting Magnets in the Detectors



Courtesy ZEUS Collaboration



HERA II Luminosity Parameters

$$L = \frac{N_p \cdot I_e}{4 \pi e \cdot \epsilon_N \cdot \sqrt{\beta_{xp} \beta_{yp}}}$$

UPGRADE ←

Beam Energies

$$E_e = 920\text{GeV} / 27.5\text{GeV}$$

Proton Beam current

$$I_p = 100\text{mA}$$

leptons current

$$I_e = 50\text{mA}$$

number of protons per bunch

$$N_p = 1 \times 10^{11}$$

normalized emittance

$$\epsilon_N = 20 \mu\text{m} \quad \text{Proton}$$

beta functions

$$\beta_{y,x} = 18\text{cm} , 2.45\text{m}$$

lepton emittance

$$\epsilon_e = 20\text{nm}$$

number of coll. bunches

$$n_b = 174$$

lepton vert. b.-b. tune shift par.

$$\Delta_{y,x e} = 0.045, 0.025$$


hor./vert. beam size at IP

$$\sigma_{x,y,p,e} = 114\mu\text{m} / 30\mu\text{m}$$

luminosity



$$L = 5 \times 10^{31} \text{cm}^{-2} \text{sec}^{-1}$$

Recommissioning: High Luminosity Demonstrated




Record Luminosity
 120 Bunches
 $I_p < 70 \text{ mA}$
 $I_e < 35 \text{ mA}$

$$L_{\text{peak}} > 2.7 \times 10^{31} \text{ cm}^{-2} \text{ s}^{-1}$$



Conclusion: HERA is able to deliver luminosity as advertised

HERA Longitudinal Polarization



Polarization after p-Beam
Loss on Feb. 12, 2004

Polarization in collisions: 30-40%
Polarization without collisions up to 50%


Further improvement plans:

Dedicated 2 Polarization Studies

Beam Based alignment
(suffers from lack of resources)

Need better polarization measurement for fast
tuning!!

Regular Rotator Flip





Backgrounds after Luminosity upgrade:

This looked very serious in the beginning and required time to gain understanding and implement counter measures


- Direct Synchrotron Radiation: solved by IR design, SR collimation and sophisticated beam steering procedures
- Indirect (backscattered) synchrotron radiation required improved masking in ZEUS
- e^+ particle backgrounds improved with improving vacuum (beam conditioning) and the addition of a pump in a critical location
- proton backgrounds improved with regular beam operation and we are at the point, where this is no issues for ZEUS anymore and almost no issue for H1 anymore

Improvement of synchrotron radiation mask system





before

after




Improvement of synchrotron radiation mask system




before

after




2004 Luminosity Accumulation





Peak luminosity $1.2 \text{ pb}^{-1}\text{d}^{-1}$
 Best week $0.9 \text{ pb}^{-1}\text{d}^{-1}$
 2004 Average $0.4 \text{ pb}^{-1}\text{d}^{-1}$

~50 days of operations lost Due
 to major technical failures
Operational efficiency needs to be improved



Improving Design Weakness:

Troublesome Flange Connection NR Replaced by Welded Connection




HERA Electron Proton Running

- Switching to Electrons done in several steps starting with recovering from shutdown with positrons ... this saved time in the end
- Careful beam based alignment
- Adjusting magnets and H1 detector positions
- Slow start due to problem with 2 GN-type magnets
- Luminosity runs started with 60 bunches in December
- Careful adjustments of files to avoid heating of vacuum components due to increased synchrotron radiation power
- After short holiday break restart with 120 bunches

Ergebnisse des Fits der Quadrupol Offsets im Norden

Magnet	s	x-Offset		z-Offset	
		nov 30th	dec 2nd	nov 30th	dec 2nd
GJ08 NL	-9.2	-0.05	0.03	-0.15	-0.09
GI07 NL	-7	0.4	-0.08	0.34	0.2
GO Tunnel	-5	0.11	0.03	-0.17	-0.07
GO IP	-2.2	-9.1	-2.5	-0.06	-0.06
GI06 NR	4.8	-0.15	-0.12	0.46	0.27
GI07 NR	7.2	0.94	0.43	0.25	0.09
GJ08 NR	9.5	-0.26	-0.12	0.22	0.09




Electron-Proton Run

- Specific Luminosity exceeds design with values of around $2 \times 10^{30} \text{ mA}^{-2} \text{ cm}^{-2} \text{ s}^{-1}$
- Absolute luminosities comparable with 2004 positron-proton run despite lower beam currents
- Luminosity production rate reaches $1 \text{ pb}^{-1} \text{ d}^{-1}$
- Vacuum in North IR slowly recovering, now $\sim 1 \text{ torr}$ with beam, H1 cannot turn on with full current
- Additional problem spiky backgrounds ...

Example: HERA Week #6

Feb 8-14, 2005




Luminosity production $\int L dt = 6.4 \text{ pb}^{-1}$

Polarization tuning disappointing: 30%

Backgrounds: still critical but somewhat better

Monday: Number of bunches increased from 120 to 150

Polarization 2005




Polarization ~50% but only for non-colliding bunches

Colliding bunches only 30 % Strong beam-beam effects

Alternative working point under consideration

Strong synchro-betatron resonances

BETATRON TUNE DIAGRAM






Mirror Tunes

HERA I and HERA II Luminosity

Peak luminosity so far
 $4.5 \cdot 10^{31} \text{ cm}^{-2} \text{ sec}^{-2}$

Measured and Modeled Peak Lumi



HERA Improvement Program:

rich program with 70 items defined in 2003, program well underway, the most important ones being:

BU Magnet Refurbishing			1.0 M€
Proton RF Systems	Improved low-level controls Suppression of long. Instability	2/2/.5 PJ	0.55 M€
Diagnostics Systems	improved monitors (BPM, SR)	1./0.3/0.1 PJ	0.15 M€
Vacuum System	better pumping in RF sections	0/0.5/1.0PJ	0.5 M€
Power Supply Systems	add'l Ps for spin matching	0 /0.3/0.2 PJ	0.2 M€
e-RF Systems	RF Modulator upgrade	0/0.5/.95 PJ	0.13 M€
Cryogenic Systems	compressor and controls upgr.	0 /0.5/1.5 PJ	0.45 M€

Summe:

14.6 PJ @ 0.605 M€ (add'l only)

1.13 M€

Coil Refurbishing Vertical n.c. BU Dipole Magnet in HERA p

- Needed to bend proton beam upwards at both ends of the IR
- There are 3 Magnets on both sides of the IP in the three IR-s
- = 18Magnets
- Magnets develop ground faults because of water leaks of the brazed Cu conductor
- All coils tested so far ~8 have leaks
- Refurbishing program
- This shutdown: 6 Half coils NL replaced
- 8 more coils ordered for later replacements



Low p-Energy Running

Experience: 500GeV p on 27.5GeV e running in 1991 with very low luminosity

Not really an existence proof

Proton energies in the range 400GeV-920GeV should be not problem

Luminosity scales (presumably) as

$$L \sim E_p^2$$

Accelerator Preparation time: 2-3 weeks

Conclusions

- HERA has always been a challenging project which required the full attention of the DESY laboratory. Thanks to the support in the 90-ties, HERA I running was turned into a respectable success and delivered the data for important physics results
- After the luminosity upgrade the background conditions were intolerable, but HERA has now overcome these problems and performed a promising luminosity run in 2004
- The peak luminosity in 2004 was twice as large as in Y 2000
- No unpleasant surprises with 2005 electron proton run, luminosity very good despite reduced intensity
- Longitudinal polarized positrons are delivered routinely to the experiments in 3 IPs
- The challenge is to achieve the Y1999/2000 operational efficiency
- There are good chances that HERA can reach its luminosity goal of 1fb^{-1}
However this requires increased efforts and continuous support of the HERA program by qualified personnel and by the implementation of an ongoing maintenance and improvement program

