



SC04 Workshop

Mumbai

February 2006

David Foster

Network and Communications Systems Group Leader

Information Technology Department

CERN – European Organization for Nuclear Research

Geneva, Switzerland

david.foster@cern.ch




LHC Networking - T0, T1, T2

- Composed of many different Infrastructures
 - Relies on many different networks
 - Dedicated Circuits
 - USLHCNet (dedicated links)
 - Research Infrastructures
 - National Research Networks (NRENS), Projects (GEANT)
 - Internet connectivity
- Has different requirements
 - Raw data transmission, production, analysis
- Some objectives very clear
 - To be able to get the data from the T0 to the T1's as quickly and reliably as possible after data taking
 - Imagine an "optical private network", OPN, for this purpose, although this is part of the overall networking that will be used.




Tier0 / Tier1 / Tier2 Networks





LHCOPN - Where are we?

- "Complete"
 - SARA - 10G provided by Surfnet but transition to GEANT expected.
 - IN2P3 - 10G provided by RENATER owned dark fiber.
 - CNAF - 10G connected via GEANT
 - FNAL - 10G link available but will share with other US transit traffic.
- Coming soon
 - FzK - Currently GEANT IP service. 10G dedicated will be provided by GEANT.
 - BNL - Currently 10G transatlantic link in place, 10G "last mile" via ESNET expected soon.
- Mid-Year
 - RAL - Currently 2x1G. Will go to 4x1G. SuperJanet4 should complete UKERNA 10G link to RAL and then via GEANT to CERN.
 - NDGF - Currently GEANT IP service. Copenhagen 10G link via GEANT will be transited to distributed T1 by Nordunet.
 - TRIUMF - Currently 10G to amsterdam in place, transited via SURFNET to CERN. Will pass to GEANT transit from Amsterdam.
- End-Year
 - PIC - Currently 1G shared, will become 1G dedicated. 10G via GEANT (maybe via drop off of Madrid dark fiber in Barcelona)
- Unclear
 - ASCC - Currently 2x1G. Plans to go to 2x2.5G



Risks, Open Issues and Problems

- The cost sharing agreement with the GEANT partners (NRENS) are not yet complete.
 - Expect the formalities to be complete in the next 4 weeks, but negotiations are on-going and difficult.

- Some links will increase bandwidth as needed.
 - USLHCNet links will pass other traffic.
 - ASCC will not have full 10G bandwidth.
 - TRIUMF will increase bandwidth as needed.

- LHC OPN working groups status
 - **Routing** - all is largely clear.
 - **Security** - all is largely clear, some work now needed for this to be ratified by the site security officers.
 - **Monitoring** - not yet clear. Options exist, but dedicated infrastructure likely.
 - **Operations** - not yet clear. Interoperation of GRID/network operations very unclear. The role of EGEE NOC (ENOC), the NREN NOCS, DANTE, GGUS etc. Processes as yet undefined but work is on-going in this area.

- Many network operations not 24x7
 - <http://lhcopn.cern.ch>