



Initial Commissioning to Stable Beams

Belen Salvachua

**On behalf of the LHC Team with MANY input from
Ph.Baudrenghien, Ch.Bracco, E.Bravin, W.Hofle, G.Iadarola,
M.Lamont, Th.Lefevre, S.Redaeli, M.Solfaroli, J.Wenninger,
H.Timko, R.Tomas**



Outline

- ▶ **Assumptions for next year**
- ▶ **Commissioning Phases**
- ▶ **System and Measurement requirements**
- ▶ **2016 Schedule**
- ▶ **Scrubbing**
- ▶ **Intensity ramp-up**

Assumptions for 2016

Beam Parameters for 2016	
Intensity per bunch	1.2×10^{11} p/b
Bunch spacing	25 ns
Max. bunches per train	288
Tune (H/V) at injection	0.275 / 0.295
Chromaticity at injection	15 / 15
Machine cycle for operation (see Matteo Solfaroli's talk)	
Injection	Same as 2015
Ramp and Squeeze (IP1/IP2/IP5/IP8)	3m/10m/3m/5m
Squeeze (IP1/IP2/IP5/IP8)	0.4m/10m/0.4m/3m
Collisions	Adjusted to new beta

Assumptions for 2016

Beam Parameters for 2016

Intensity per bunch

1.2×10^{11} p/b

Bunch spacing

25 ns

Max. bunches per train

288

Tune (H/V) at injection

0.275 / 0.295

Chromaticity at injection

15 / 15

Machine cycle for operation (see Matteo Solfaroli's talk)

Injection

Same as 2015

Ramp and Squeeze (IP1/IP2/IP5/IP8)

3m/10m/3m/5m

Squeeze (IP1/IP2/IP5/IP8)

0.4m/10m/0.4m/3m

Collisions

Adjusted to new beta

Commissioning Phases

Commissioning Phases

HW Commissioning

Commissioning Phases

HW Commissioning

4 weeks

Beam Commissioning

Stable Beams

Commissioning Phases

HW Commissioning

4 weeks
Beam Commissioning
Stable Beams

Scrubbing 1 weeks

Commissioning Phases

Setup and Validate all relevant systems. MP Test.

Measurements to assess final beam parameters.

Established the new cycle and low intensity

Stable Beam conditions

Prepare machine for high intensity beam. Setup of trains. Ramp up: goal 2800b

HW Commissioning

Beam Commissioning 4 weeks
Stable Beams

Scrubbing 1 weeks

Commissioning Phases

Setup and Validate all relevant systems. MP Test.

Measurements to assess final beam parameters.

Established the new cycle and low intensity

Stable Beam conditions

Prepare machine for high intensity beam. Setup of trains. Ramp up: goal 2800b

Ramp & Squeeze:

- First pass with probes, feedforward corrections from MD. OFB and QFB on, flat orbit, optic measurements.
- Second pass with RF modulation, feedforward tune, flat orbit...
- Ramp with bumps (probes)
- Ramp with bumps (nominals)

HW Commissioning

4 weeks
Beam Commissioning
Stable Beams

Scrubbing 1 weeks

Commissioning Phases

Setup and Validate all relevant systems. MP Test.

Measurements to assess final beam parameters.

Established the new cycle and low intensity

Stable Beam conditions

Prepare machine for high intensity beam. Setup of trains. Ramp up: goal 2800b

Ramp & Squeeze:

- First pass with probes, feedforward corrections from MD. OFB and QFB on, flat orbit, optic measurements.
- Second pass with RF modulation, feedforward tune, flat orbit...
- Ramp with bumps (probes)
- Ramp with bumps (nominals)

Squeeze:

- First pass in steps, probes and optics measurements
- Squeeze in steps with probes, optics corrections
- Squeeze feedforward, chroma, tunes and optics corrections.
- Squeeze with bumps on
- Squeeze with bumps (nominals) and aperture measurements

HW Commissioning

4 weeks
Beam Commissioning
Stable Beams

Scrubbing 1 weeks

Commissioning Phases

Setup and Validate all relevant systems. MP Test.

Measurements to assess final beam parameters.

Established the new cycle and low intensity

Stable Beam conditions

Prepare machine for high intensity beam. Setup of trains. Ramp up: goal 2800b

Ramp & Squeeze:

- First pass with probes, feedforward corrections from MD. OFB and QFB on, flat orbit, optic measurements.
- Second pass with RF modulation, feedforward tune, flat orbit...
- Ramp with bumps (probes)
- Ramp with bumps (nominals)

Squeeze:

- First pass in steps, probes and optics measurements
- Squeeze in steps with probes, optics corrections
- Squeeze feedforward, chroma, tunes and optics corrections.
- Squeeze with bumps on
- Squeeze with bumps (nominals) and aperture measurements

HW Commissioning

4 weeks
Beam Commissioning
Stable Beams

Scrubbing 1 weeks

Intensity Ramp up

Scrubbing

Scrubbing

2800 bunches

Commissioning Phases

Setup and Validate all relevant systems. MP Test.

Measurements to assess final beam parameters.

Established the new cycle and low intensity

Stable Beam conditions

Prepare machine for high intensity beam. Setup of trains. Ramp up: goal 2800b

Ramp & Squeeze:

- First pass with probes, feedforward corrections from MD. OFB and QFB on, flat orbit, optic measurements.
- Second pass with RF modulation, feedforward tune, flat orbit...
- Ramp with bumps (probes)
- Ramp with bumps (nominals)

Squeeze:

- First pass in steps, probes and optics measurements
- Squeeze in steps with probes, optics corrections
- Squeeze feedforward, chroma, tunes and optics corrections.
- Squeeze with bumps on
- Squeeze with bumps (nominals) and aperture measurements

HW Commissioning

4 weeks
Beam Commissioning
Stable Beams

Scrubbing 1 weeks

Intensity Ramp up

Scrubbing

Scrubbing

2800 bunches

Stable Physics

Systems and Measurements

Systems and Measurements

Systems

Injection

LDBS

Collimation

RF and ADT

B. Instrumentation

Systems and Measurements

Systems

Injection

LDBS

Collimation

RF and ADT

B. Instrumentation

Measurements

Orbit

Optics

Aperture

Impedance

Magnetic Reproducibility

MP and Loss maps Validation

Setup of trains

Systems and Measurements

New LHC Cycle: Ramp-squeeze and Squeeze to 0.4 m

Measurements

Systems

Injection

LDBS

Collimation

RF and ADT

B. Instrumentation

Orbit

Optics

Aperture

Impedance

Magnetic Reproducibility

MP and Loss maps Validation

Setup of trains

Injection & LBDS

Injection & LBDS

Injection

► SPS extraction ([link to YETS modifications](#)):

- ➡ MKE4 waveform: beam on downstream TED (4hours)
- ➡ Extraction aperture (0.5 hours/beam)

► Transfer Lines

- ➡ TCDI setup and validation (2hours/beam)

► Injection Protection Collimators

- ➡ TDI, TCLIA, TCLIB setup and validation (8 hours / beam)

Injection & LBDS

Injection

► SPS extraction ([link to YETS modifications](#)):

- ➔ MKE4 waveform: beam on downstream TED (4hours)
- ➔ Extraction aperture (0.5 hours/beam)

► Transfer Lines


- ➔ TCDI setup and validation (2hours/beam)

► Injection Protection Collimators

- ➔ TDI, TCLIA, TCLIB setup and validation (8 hours / beam)

Transfer line commissioning

- Establish the transfer line references with pilot
- Procedure improved for the pilot trajectory to be more representative of the nominal :



Kickers delays changed for the MKEs and the MKIs so that the pilot is positioned at the middle of the waveform



In the SPS pilot on the nominal cycle for comparable magnetic history

Chiara Bracco

Injection & LBDS

Injection

► SPS extraction ([link to YETS modifications](#)):

- ➔ MKE4 waveform: beam on downstream TED (4hours)
- ➔ Extraction aperture (0.5 hours/beam)

► Transfer Lines


- ➔ TCDI setup and validation (2hours/beam)

► Injection Protection Collimators

- ➔ TDI, TCLIA, TCLIB setup and validation (8 hours / beam)

Transfer line commissioning

- Establish the transfer line references with pilot
- Procedure improved for the pilot trajectory to be more representative of the nominal :



Kickers delays changed for the MKEs and the MKIs so that the pilot is positioned at the middle of the waveform

We gain later on TL steering with a good initial reference.

on the nominal cycle for magnetic history

Chiara Bracco

Injection & LBDS

Injection

► SPS extraction ([link to YETS modifications](#)):

- ➔ MKE4 waveform: beam on downstream TED (4hours)
- ➔ Extraction aperture (0.5 hours/beam)

► Transfer Lines

- ➔ TCDI setup and validation (2hours/beam)

► Injection Protection Collimators

- ➔ TDI, TCLIA, TCLIB setup and validation (8 hours / beam)

LBDS

► TCDQ and TCSP setup and validation (8 hours/beam)

► Calibration measurements for Async. BD ([link](#))


- ➔ Aperture measurements IP6 (2 hours / beam)
- ➔ Transmission measurements (4 hours / beam)

► Validation of BPMS (BI)

► Final validation with Async. BD test

Transfer line commissioning

- Establish the transfer line references with pilot
- Procedure improved for the pilot trajectory to be more representative of the nominal :



Kickers delays changed for the MKEs and the MKIs so that the pilot is positioned at the middle of the waveform

We gain later on TL steering with a good initial reference.

on the nominal cycle for magnetic history

Chiara Bracco

Injection & LBDS

Injection

► SPS extraction ([link to YETS modifications](#)):

- ➔ MKE4 waveform: beam on downstream TED (4hours)
- ➔ Extraction aperture (0.5 hours/beam)

► Transfer Lines

- ➔ TCDI setup and validation (2hours/beam)

► Injection Protection Collimators

- ➔ TDI, TCLIA, TCLIB setup and validation (8 hours / beam)

LBDS

► TCDQ and TCSP setup and validation (8 hours/beam)

► Calibration measurements for Async. BD ([link](#))


- ➔ Aperture measurements IP6 (2 hours / beam)
- ➔ Transmission measurements (4 hours / beam)

► Validation of BPMS (BI)

► Final validation with Async. BD test

Transfer line commissioning

- Establish the transfer line references with pilot
- Procedure improved for the pilot trajectory to be more representative of the nominal :



Kickers delays changed for the MKEs and the MKIs so that the pilot is positioned at the middle of the waveform

We gain later on TL steering with a good initial reference.

on the nominal cycle for magnetic history

Chiara Bracco

Build a reference of conditions before an asynchronous beam dump happens.

Collimation

Collimation



Commissioning plans for 2016




- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➡ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (*1 - 2 shifts*):
 - ➡ BLM vs BPM alignment cross-checks
 - ➡ Collimator scans to measure BPM non-linearities
 - ➡ Tests of BPM interlock implementation

Collimation

► Alignment (3x8h)



Commissioning plans for 2016



- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➡ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (*1 - 2 shifts*):
 - ➡ BLM vs BPM alignment cross-checks
 - ➡ Collimator scans to measure BPM non-linearities
 - ➡ Tests of BPM interlock implementation

Evian Workshop - 16/12/2015

G. Valentino - BE/ABP


17

Collimation


► Alignment (3x8h)

► BPMs at collimators (1-2 x 8 h):

- ➡ Polarity checks (BI) 15min
- ➡ BPM calibration: linearity scans
- ➡ BLM vs BPM alignment check
- ➡ Test BPM interlock implementations



Commissioning plans for 2016



- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➡ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (*1 - 2 shifts*):
 - ➡ BLM vs BPM alignment cross-checks
 - ➡ Collimator scans to measure BPM non-linearities
 - ➡ Tests of BPM interlock implementation



Evian Workshop - 16/12/2015

G. Valentino - BE/ABP

17

Collimation

- ▶ **Alignment (3x8h)**
- ▶ **BPMs at collimators (1-2 x 8 h):**
 - ➔ Polarity checks (BI) 15min
 - ➔ BPM calibration: linearity scans
 - ➔ BLM vs BPM alignment check
 - ➔ Test BPM interlock implementations
- ▶ **Global aperture: (1-2 x 8h)**
 - ➔ **Injection:** Global aperture, if reproducible then we do not repeat the local aperture with bumps. (8 h)
 - ➔ **6.5 TeV @ 3 m:** not needed
 - ➔ **6.5 TeV @ 0.4 m:** needed (8 h)
 - ➔ ULO (4 h)




Commissioning plans for 2016

- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➔ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (1 - 2 shifts):
 - ➔ BLM vs BPM alignment cross-checks
 - ➔ Collimator scans to measure BPM non-linearities
 - ➔ Tests of BPM interlock implementation

Evian Workshop - 16/12/2015 G. Valentino - BE/ABP 17

Collimation

- ▶ **Alignment (3x8h)**
- ▶ **BPMs at collimators (1-2 x 8 h):**
 - ➔ Polarity checks (BI) 15min
 - ➔ BPM calibration: linearity scans
 - ➔ BLM vs BPM alignment check
 - ➔ Test BPM interlock implementations
- ▶ **Global aperture: (1-2 x 8h)**
 - ➔ **Injection:** Global aperture, if reproducible then we do not repeat the local aperture with bumps. (8 h)
 - ➔ **6.5 TeV @ 3 m:** not needed
 - ➔ **6.5 TeV @ 0.4 m:** needed (8 h)
 - ➔ ULO (4 h)
- ▶ **Alignment of Roman Pots (TOTEM for low beta)**





Commissioning plans for 2016

- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➔ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (1 - 2 shifts):
 - ➔ BLM vs BPM alignment cross-checks
 - ➔ Collimator scans to measure BPM non-linearities
 - ➔ Tests of BPM interlock implementation

Evian Workshop - 16/12/2015 G. Valentino - BE/ABP 17

Collimation

- ▶ **Alignment (3x8h)**
- ▶ **BPMs at collimators (1-2 x 8 h):**
 - ➔ Polarity checks (BI) 15min
 - ➔ BPM calibration: linearity scans
 - ➔ BLM vs BPM alignment check
 - ➔ Test BPM interlock implementations
- ▶ **Global aperture: (1-2 x 8h)**
 - ➔ **Injection:** Global aperture, if reproducible then we do not repeat the local aperture with bumps. (8 h)
 - ➔ **6.5 TeV @ 3 m:** not needed
 - ➔ **6.5 TeV @ 0.4 m:** needed (8 h)
 - ➔ ULO (4 h)
- ▶ **Alignment of Roman Pots (TOTEM for low beta)**
- ▶ **Validation: (4 x 8 h)**




Commissioning plans for 2016

- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➔ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (1 - 2 shifts):
 - ➔ BLM vs BPM alignment cross-checks
 - ➔ Collimator scans to measure BPM non-linearities
 - ➔ Tests of BPM interlock implementation


Evian Workshop - 16/12/2015 G. Valentino - BE/ABP 17

Collimation

- ▶ **Alignment (3x8h)**
- ▶ **BPMs at collimators (1-2 x 8 h):**
 - ➔ Polarity checks (BI) 15min
 - ➔ BPM calibration: linearity scans
 - ➔ BLM vs BPM alignment check
 - ➔ Test BPM interlock implementations
- ▶ **Global aperture: (1-2 x 8h)**
 - ➔ **Injection:** Global aperture, if reproducible then we do not repeat the local aperture with bumps. (8 h)
 - ➔ **6.5 TeV @ 3 m:** not needed
 - ➔ **6.5 TeV @ 0.4 m:** needed (8 h)
 - ➔ ULO (4 h)
- ▶ **Alignment of Roman Pots (TOTEM for low beta)**
- ▶ **Validation: (4 x 8 h)**
 - ➔ Standard Loss maps



Commissioning plans for 2016



- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➔ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (1 - 2 shifts):
 - ➔ BLM vs BPM alignment cross-checks
 - ➔ Collimator scans to measure BPM non-linearities
 - ➔ Tests of BPM interlock implementation

Evian Workshop - 16/12/2015

G. Valentino - BE/ABP

17

Collimation

► Alignment (3x8h)

► BPMs at collimators (1-2 x 8 h):

- ➔ Polarity checks (BI) 15min
- ➔ BPM calibration: linearity scans
- ➔ BLM vs BPM alignment check
- ➔ Test BPM interlock implementations


► Global aperture: (1-2 x 8h)

- ➔ **Injection:** Global aperture, if reproducible then we do not repeat the local aperture with bumps. (8 h)
- ➔ **6.5 TeV @ 3 m:** not needed
- ➔ **6.5 TeV @ 0.4 m:** needed (8 h)
- ➔ ULO (4 h)

► Alignment of Roman Pots (TOTEM for low beta)

► Validation: (4 x 8 h)

- ➔ Standard Loss maps
- ➔ Loss maps during the Ramp/Squeeze (parasitically during the first test ramp with nominals)



The slide is titled "Commissioning plans for 2016" and features the CERN logo on the top left and the LHC Collimation Project logo on the top right. It contains a bulleted list of commissioning tasks and their durations. The footer includes the text "Evian Workshop - 16/12/2015", "G. Valentino - BE/ABP", and the slide number "17".

- Require usual alignments + validation at 4 points in the machine cycle (injection, ramp, squeeze, collisions).
 - ➔ 3 shifts for alignments + 3 shifts for validation
- Don't plan major changes to the control software, so we will only repeat a subset of MP tests that ensures that each IP is tested.
- For the embedded BPM collimators, with the final DOROS electronics software in place since TS2, will have to repeat several tests with beam (1 - 2 shifts):
 - ➔ BLM vs BPM alignment cross-checks
 - ➔ Collimator scans to measure BPM non-linearities
 - ➔ Tests of BPM interlock implementation

Evian Workshop - 16/12/2015 G. Valentino - BE/ABP 17

ADT and RF

RF

- ▶ **For nominal parameters:** $1.2 \times 10^{11} p/b$, 25 ns, 6.5 TeV
 - ➔ RF synchro and capture (8h)
 - ➔ 1.25 ns and 10-12 MV
- ▶ **If bunch intensity above nominal:**
 - ➔ Condition the klystrons at 300 kW (HW commissioning)
 - ➔ Preparation of phase modulation scheme to cope with double bunch intensity (MD time). IPAC12, MOPPC015

ADT and RF

RF

- ▶ **For nominal parameters:** $1.2 \times 10^{11} p/b$, 25 ns, 6.5 TeV
 - ➔ RF synchro and capture (8h)
 - ➔ 1.25 ns and 10-12 MV
- ▶ **If bunch intensity above nominal:**
 - ➔ Condition the klystrons at 300 kW (HW commissioning)
 - ➔ Preparation of phase modulation scheme to cope with double bunch intensity (MD time). IPAC12, MOPPC015

ADT

- ▶ **Standard setup (8h)** LBOC 2014
 - ➔ bunch intensity, tunes, Abort gap cleaning, injection cleaning, loss maps
- ▶ **Automatic intensity settings and protection (4 h)**
- ▶ **Setup of trains**
- ▶ ***New pickups Q8/Q10 will be commissioned mid 2016***

Beam Instrumentation

preliminary list...

Beam Instrumentation

► BLM (11h + ramp up)

preliminary list...

- ➔ Interlock functionality check (3h)
- ➔ Latency check (2h)
- ➔ direct BLM tests with beam dumping system (4h)
- ➔ Threshold and reaction time at collimators at injection and top energy (1h+1h and ramp up)

Beam Instrumentation

► BLM (11h + ramp up)

preliminary list...

- ➔ Interlock functionality check (3h)
- ➔ Latency check (2h)
- ➔ direct BLM tests with beam dumping system (4h)
- ➔ Threshold and reaction time at collimators at injection and top energy (1h+1h and ramp up)

► BPM (9h)

- ➔ Connectivity tests using kick response and with RF trimming (3h) - polarity inversion and faulty channels.
- ➔ BPM phasing to verify the capture and bunch orbit mode (IQC) (3h)
- ➔ Interlock BPMs: bumps and slow bunch cleaning with ADT. Check of position threshold and sensitivity range (4h)
- ➔ Collimator BPMs: covered in collimation

Beam Instrumentation

► BLM (11h + ramp up)

preliminary list...

- ➔ Interlock functionality check (3h)
- ➔ Latency check (2h)
- ➔ direct BLM tests with beam dumping system (4h)
- ➔ Threshold and reaction time at collimators at injection and top energy (1h+1h and ramp up)

► BPM (9h)

- ➔ Connectivity tests using kick response and with RF trimming (3h) - polarity inversion and faulty channels.
- ➔ BPM phasing to verify the capture and bunch orbit mode (IQC) (3h)
- ➔ Interlock BPMs: bumps and slow bunch cleaning with ADT. Check of position threshold and sensitivity range (4h)
- ➔ Collimator BPMs: covered in collimation

► BSRT (4h + 4h and 2 ramp-ups)

- ➔ One week of parasitic data taking and tuning
- ➔ Machine validated for INDIV. Calibration with beam (2h + 2h and a ramp up)
- ➔ Repeat calibration few days later after HW adjustments (2h + 2h and a ramp up)

Beam Instrumentation

► BLM (11h + ramp up)

preliminary list...

- ➔ Interlock functionality check (3h)
- ➔ Latency check (2h)
- ➔ direct BLM tests with beam dumping system (4h)
- ➔ Threshold and reaction time at collimators at injection and top energy (1h+1h and ramp up)

► BPM (9h)

- ➔ Connectivity tests using kick response and with RF trimming (3h) - polarity inversion and faulty channels.
- ➔ BPM phasing to verify the capture and bunch orbit mode (IQC) (3h)
- ➔ Interlock BPMs: bumps and slow bunch cleaning with ADT. Check of position threshold and sensitivity range (4h)
- ➔ Collimator BPMs: covered in collimation

► BSRT (4h + 4h and 2 ramp-ups)

- ➔ One week of parasitic data taking and tuning
- ➔ Machine validated for INDIV. Calibration with beam (2h + 2h and a ramp up)
- ➔ Repeat calibration few days later after HW adjustments (2h + 2h and a ramp up)

► BCTs, BSRL, BBQ, BTV etc.

Optics

Optics

► Ballistic optics (1.5 shifts)

- ➔ Precise calibration of the BPMs

- ➔ improve beta-star measurement


(LBOC 2015)

Optics

► Ballistic optics (1.5 shifts)

➔ Precise calibration of the BPMs

➔ improve beta-star measurement
(*LBOC 2015*)



Optics

► Ballistic optics (1.5 shifts)

➔ Precise calibration of the BPMs

➔ improve beta-star measurement

(LBOC 2015)


► Ramp-Squeeze (1 shift)

➔ Optics measurements during the ramp

► 40cm beta-star (3 shifts)

➔ Optics and aperture, crossing angles

► non-linearity corrections (2 shifts)




Commissioning Phases

Recap from previous commissioning periods


Commissioning Phases

Recap from previous commissioning periods



Commissioning Phases

Recap from previous commissioning periods



Planning outline - I

Work in progress...

Shift-by-Shift		
Day	Time	Activity
1	8	Injection, first turn B1&B2
1	8	Closed orbit and capture B1&B2
2	4	Instrumentation - orbit, Q, Q', wire scanner
2	4	Dispersion, coupling, Q, Q', C-measure and correct
2	8	RF capture, delay buckets and ADT first setup with probe
2	4	Feedbacks - recommissioning at injection (Q, orbit, radial)
3	4	Beta beating measurements and correction @ 450 GeV
3	8	Dump check-out
3	8	Ramp-squeeze (1st fill): feed forward corrections from MD, tune feedback on, no
3	0	End previous fill with MP test: BLM ?
3	4	BLM: Transmission time, MPS functionality @ 450 GeV
4	8	Ramp-squeeze (2nd fill): chroma measurement, no tune feedback
4	12	Ballistic optics
4	4	SIS MP test
5	8	Squeeze to 0.4 m
5	8	Squeeze to 0.4 m - Optics measurements
5	8	Reference orbit with probe
6	8	Injection correction and TI2/8 reference trajectories
6	8	Pre-cycle or ramp (no beam) - decay measurements at 450 GeV
6	8	BI shift
7	8	Injection of nominal bunch
7	4	Flat reference orbit at injection with nominal bunch
7	4	ADT setup for nominal bunch - test excitation, abort gap, lossmaps
7	4	ADT setup for nominal bunch - test excitation, inj. cleaning
7	4	Ramp-squeeze (3rd fill): Feed forward, measure chroma, no feedback
8	8	ULO measurement at injection
8	8	Ramp-squeeze (4th ramp): optics measurements along ramp
8	8	Squeeze to 0.4 m - Optics measurements and corrections
9	8	Aperture at 6.5 TeV squeezed

2016 schedule

[Link to 2016 schedule](#)

	Jan				Feb				Mar				
Wk	1	2	3	4	5	6	7	8	9	10	11	12	13
Mo	4	11	18	25	1	8	15	22	29	7	14	21	Easter Mon 28
Tu										Powering tests		Recommissioning with beam	
We				Year end technical stop									
Th										Machine checkout			
Fr												G. Friday	
Sa													
Su													


	Apr			May				June					
Wk	14	15	16	17	18	19	20	21	22	23	24	25	26
Mo	4	11	18	25	2	9	16	23	Whit 30	6	13	20	27
Tu			↓									Special physic run	
We										TS1			
Th							Ascension						
Fr									MD 1				
Sa													
Su				1st May									

Intensity ramp up

3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.





Intensity ramp up

3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.






Intensity ramp up

3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.







Intensity ramp up

3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.




Intensity ramp up

3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.



Intensity ramp up


3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.

► How was in 2012?

- ➔ start: 11 days to 1400b.
- ➔ 3 days to 1400b after TS



Intensity ramp up



3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.

► How was in 2012?

- ➔ start: 11 days to 1400b.
- ➔ 3 days to 1400b after TS



Intensity ramp up




3 fills / 20h SB

► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.

► How was in 2012?

- ➔ start: 11 days to 1400b.
- ➔ 3 days to 1400b after TS




Intensity ramp up

3 fills / 20h SB



► How was in 2015?

- ➔ 50 ns: slow start 11 days to 50 b
- ➔ 25 ns: faster 10 days to 450 b
- ➔ improvement towards the end: 3 days to 1800b.



► How was in 2012?

- ➔ start: 11 days to 1400b.
- ➔ 3 days to 1400b after TS



But remember, next year we will be dominated by cryogenics and e-cloud

Intensity Ramp-Up

► Intensity steps something like:

➔ 3/12 - 50/70 - 250 --- 500 --- 800 - 1200 + 200 to 2200

Intensity Ramp-Up

► Intensity steps something like:

➡ 3/12 - 50/70 - 250 --- 500 --- 800 - 1200 + 200 to 2200

↑
*Single
12b*

1 fill per test,
confirms cycle,
optics, transfer line
steering, etc

Intensity Ramp-Up

► Intensity steps something like:

➔ 3/12 - 50/70 - 250 --- 500 --- 800 - 1200 + 200 to 2200

↑
Single
12b

← 72b, 144b, 288b →
Relevant for Machine Protection

1 fill per test,
confirms cycle,
optics, transfer line
steering, etc

Keep the 3fill/20h SB
Commissioning of longer
trains ASAP: benefit on
scrubbing

Intensity Ramp-Up

► Intensity steps something like:

➔ 3/12 - 50/70 - 250 ★ 500 ★ 800 - 1200 + 200 to 2200

↑
Single
12b

1 fill per test,
confirms cycle,
optics, transfer line
steering, etc

↔
72b, 144b, 288b
Relevant for Machine Protection

Keep the 3fill/20h SB
Commissioning of longer
trains ASAP: benefit on
scrubbing

From this point we might be
limited by e-cloud and cryo

Scrubbing interleave with
intensity ramp-up

Intensity Ramp-Up

► Intensity steps something like:

➡ 3/12 - 50/70 - 250 ★ 500 ★ 800 - 1200 + 200 to 2200

Single
12b

1 fill per test,
confirms cycle,
optics, transfer line
steering, etc

72b, 144b, 288b
Relevant for Machine Protection

Keep the 3fill/20h SB
Commissioning of longer
trains ASAP: benefit on
scrubbing

“Mini” intensity steps, 1
train 288 each time but 1-2
fills with reasonable
physics.

From this point we might be
limited by e-cloud and cryo

Scrubbing interleave with
intensity ramp-up

Intensity Ramp-Up

Intensity Ramp-Up

► Intensity steps something like:

➡ 3/12 - 50/70 - 250 --- 500 --- 800 - 1200 + 200 to 2200

Intensity Ramp-Up

- ▶ **Intensity steps something like:**

 - ➔ 3/12 - 50/70 - 250 --- 500 --- 800 - 1200 + 200 to 2200

- ▶ **keep 3 fills / 20 hours but be flexible.**

Keep this approach until 500 bunches in order to validate machine configuration and optics, allow time to post analyze the fills. Then “mini” steps of 1 extra train with 1 fill in SB without problems.

Intensity Ramp-Up

► Intensity steps something like:

➡ 3/12 - 50/70 - 250 --- 500 --- 800 - 1200 + 200 to 2200

► keep 3 fills / 20 hours but be flexible.

Keep this approach until 500 bunches in order to validate machine configuration and optics, allow time to post analyze the fills. Then “mini” steps of 1 extra train with 1 fill in SB without problems.

► **Similar bunch intensities as end of last year:**

➡ $1.2(5) \times 10^{11}$ p/b (try 1.3×10^{11} when heat load permits)

➡ Only 25ns configuration

➡ Priority to setup 288 bunches

Summary

Summary

► 2016 should be a production year

- ➡ Shorter time for commissioning: 4 weeks
- ➡ Prepare machine for high intensity: 7 days of scrubbing
- ➡ Commissioning of new optics with the goal of 40cm beta-star, measurements and aperture checks will be the decision points for the final beta-star.

Summary

► 2016 should be a production year

- ➡ Shorter time for commissioning: 4 weeks
- ➡ Prepare machine for high intensity: 7 days of scrubbing
- ➡ Commissioning of new optics with the goal of 40cm beta-star, measurements and aperture checks will be the decision points for the final beta-star.

► Intensity Ramp up with the goal to 2800b

- ➡ Keep the strategy of previous years of 3 fills /20 hours, this works well to spot problems during the ramp up.
- ➡ Machine Protection encourages to keep this approach up the injection of 500 bunches
- ➡ Then we will probably be limited by e-cloud and cryogenics
- ➡ After 500 bunches we could envisage to continue with “mini”-steps of intensity (only 1 fill per step) adding 1 train 288 each time.