

# Infrastructure and Operation Summary of parallel sessions

Volker Mertens, CERN

*on behalf of the FCC Infrastructure & Operation Working Group  
and the collaborating partners*

FCC Week 2016  
Rome, 11-15 April 2016

**Big thanks to presenters, chairpersons, organisers !!!**



# Session overview

Infrastructure and Operation overview (V. Mertens, 10')  
 Civil engineering (John A. Osborne, 20')

**Monday**

Time	Day	Topic	Speaker
08:00-09:00	Monday	Registration	
09:00-10:00	Monday	Infrastructure and Operation overview	V. Mertens
10:00-11:00	Monday	Civil engineering	John A. Osborne
11:00-12:00	Monday	Cryogenics	Jaroslav Polinski
12:00-13:00	Monday	Lunch	
13:00-14:00	Monday	Implementation, Electricity, Cooling and Ventilation	Philippe Lebrun
14:00-15:00	Monday	Coffee Break	
15:00-16:00	Monday	Safety, Availability, Controls	Ralf Trant

**Friday**

Summary of parallel Infrastructure and Operation sessions  
 (V. Mertens, 15')

11:00

**Cryogenics**

*Jaroslav Polinski (TU Wroclaw)*

12:00

**Thursday**

**Room:  
Costantino**

13:00

14:00

**Implementation,  
Electricity, Cooling  
and Ventilation**

*Philippe Lebrun (CERN)*

15:00

**Coffee Break**

*Winter Garden, Crowne Plaza*

16:00


**Safety, Availability,  
Controls**

*Ralf Trant (CERN)*

Thursday, 10:30-12:10

## **Cryogenics** – chair: Jaroslaw Polinski / TU Wroclaw


- Cryogenics overview (Laurent Tavian)
- Ne-He cycle refrigeration above 40 K (Steffen Klöppel / TU Dresden)
- Innovative He cycle (François Millet, CEA Grenoble)
- Cool-down and warm-up studies of a FCC sector, Hugo Correia Rodrigues
- Impact of high design pressures on heat inleaks, Pawel Duda / TU Wroclaw




Baseline scheme with 10 cryoplants on 6 technical sites.

Cross section of the magnet    Cross section of the tunnel distribution line


## Electrical consumption for FCC-hh




- RH:** resistive heating
- BGS:** beam-gas scattering
- CM:** cold mass heat-inleaks
- CL:** current lead
- BS cir.:** Beam screen circulator
- TS:** thermal shield
- IC:** image current
- SR:** synchrotron radiation



## Electrical consumption for FCC-ee





Substantial progress in various domains.


Next important steps:

- Cryoplant studies by industrial partners (Air Liquide & Linde)
- Beam-screen transient → local and global controls strategy
- Quench discharge and recovery (impact on CM design pressure and # of quench valves)
- Distribution system (heat inleaks, INVAR option)
- Freezing of magnet operating temperature

# S. Klöppel: Cryogenics refrigeration with Ne-He mixtures for FCC beam screens


High cooling power needed for beam screen and thermal shield (new for accelerators).  
 Special effort needed to develop an efficient and flexible cycle 300 – 40 K.

Conventional He cycle  
Screw compressor



≈30 % of Carnot efficiency  
 → 13 MW input power

Alternative Ne He cycle  
Turbo compressor



≈45 % of Carnot efficiency  
 → 8.7 MW input power

Required pressure ratios in the cycles: ≈ 7

Achievable pressure ratios per stage:

Pure He: 1.05 → 39 stages

Pure Ne: 1.27 → 8 stages, but large HXs


Compromise:

20 mol-% Ne + 80 mol-% He,

Pressure ratio per stage: 1.1 → 20 stages

# S. Klöppel: Cryogenics refrigeration with Ne-He mixtures for FCC beam screens


## Design for 20 % neon



Compressor: 19 stages



## Design for 40 % neon



Compressor: 12 stages



Optimal system is defined by lowest cost

CAPEX:

Compressor  
HX  
Coldbox

OPEX:


Input Power  
Neon losses

Next steps: develop model, optimise cost of compressor, heat exchanger and refrigerant.



No pre-cooling  
& 7 expanders

Pelec. ~6.45 MW




- Autonomous
- Less efficient ?

LN2 pre-cooling  
& 4 expanders

Pelec. ~6.0 MW + LN2

Pelec. ~6.2 MW




- Dependent of LN2 supply
- Selected when LN2 plant present on site (ITER)

Nelium pre-cooling  
& 4 expanders

Pelec. ~6.0 MW + Nelium

Pelec. ~6.3 MW



- Dependent of Ne-He plant


=> Process options to be evaluated with partners & major cryogenic industries (Air Liquide, Linde)

Studying different He cycle options to optimise efficiency (e.g. expanders vs. pre-cooling)

- Warm compression generates huge gas heating (**150 to 200 MW**) and requires large water cooled heat exchangers and cooling towers  
*Gas heating will be function of gas nature and compressor technology*



=> Heat Recovery System (in addition to HVAC system) to optimise global energy management on FCC site



Office building heating




City heating



Industry studies to be started in 2016.

## Sector cool-down and warm-up studies

### Magnet design and half-cell layout




$$M \cdot c_p(T^M) \cdot \frac{\partial T^M}{\partial t} = -\alpha \cdot (T^M - T^{He})$$




$$\frac{\partial h}{\partial t} + u \frac{\partial h}{\partial x} = \frac{1}{\rho A} \cdot \underbrace{\alpha \cdot (T^M - T^{He})}_Q$$

$T$  : Net rate of heat added to the fluid element  
 $P$  : Convective transport  
 $Q$  : Source term (heat exchange with the magnet)

- Numerical method: Finite-differences
- Materials: 70% Iron (Fe) and 30% Stainless steel 316 (SS16)
- Maximum thermal gradient: 50 K (over the magnet length)



Half-cell cool-down times 300 – 40 K.



## Sector cool-down and warm-up studies

Cool-down and warm-up timescales are comparable to those of the (LHC).

	FCC	LHC <sup>1</sup>
<b>Cool-down:</b> 300 - 4.5 K	10.9 days	11.0 days
<b>Warm-up:</b> 4.5 - 300 K	12.0 days	9.5 days

1) L. Liu et al., "Numerical analysis of cooldown and warmup for the Large Hadron Collider", Cryogenics, Vol. 43-6, p. 359-367, 2003.

N<sub>2</sub> consumption  
(10 sectors):

44500 t = 5.89E7 litres  
(12 trucks/hr)


**5.7 x**




The Globe of Science and Innovation  
Geneva

The temperature gradients over the half-cell length comply with the established requirements (50 K).

## Steel



## Invar



	T	$Q_{\text{STEEL}}$ 20 bar	$Q_{\text{STEEL}}$ 50 bar	$Q_{\text{INVAR}}$
	K	W	W	W
DN80	4.6	4.57	4.59	4.01
DN200	40	3.22	3.66	2.75
DN240 F	40	3.48	4.92	2.99
DN240 R	60	145.6	157.5	109.9
DN250	4	6.8	7.44	4.98



## P. Duda: Impact of high design pressures of the cryogenic transfer lines on heat inleaks

Invar	Stainless steel
<ul style="list-style-type: none"><li>• Less types and numbers of supports</li><li>• Lower heat fluxes</li><li>• No compensation bellows</li><li>• Lower numbers of welds</li><li>• Lower forces on the vacuum barriers</li><li>• Lower probability of failure</li></ul>	<ul style="list-style-type: none"><li>• Conventional design</li><li>• Well-known welding method</li><li>• Pipes commonly available</li></ul>

Using Invar process pipes seems to be a very attractive alternative for FCC.

Thursday, 13:30-15:00

## **Implementation, Electricity, Cooling and Ventilation** – chair: Philippe Lebrun


- FCC civil engineering – tunnel optimisation (Charles Cook)
- Large scale metrology for the FCC work package (Mark Jones)
- Design considerations for the FCC electrical network architecture (Davide Bozzini)
- FCC electrical power requirements –
- methodology for data collection and geographical mapping (Maria Mylona)
- Cooling plants and ventilation systems (Mauro Nonis)




## For the time being advancing with the 100 km 'Intersecting' option.

Choose alignment option  
  
 Tunnel elevation at centre: 261mASL  
 Grad. Params  
 Azimuth (°): -20  
 Slope Angle x-x(%): 0.65  
 Slope Angle y-y(%): 0  
    
 Alignment centre  
 X: 2499731 Y: 1108403

	Angle	CP 1 Depth	Angle	CP 2 Depth
LHC	-64°	220m	64°	172m
SPS		242m		241m
TI2		235m		241m
TI8		242m		170m



Point	Actual	Shaft Depth (m)			Geology (m)		
		Molasse SA	Wildflysch	Quaternary	Molasse	Urgonian	Calcaire
A	304	0	0	12	213	0	79
B	266	0	0	80	156	0	30
C	257	0	0	58	199	0	0
D	272	52	0	40	181	0	0
E	132	0	0	64	68	0	0
F	392	0	0	40	296	0	56
G	354	0	0	116	237	0	0
H	268	0	0	0	268	0	0
I	170	0	0	12	158	0	0
J	315	0	0	22	293	0	0
K	221	0	0	52	169	0	0
L	260	0	0	21	239	0	0
<b>Total</b>	<b>3211</b>	<b>52</b>	<b>0</b>	<b>517</b>	<b>2478</b>	<b>0</b>	<b>109</b>




- Limestone region: **Jura**
- Max overburden: **650 m**
- Deepest shaft: **392 m**
- % of tunnel in limestone: **13.5 %**
- Total shaft depths: **3211 m**

- ### Challenges:
- 7.8 km tunnelling through Jura limestone
  - Up to 300 - 400 m deep shafts + caverns in molasse



## Future steps

- Official FCC Naming Convention
- CE Environmental Impact Assessment
- First order cost estimates
- First full (high-level) schedule forecast
- Update & development of tunnel cross-sections
- Single vs. double tunnel cost & schedule (ongoing)
- Study of surface building requirements
- Experiment gantry crane study (with MDI WG)
- Closer look at cavern construction




Different activities (geodesy, data management/processing, accelerator alignment, sensors for permanent monitoring of critical components, as-built surveys (laser scanning)).

Specifications needed (relative precision, global requirements to be broken down into: manufacturing, component assembly, final alignment, ...).

Access restrictions (radiation hazard, magnetic fields, space limits).

CERN coordinate system vs. connection to CH / F / global reference frame (some parameters to be modified)






Geoid model – some inconsistencies



New model needed, combining CH and F data

Analyses underway, with support from „swisstopo“.

Looking for input from IGN and some universities.



Looking into space reserved for survey, and methods how to bring down the reference system.



Continuing to work on: geoid model, geodetic network simulations, instruments + math. models



**Specifications needed** for FCC-hh, FCC-ee, transfer lines, experiments.  
 These will define alignment, monitoring  
 and control system technology (could imply R&D).






# D. Bozzini: Design considerations for the FCC electrical network architecture


Studying supply of neighbouring FCC points from 3 400 kV feeds, in normal + degraded mode. Based on first input from system designers (target values: FCC-hh 500 MW, FCC-ee 400 MW)



400 kV sources and distribution powerlines loads



400 kV sources and power lines loads



# D. Bozzini: Design considerations for the FCC electrical network architecture





Present conceptual design foresees overhead line from nearest 400 kV point and underground distribution (study case 132 kV; to be refined).

Cross bonding required to limit sheath induced longitudinal voltages and currents circulating in sheath.

Maximum transportable length of cable will determine # of pits for cable joints and cross bonding (ca 500-800 m).

Distribution network to be integrated into cross section.

Dimensioning depends on system requirements and capability to run in degraded mode.



who

when

where


how





Operating cycle

Power location (mapping)

Classification (network, voltage)



Method being set up. **Data needed** from users for various phases and different machines.



# Cooling and ventilation plants



FCC-hh: heat loads cooling circuits [MW]

MW	L-A	As	Au	A-B	Bs	Bu	B-C	Cs	Cu	C-D	Ds	Du	E-D	Es	Eu	E-F
Cryo	20	1.3	2.1	1.5	2.1	2.1	4.1	2.6						4.1	2.6	
RF																
Exper	7.3	2		10.5	2.7											
Gen services	2			2												
Magnets			0.5													
Pow converters	0.1			0.1												
Chilled water	3			5.4												
Total	12.4	2	0.5	38	4											
<b>Total point</b>	<b>14.4</b>			<b>43</b>												


POINT A	Power kW	$\Delta T$ K	Q m <sup>3</sup> /h	ND mm	H bar
Primary	43,000	15	2,470	550	1.2
Primary (shaft)	3,700	15	213	200	2.0
Cryogenics S	20,000	15	1,149	400	1.3
Experiments S	10,500	15	603	300	1.6
Gen services	2,000	15	115	150	2.7
Chilled water	5,400	6	775	350	1.4
Power converters	100	15	6	50	1.7
Cryogenics U	1,300	15	75	125	1.4
Tunnel circuit L-A	500	15	29	125	4.6
Tunnel circuit A-B	500	15	29	125	4.6
Experiments U	2,700	15	155	150	2.2
make up water (5%)			124	150	1.0

## Cooling plant layout






## Primary water supply



## Various constraints from topology

- Depth
- Sector length
- Altitude variation







# Cooling and ventilation plants

Ventilation system at combined collimator/dump points D, J

Ventilation of the Dump Area



Ventilation of the Collimation Area

Ventilation of the UAs

Ventilation of the Tunnel Machine Area

Ventilation Emergency Extraction

Pressurisation of Shaft Lift(s) and Stairs

Ventilation of the Tunnel Safe Zone

General architecture exists – details to refine.  
 Mainly existing industrial solutions.  
 Recycling of machine air.  
 To come: environmental impact, overall efficiency, valorisation of waste heat, ...

Thursday, 15:30-17:00

## **Safety, Availability, Controls** – chair: Ralf Trant

FCC collaboration “Fire safety” (Saverio La Mendola)

Conventional safety (André Henriques)

Radiation protection (Markus Widorski)

First results from availability studies (Andrea Apollonia)

Controls architecture challenges for beam dump kickers (Pieter van Trappen)

Starting from ITSF (International Technical Safety Forum).  
Realising that same issues get explored (smoke propagation, evacuation, air management, ...).



On initiative of ESS and CERN

## Workshop on Fire Protection at Research Facilities

21-22 January 2015  
Tunavägen 24  
Europe/Stockholm timezone

Lund January 2015


Main topic	Sub-topic
Hazard characterization	Burning behavior of commonly present items
	Fire simulations
	Oxygen Deficiency Hazard
	Flammable gases
Passive fire protection	
Active fire protection systems	Fire detection
	Fire extinction
	Smoke extraction and ventilation
Intervention of rescue teams	
Life safety in underground facilities	Evacuation of occupants
Fire risk methodologies and tools	Collection, analysis and use of statistics
	RAMS aspects

FCC as framework for more direct  
(thus effective) collaboration  
between labs → synergy.


Consistency of assumptions and  
tools is key for reliable results.



Welcoming additional partners.



Fire protection workshop at CERN October 2015



Presenting first results at next ITSF

## International Technical Safety Forum 2016

9-13 May 2016, DESY, Hamburg


Topics: Lessons learned, Risk assessment, Laser safety, Continuous improvement in HSE matters, New Projects and challenges, Equipment certification, Sustainability, Communications, Nanoparticles, Incident/accident management

International Committees:  
 A. Hoppo (DESY), S. Kostelak (XFEL), E. Cennini (CERN), A. Trudel (TRIUMF), P. Jacobsson (ESS), B. Marszalek (JLAB), J. Anderson (FERMILAB), J. Kenny (SLAC)

<http://tsf2016.desy.de>

## General safety studies + considerations for FCC

Smoke propagation studies ongoing ...  
(standard arc)



... leading to indications about the maximum distance between connections between the machine area and the „safe zone“ (single or double tunnel).

Ventilation speed [m/s]	Maximum distance (mean value Monte Carlo sim.) [km]*
1	2.0
1.5	0.73
2	0.61

\*preliminary results

1 km baseline value validated  
Optimisation once ventilation speed is fixed

## General safety studies + considerations for FCC

Other studies, with concrete recommendations coming up:

General points on safe zone

- Minimum fire risk/load

Evacuation modeling

- Smoke compartmentalisation, personnel transport means along 10 km arc, alarms, ...

# of shafts + lifts

- 1 shaft per point is acceptable, at least 2 lifts, lift time = LHC, protected area at bottom

Air management

- Overpressurised safe zone (resp. pressurised airlock between double tunnel)

He release + extraction during access mode

- Smoke extraction system to cope with 1 kg/s He. Temperature vs mech. properties.

Connections experimental/service caverns

- Zoning, flow of people/material. Access to service caverns with beam on.

Magnetic field in experimental caverns

- Hazards mainly of technical nature.

Verification and optimisation to continue with definitive values, e.g. of ventilation speed, number of people present during different phases (installation, operation, ...), electrical network, cryogenic system, ...



# Radiation protection at FCC-hh – status update

Assessment of ventilation of machine tunnel and safe zone.

Proposal for „recycling“ machine air in line with RP requirements.

Air in safe zone needs to be flushed before access (single tunnel variant).

Double (bypass) tunnel needed in collimator/beam dump regions (2 x 4.2 km) and focusing regions (8 x 1 km)

# of connection tunnels per high-radiation point (4.2 km): ca 5-7 → ca every 500 m.


Optimisation when collimator layout and loss distribution are known.

Bypass to join (near) the service cavern.

Ca 1-2 connections in focusing regions.




No dead ends.

Top view



Layout and zoning at experimental points (from RP point of view)


Side view



# Radiation protection at FCC-hh – status update


Studies for experimental caverns/shafts.

FCChh Ultimate collisions



Massive 2 m iron shielding around forward detector → still under study

Forward detector





Higher dose rate in horizontal plane gives recommend's for layout of access paths.

No RP issues at top of experimental shafts, neither for ultimate operation nor full beam loss. Residual dose rates after operation being investigated (forward detector).

Next: refinement as design proceeds, FCC-ee evaluation, HTS beam screen coating material (?).



Important to address from the outset (and further throughout whole accelerator lifetime), to maximise performance within technological and financial boundaries.



### Scope:

- Evaluate suitability of industrial availability methods to particle accelerators.
- Identify and analyse possible design and operation scenarios for FCC-hh.
- Identify key impact factors for availability and luminosity production.



### Not:

- Specific guidelines for individual system designs.

## Conclusions & Outlook

- ❑ Estimates of the **achievable availability** of the FCC-hh will be one of the main factors for the assessment of its **feasibility**
- ❑ LHC Availability model implemented (better than 1 % acc.), ready for extrapolation to FCC
- ❑ Future studies should focus on:
  - ❑ Definition of a FCC **cycle duration** (also influencing system design)
  - ❑ Analysis of different **injector options** (also influencing cycle duration)
  - ❑ Identify strategy for **scaling** number of components (e.g. number of power converters, redundancy in cryogenic system,...)
  - ❑ **Data quality** management (RAMS Database)
- ❑ Possibility: extend the study to the FCC-ee?
  - ❑ Requires expertise (and data) on lepton machines

In LHC LBDS is already a mission-critical system with specific design features (kicker granularity, redundant HV switches, redundant trigger paths, avoidance of common-mode failures, ...).



FCC (8 GJ beam energy, distances/access, performance demand) requires another approach:

- Perform **qualitative reliability analysis** for each part from the design phase on.
- Implement **system redundancy**: hot swappable HV pulse generators.
- Apply **Triple Modular Redundancy (TMR)** to critical parts.
- Accept operation in **degraded mode** where non-critical redundant paths are lost.
- Meticulously plan **preventive maintenance** during Technical Stops by leveraging advanced data monitoring.

**RAMS**  
aspects  
from the  
outset

FBDS plans to use 300 extraction kickers of ca. 30 cm (+ dilution kickers).

Need to fit HV generators and switches, controls electronics, ... in these 100 m.

More custom-made electronics (yet allowing design re-use); rad-hardness to be „designed in“.  
Minature controllers, decentralisation, less cables and connections, combined HW/SW (SoC).

Investigating to place the HV generator and controls close to the beam  
to shorten the transmission line and reduce field rise time  
(depends on dose and SEE rate).

Triggering and retriggering

Looking whether delayed synchronous dump is possible when 1/300 kickers fires erratically.  
(several about gaps of 1 us ?).

Laser-pumped thyristor triggering ?

Huge amount of channels to supervise, waveforms to check to make sure that next dump is OK.  
LHC: post-operational checks. FCC: Artificial Intelligence (?)



# Concluding remarks

Huge amount of activity going on – „IO train running at full steam“.

Concepts for several systems elaborated, using approximate data and estimates  
(civil engineering, cryogenics, electrical distribution, cooling & ventilation, ...).

Machine(s) requirements are needed to narrow down, become more specific and quantitative,  
resp. know about need for R&D efforts (survey, ...).

New level of challenges – for full exploitation FCC cannot just be extrapolation of LHC „methods“.

Use momentum and develop new methods – some of them mentioned at this workshop  
(superconducting power transmission, laser alignment, possibility to run  
in degraded mode, AI for data mining, high degree of automatisisation, ...).

Such developments can have useful spin-off also for other applications.

Great occasion for (further) collaborations.

Grazie per l'attenzione !



[www.cern.ch](http://www.cern.ch)