



Present Status of SRF Technology for the ILC

Akira Yamamoto
(KEK and CERN)

1. Progress highlighted
2. Prospect for realizing the ILC



Outline

1. SRF Progress highlighted


- Progress in cavity gradient
- RF Input-Coupler with new ceramic window
- Marx Generator for RF Power Supply

2. Prospect for realizing the ILC


- SRF Cavity development
 - “Global (SRF) Cryomodule” proposal
-




ILC Acc. Design Overview (in TDR)



Physics Detectors



Key Technologies



Item	Parameters
C.M. Energy	500 GeV
Length	31 km
Luminosity	$1.8 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$
Repetition	5 Hz
Beam Pulse Period	0.73 ms
Beam Current	5.8 mA (in pulse)
Beam size (γ) at FF	5.9 nm
SRF Cavity G.	31.5 MV/m
Q_0	$Q_0 = 1 \times 10^{10}$

Progress in SRF Technology in TDR and after

Global Progress in TDR (~ 2013)

- **SRF cavity gradient:**
 - G-max = **37 MV/m** and an Yield of **94 %** at **> 28 MV/m**
- **SRF beam acceleration:**
 - Beam current: **9 mA** (at **DESY-FLASH**)
 - Pulse duration: **1 ms** (**KEK-STF**)

Regional Progress (~ 2015) :

- **European XFEL:**
 - SRF Cavity production **100%** (of 800) , with G= ~ **30 MV/m** (av).
 - Cryomodule (CM) assembly, > 70% (of 100) completing
- **Fermilab** : CM reached the **ILC gradient** specification of **> 31.5MV/m** (av.)
- **KEK**: A full CM (8) + a half-CM (4) in preparation for beam acceleration
 - CM (8-string) aiming beam acceleration at **> 31.5 MV/m** (av).



Major Accelerators Under Construction

2010 ~ 2020

Project	Notes	# cavities	year
CEBAF-JLAB (US)	Upgrade 6.5 GeV => 12 GeV electrons	80	
XFEL-Hamburg (EU)	18 GeV e – for Xray Free Electron Laser	840	~ 2015
LCLS-II – SLAC (US)	4 GeV electrons –CW XFEL	300	~ 2019
SPIRAL-II (France)	30 MeV, 5 mA protons -> Heavy Ion	28	
FRIB – MSU (US)	500 kW, heavy ion beams	340	
ESS (Sweden)	1 – 2 GeV, 5 MW n-Source ESS - pulsed	150	
PIP-II–Fnl (US)	High Intensity p-Linac for Neutrino Beams	115	
ADS- (China, India)	R&D for accelerator drive system	> 200	
Global sum		> 2000	



European XFEL Progressing

Progress:


2013: Construction started
2015: SRF cav. (100%) completed
 CM (70%) progressed

Further Plan:


2016: E-XFEL acc. completion
2017: XFEL beam to start

Acc. : $\sim 1/10$ scale to ILC-ML's
 SRF system: $\sim 1/20$ to ILC SRF's

1.3 GHz / 23.6 MV/m
808 SRF acc. Cavities
101 Cryo-Modules (CM)



E-XFEL: SRF Cavity Performance (as received)




	G-usable ($Q_0 > 10^{10}$)	G-max	(ILC)
<G> MV/m	29.4	33	(35)
Yield at 28MV/m	66%	86%	(90%)

SRF cavity production/test ;

- # RI Cavities, **373** (as of Sept. 2015)
- Final process: 40 μm EP.
- The same recipe to ILC-SRF
- Tested at DESY-AMTF


Notes::

- “Ultra-pure water rinsing as the 2nd process improving the gradient performance (~10%) for lower-performed cavities (not shown here).





Cryomodule Performance : XM59



XM59 is an excellent module, assembled after the change of CR procedure.

Fermilab : CM2 reached $<31.5 \text{ MV/m} >$

CERN Courier December 2014


ACCELERATORS

ILC-type cryomodule makes the grade

For the first time, the gradient specification of the International Linear Collider (ILC)

design study of 31.5 MV/m has been achieved on average across an entire ILC-type cryomodule made of ILC-grade cavities. A team at Fermilab reached the milestone in early October. The cryomodule, called CM2, was developed to advance superconducting radio-frequency technology and infrastructure at laboratories in the Americas

region, and was assembled and installed at Fermilab after initial vertical testing of the cavities at Jefferson Lab. The milestone – an achievement for scientists at Fermilab, Jefferson Lab, and their domestic and international partners in superconducting radio-frequency (SRF) technologies – has been nearly a decade in the making, from



Cavity	Gradient (MV/m)
1	31.9
2	30.8
3	31.8
4	31.7
5	31.5
6	31.3
7	31.6
8	31.4

Cryomodule test at Fermilab reached $<31.5 >$ MV/m, exceeding ILC specification

KEK-STF: Cavity Performance after CM Assembly



Beam Acceleration w/ 8 cavity string in JFY2016

SRF cavity performance before/after CM Assembly

Module	CM1a				CM1b				CM2a			
Cav. #	1	2	3	4	5	6	7	8	9	10	11	12
空洞単体 [MV/m]	37	36	38	36	37	35	39	36	12	36	32	32
CM内 (pulse) [MV/m]	39	37	35	36	26	1 6	26	32	18	34	33	32
	Gradient stable				Degraded				Gradient stable			


FY14: CM1+CM2a (8+4) assembly
 FY15: Cavity individually tested in CM RF power system in preparation
 FY16: 8-cavity string to be RF tested
 Beam Acceleration (w/ a goal to reach > 250 MeV)

*Gradient(av) w/ 12 cavities: ~ 31 MV /m
 Gradient (av) w/ best 8 cavities: ~ 35 MV/m





ILC SRF ML Parameters




1.3 GHz Nb 9-cell Cavities	16,024
Cryomodules	1,855
SC quadrupole pkg	673
10 MW MB Klystrons & modulators	436/378 *

* site dependent




A Possibility for the cost effective ILC Cavity Integration




Longitudinal interconnect constraint for the ILC and EFXEL cavity string




RF-Power Coupler Development w/ low-SEE coefficient ceramic window



TTF-III/E-XFEL Coupler w/ bellows





New, KEK-STF Coupler w/o bellows




Plug-compatible, cold-interface

	STF-40-A	STF-40-B*
Cold end-flange	40 mm	40 mm
Ceramic window	A479	AH100A
SEE coefficient	11.2	4.6
Coating	yes	no
Conditioning time	86 hrs	In progress



* CERN-KEK Cooperation





High-Level RF System for ILC

Accelerator Laboratory



**Pulse Power Supply
(Marx Modulator)**
→ 378 units
for 39 cavities / unit


Klystron

©Rey.Hori/KEK




Marx Circuit Concept

- Classic Marx circuit (1923 invented by Erwin Marx)



- Charge in Parallel
- Discharge in series
- $V_{\text{out}} = n V_{\text{in}}$


- Solid state Marx circuit (2000, by A. Krasnykh)




Marx
Generator
digitized



KEK ILC Modulator Development



- Marx Topology and Design Concept :
 - Charge in parallel, discharge in series
- Specification:
 - 120 kV, 140 A, 1.7 ms, 5 Hz
- Modules:
 - 6.4 kV pulse output with Marx circuit
 - Cell having a step-down chopper circuit with a switching frequency of 50 kHz
- Design Considerations:
 - Modular design with high availability
 - N+1 Redundancy
 - Cost effective
 - Components and modular design
 - Easy maintenance
 - Oil-free design
 - Compact
 - No output transformer





Outline

1. SRF Progress highlighted

- Progress in cavity gradient
- RF Input-Coupler with new ceramic window
- Marx Generator for RF Power Supply


2. **Prospect** for realizing the ILC

- SRF Cavity development
 - “Global (SRF) Cryomodule” proposal
-






Further Technical Issues to prepare for the ILC

The. Field	Subject	Global Cooperation
ADI	Optimize Acc. Design and Integration	LCC-ILC-ADI Global Team
SRF	Improve Gradient and Stability Establish three regional contribution <ul style="list-style-type: none">- Industrialization- Hub-lab functioning	TTC: TESLA Tech. Collaboration: Three regional effort and experience <ul style="list-style-type: none">- EU: European XFEL- AMs: LCLS-II- AS: KEK-STF as Asian Hub.
Nano-beam	Realize ultra-low emittance (in DR), and nano-beam size and stability at FF	ATF: Acc. Test Facility Collab: - Global collaboration with KEK-centered




SRF Cavity development anticipated

- **High Gradient**
 - Ingot sliced Nb for high-gradient cavities
 - Advantage: Cleanest Nb surface
 - Subject to be settled: mechanical stability
 - Possible solution : direct slicing medium-grain ingot
- **High Q**
 - Lowering operational temperature (2.0 → 1.8 K)
 - Saving AC power in balance
 - N2 doping and other surface treatment
 - Future subject to be investigated even for high gradient
 - Referring work originated at Fermilab





SRF Facilities anticipated for Hub/Consortiums



AMTF @ DESY, E-XFEL @ CEA,

STF @ KEK

ASTA @ FNAL, TEDF @ JLab



A proposal: “Global SRF Cryomodule ” Program



Objectives:

Establish system-engineering to realize **Global Cryomodules** (globally compatible cryomodule) including:

- **Industrial** technology, with optimum **plug-compatibility**/standardization,
- **Safety** regulation (such as “high-pressure-code”) with inter-regionally compatible authorization,
- **Gradient** performance reproducibility **after inter-regional transportation.**

Global Cooperation:


EU (AM) contributes a **full cryomodule** including manufacturing and performance test,

EU (AM), and **JP** work together for **inter-regional transportation** and safety regulations to be compatibly authorized,

JP contributes to the cryomodule performance test **and** to **reproduce the performance,**

Time-line:

The program to be realized **in the ILC main preparation phase of 4 years, and the preparation should start soon,** to negotiate with legal authorities and to learn E-XFEL CM qualification process,






Summary

- International Linear Collider (**ILC**) is an energy frontier **e+e- colliding** accelerator to reach **500 GeV** extendable to 1 TeV.
- The SRF technology well **globally demonstrated and matured**, specially by European XFEL, functioning prototype works.
- **ILC SRF technology** to be further advanced for reliable and cost-effective.





Progress/Prospect in SRF Cavity Gradient for Frontier Particle Accelerators






Progress in SRF Cavity Production Yield during ILC – Technical Design Stage

2nd pass yield - established vendors, standard process

◆ >28 MV/m yield ■ >35 MV/m yield



Production yield:
94 % at > 35+/-20%

Average gradient:
37.1 MV/m
> R&D goal of 35 MV/m

reached (2012)



Material Design Concept

Purpose

High Resistance for
Creeping Discharge

Discharge Effecting Factor

Electron Multiplication

Material Approach

Low Secondary Electron
Emission Coefficient(SEEC)

Status for Material

Low SEE


SEEC: 11.2
 $10^{14}\Omega \cdot \text{cm}$
99% Alumina
KYOCERA A479

SEEC: 4.6
 $10^{14}\Omega \cdot \text{cm}$
New Alumina
KYOCERA AH100A





On a commercial
basis

Introduction of AH100A




ILC SCRF Cavity Plug-compatible Conditions discussed in the Technical Design Phase



Item	Varieties	Baselines in ILC-TDR
Cavity shape	TESLA / LL	TESLA
Length		Fixed
Beam pipe flange		Fixed
Suspension pitch		Fixed
Tuner	Blade/ Slide-Jack	Blade
Coupler flange (cold end)	40 (60 at KEK)	40 mm
Coupler pitch		Fixed
He –in-line joint		Fixed



SCRF Procurement/Manufacturing Model



ILC Host-Lab

Technical Coordination
for Lab-Consortium

Regional
Hub-Lab:
A

Regional
Hub-Lab:
E, & ...

World-wide
Industry responsible to
'Build-to-Print'
manufacturing


Regional
Hub-Lab:
B

Regional
Hub-Lab:
D

Regional Hub-Lab:
C: **responsible to
Hosting System Test
and Gradient
Performance**

Regional hub-laboratories responsible to regional procurements to be open for any world-wide industry participation

: Technical coordination link
: Procurement link





KEK-STF: Cavity Performance after CM Assembly



Beam Acceleration w/ 8 cavity string in JFY2016

SRF cavity performance before/after CM Assembly

Module	CM1a				CM1b				CM2a			
Cav. #	1	2	3	4	5	6	7	8	9	10	11	12
空洞単体 [MV/m]	37	36	38	36	37	35	39	36	12	36	32	32
CM内 (pulse) [MV/m]	39	37	35	36	26	1 6	26	32	18	34	33	32
	Gradient stable				Degraded				Gradient stable			

FY14: CM1+CM2a (8+4) assembly
 FY15: Cavity individually tested in CM RF power system in preparation
 FY16: 8-cavity string to be RF tested
 Beam Acceleration
 (w/ a goal to reach > 250 MeV)

*Gradient(av) w/ 12 cavities: ~ 31 MV / m
 Gradient (av) w/ best 8 cavities: ~ 35 MV/m





Technical Issues to be settled during the ILC Preparation Phase

Table 2. Technical issues to be settled during the ILC accelerator preparation phase

	Pre-preparation Phase	Main Preparation Phase			
	Present	P1	P2	P3	P4
ADI	Establish main parameters	Verify parameters w/ simulations			
SRF	Accelerate beam with SRF cavity string and cryomodule	Demonstrate mass-production technology and stability Demonstrate Hub-lab functioning and global sharing			
Nanobeam	Achieve the ILC beam-size goal	Demonstrate the nanobeam size and stabilize the beam position			
Positron source	Demonstrate technological feasibility	Demonstrate both the undulator and e-driven e+ sources			
CFS	Pre-survey and basic design	Geology survey, engineering design, specification, and drawings			
Common technical support	Support engineering and safety	Common engineering supports (network, radiation safety, etc.)			
Administration	Project planning and promotion Preparation for the ILC pre-lab	General affairs, finance, international relations, public relations Establishing the ILC pre-lab and managing the ILC preparation			

Global Cryomodule Program

