





Overview of the ToF400 BM@N

M. Rumiantcev on behalf of the BM@N collaboration
Veksler and Baldin Laboratory of High Energy Physics
Joint Institute for Nuclear Research


BM@N beam line from the Nuclotron

26 elements of magnetic optics:
→ 8 dipole magnets
→ 18 quadruple lenses






~ 160 m
Building 205

Main systems of the BM@N setup



Preliminary ToF-400 design




ToF-400 walls on the mounting frame




20 detectors (48 strips)
 24 x 48 = 960 strips (300x12.5 mm²)
 960 x 2 = 1920 electronics channels

Simulation for the ToF-400 (by S. Lobastov)

h_4XvsY_Rate kHz/cm^2





LAQGSM, central, 3.36 GeV, Au+Au, π^\pm , 4 m from the target




Estimated occupancy for central 3.36 GeV/u Au-Au

MRPC for the ToF-400 (Dubna)




- Glass – 280 μm
- Gap width – 200 μm
- Number of gaps – 15
- Active area – 300*600 mm^2
- Strip size – 10*600 mm^2 , pitch 12.5 mm
- Strip impedance – 50 Ohm
- 24 strips, 48 ch FFE.




24 channels, base NINO FEE



TDC72VHL: 72 channel, 25 ps TDC





Beam test prototypes of MRPC






Two prototypes of MRPC were tested on deuteron beam of Nuclotron (JINR). Two MWPC station for tracking. Prototype T0 (FFD) for MPD are used like start detector.

Efficiency > 95%
Time Resolution < 50 ps







BM&N setup in the first technical run in February-March 2015



Tasks for BM@N technical run:

- deuteron and C^{12} beams with $T_0 = 3.5$ AGeV
- Trace beams, measure beam profile and time structure
- Test detector response: ToF-400, ToF-700, T0+Trigger, DCH-1,2, ZDC, ECAL modules, Beam monitors BM
- Test integrated DAQ and trigger system



- Time resolution of TOF-700 chamber $\sim 60 \text{ ps}$
- Time resolution of ToF-400 chamber $\sim 50 \text{ ps}$
- Time resolution of ToF-400, ToF-700 relative to start CD detector (T₀) $\rightarrow \sim 140 \text{ ps}$ (d)




HV system with remote control by Ethernet will be ready to 2016.

LV system is under construction.

We have two ways to realize it:

- “Mpod” system by W-IE-NE-R or “Mainframes” system by CAEN. Expensive way.
- Hand made system by industrially available solutions (for example Mean Well DR-4505 DIN). Chip way.

HV power supply designed by HVSys is under manufacturing



	For first run in 2015	In the future
Total volume	40 liters	400 liters
Gas mixture	C2H2F4, i-C4H10, SF6 (90%/5%/5%)	
Volume exchange/day	3.5	4
Total flow rate	6 l/hour	67 l/hour
Reflow system	No	Yes
Working pressure	<3 mbar	
Status	Ready	Under construction

Conclusions

- The construction of mRPC detectors and design of TOF400 wall are fixed.
- The first technical run is performed in February-March 2015 with aim to trace beam, test detector response, trigger and integrated DAQ system.
- Discussion on the choice of the LV system continues. Young engineers welcome!
- Reflow Gas system is under construction. Young engineers welcome!
- Design of gas box is under construction. Young engineers welcome!
- Research of limit time resolution of MRPC, construction High Rate MRPC. Young scientist welcome!

Thank you for attention!

