


High Efficiency Klystron (HEKCW) for FCC info/status


I. Syratchev

The new bunching technology has a potential to boost klystron efficiency to the 90% level.




"Classical" bunching




Bunch velocities distributions prior entering the output cavity



Bunching with core oscillations



The first conceptual/ technological S-band MBK prototype is now being built in Russia.



PPM, 52 kV, 7MW, Duty cycle 0.002, Eff. >70% (to be demonstrated)

FCC e^+e^- CW, MBK klystron (HEKCW)

HEIKA/HEKCW working team:



- I. Syrathev (CERN)
- II. G. Burt (Lancaster)
- III. C. Lingwood (Lancaster)
- IV. D. Constable (Lancaster)
- V. V. Hill (Lancaster)
- VI. R. Marchesin (Thales)
- VII. Q. Vuillemin (Thales/CERN)
- VIII. A. Baikov (MUFA)
- IX. I. Guzilov (VDBT)
- X. C. Marrelli (ESS)
- XI. R. Kowalczyk (L-3com)

Tube parameters:

- Voltage: 40 kV
- Power: 1.5 MW
- Total current: 42A
- N beams: 16
- $\mu\text{K}/\text{beam}$: 0.33
- N cavities: 7
- Bunching methods COM/BAC
- Cathode loading: 2 A/cm²
- Beam radius: 3 mm
 - Filling factor 8 mm
- Length: 2.3 m
- Beam circle radius: 75 mm
- Solenoid field (2x): 600 G
- Solenoid radius: 150 mm
- Collector: common
 - Nominal load: 170 kW




16 beams MBK cavity
R/Q = 22 Ohm/beam




HEKCW RF COM circuit optimisation

Few tubes were optimised using **KlypWin** (1D code). Two of them were selected for further study.

HEKCW #11-02 (highest efficiency) $\eta = 90.1\%$




HEKCW #11-07 ('cleanest' phase trajectories) $\eta = 89.2\%$




High efficiency confirmed by another non-commercial 1D code **AJDisk**





$\eta = 88.0\%$







$\eta = 87.5\%$



NRL/SAIC TESLA (2.5D). Tube is slightly re-tuned (stability issues). Efficiency 80%.



MAGIC (2.5D). Tube is shortened (6 gaps) (reflected electrons issues). Efficiency 78%. (yet in a progress)



Remarks: Drive F = 0.80000 GHZ, Power in 30.00 W	Author: D.A. Constable Lancaster University Device: 800 MHz High Efficiency File: 17-01 30 00Watts.m2d
MAGIC2D,Double Version: 6.57, December 2003 Date: Oct 13,2015 Time: 15:47	Page: 912

HEKCW 'preparatory' activities. ~Needs and ~schedules.

1. Computer simulations (1D, 2D, 3D). Development/improving of the klystron circuit (COM/BAC/new methods) and exploring the new ideas (electron beam mixing technique, hollow beams etc.).

-Target: robust MBK klystron design with efficiency above 80%.

- Resources:

CERN: I. Syratchev, Q. Vuillemin (PhD. CERN/Thales)

Others: HEIKA team contribution.

- Needs: Dedicated computer facility (Lancaster U). Investment: computer cluster ~30 kCHF.

- Schedule: Ongoing activity (+ 3 years?)

2. HEKCW prototyping. GSP (scaled) tubes.

- Target: Inexpensive experimental demonstrators of the HEKCW concept(s) at a lower power (different frequency (3 GHz)). 3-4(+) tubes.

- Resources:

CERN: I. Syratchev, Fellow or equal (for testing).

Others: HEIKA team contribution

Industry (on the collaborative bases)

Needs: General purpose test stand (XBOX area (?)), LLRF/ 'flexible' modulator; app. 150 kCHF.

- Investment (industry): klystrons/(solenoid) fabrications; app. 200 kCHF. Total 350 kCHF.

- Schedule: Starts from ~mid. 2016. Two years program.

3. Alternative/advanced technologies:

- Other than klystron. IOT with extra bunching cavity(ies). The existing 0.53 GHz,10 kW tube (called Tristrod. Developer: “Kontakt”, Russia) operates routinely at 90% efficiency.
- Cathodes:
 - * Gated (low voltage controlled) cathode. Overall system efficiency improvement.
 - * Hollow beam cathodes (MIG, cold emission...). Reaching the ultimately high efficiency (90%).
- Resources, needs and schedules are not yet specified. For now covered by HEIKA.

Fabrication and testing of the final HEKCW prototype.

- The choice of final circuit configuration and computer detailed design. HEIKA team.
- Technical design of the klystron (including all subsystems). Industry.
- Efficiency demonstration (target: 85%) in pulsed mode. CERN/X(S)BOX modulators.

If accepted, could be started not before late 2017. Overall project duration is about 3 years (tests at 2021). Anticipating reduced NRE expenses in industry, the projected cost is 500 kCHF.