





Status and progress of the CTF3 probe beam



Probe beam LINAC for the TBTS





The CTF3 Facility



Inside the CLEX building





- CALIFES specifications:
- Energy : ~ 177 MeV
 - Energy dispersion : $\pm 2\%$
 - Emittance : $< 20 \pi$ mm.mrad
 - Bunch charge : 0.6 nC
 - Bunch train : 1 – 32 – 226
 - Bunch spacing : 0.667 ns
 - Bunch length : 0.75 ps
 - repetition rate : 5 Hz



Based on:



- Photo-injector (LAL Orsay)
- Laser line (using the same laser as for PHIN)
- 3 former LIL accelerating structures
- A single klystron RF 45 MW, RF distributed to the structures and the gun
- A complete set of diagnostics








- 1st period: beam to the end of Califes line but with dark current only.
- 2nd period: real beam arriving at the end of TBTS.
- 3rd period characterization and optimization of the beam, hand given to the TBTS team
- Next period: the goal is to achieve nominal performances...

Thanks to Jose Monteiro for planning




Beam was immediately seen at the gun output





- Dark Current with ~ 70 MV/m on the photocathode
(video gain is pushed at x 6.5, no filter)

- The beam with laser pulse train of 100 ns:
150 bunches - 0.073 nC per bunch – QE $\sim 1\%$
(video gain x 1 and optical filter inserted)




- Monday 8 Dec.: the laser driver failed after one month of regular operations.
- We decide to carry on with the dark current only, BPM electronics was adapted accordingly (27 dB amplifier and band-pass filter added).



Video gain x 8,
Beam diameter 1mm approx

Axis scales
not calibrated




Dipole current 28.4 A : 114 MeV
Energy dispersion : < 1%

Thanks to Alexandra
Andersson

This unusual commissioning gave confidence in the Califex operations and allowed a list of corrective actions to be established and completed before the next run, regarding : RF phase tuning, survey, diagnostics, C/C...


A lot of improvements conducted during the shut-down: phases between accelerating structures tuned, deflecting cavity connected, laser made reliable, RF network improved...




- Gun charge vs. phase scan
- Similar to the PHIN
- 0.2 nC/bunch, QE = 0.5%,
- Energy 5.7 MeV (evaluated with the DH/DV130 corrector)

Transmission vs. phase scan

Energy vs. phase scan




Bunch train max energy : 140 MeV (nominal 177 MeV)




170 keV < ΔE < 370 keV



Bunches are energy resolved – 7 ns train




3 ns train



12 ns train




First measure of emittance with quad scan :
 $\epsilon_{Nx} = 66 \mu\text{m}$, $\epsilon_{Ny} = 82 \mu\text{m}$ (specif. $< 20 \mu\text{m}$)



9th April 09: First beam at the end of the TBTS



Happiness in the control room



Poisson d'Avril for April's fools day



15th May 09: The conditioning of the deflecting cavity experiences too high reflected power (-13 dB). Eventually, we suspect an obstacle in the long waveguide line (~80 m) from MKS14 to the deflecting cavity. Reflectometric method allows to spot this waveguide.







Thanks to Gerry Mc Monagle for pictures and investigation

Object found inside: a device used in the brazing oven

- The laser system has been greatly improved (energy, beam size)
- Command control now allows to operate from the control room.
- Deflecting cavity is ready for bunch length measurement.
- Matlab





data analysis.






- Beam size $\sigma_x = 1.55 \text{ mm}$, $\sigma_y = 1.15 \text{ mm}$ with minimum of magnetic elements used.
- The SNG0250 solenoid was responsible of a significant vertical deviation.
- Nearly 100 % transmission and beam to the end of TBTS with a minimum of tuning every day.





POW-V	Status	CCV	AQ
CA. SNI0120	On	285.00	
PowDF7000	Mode	Control	CCV
CA. SNH0110	On	Remote	255.00
CA. SNG0230	On	Remote	135.00
CA. SNG0250	On	Remote	0.00
PowDF7000	Mode	Control	CCV
CA. QFD0350	Stand-By	Remote	80.80
CA. QDD0355	Stand-By	Remote	82.00
CA. QFD0360	Stand-By	Remote	80.80
PowDF7000	Mode	Control	CCV
CA. BHB0400	On	Remote	28.70
PowDF7000	Mode	Control	CCV
CA. DHG0130	On	Remote	1.60
CA. DHG0225	On	Remote	0.00
CA. DHB0230-S	On	Remote	0.00
CA. DHG0245	On	Remote	-0.50
CA. DHB0250	On	Remote	-1.10
CA. DHG0265	On	Remote	-2.80
CA. DHB0270	On	Remote	0.00
CA. DHG0320	On	Remote	0.00
CA. DHG0385	On	Remote	2.00
CA. DVG0130	On	Remote	0.00
CA. DVG0225	On	Remote	-1.20
CA. DVB0230-S	On	Remote	2.60
CA. DVG0245	On	Remote	2.00
CA. DVB0250	On	Remote	2.00
CA. DVG0265	On	Remote	3.10
CA. DVB0270	On	Remote	0.00
CA. DVG0320	On	Remote	0.00
CA. DVG0385	On	Remote	-4.00



- Max. energy reached 143 MeV at the end of the line.
- Pulse to pulse energy drift (beam loading or amplitude/phase shift during pulse train)





- At gun output, using corrector DV/DH 130 : about 5.2 MeV.
- Hor. and Vert. coupling due to gun solenoids fringe field



Volker Ziemann program


- Energy = 140 MeV
- $\mathcal{E}_{\text{norm. Hor}}$: 43.6 mm.mrad
- $\mathcal{E}_{\text{norm. Vert.}}$: 68.6 mm.mrad (spécif. < 20 mm.mrad).
- The Twiss parameters allowed to compute theoretical settings for the TBTS line and so to drive efficiently the beam up to the TBTS spectrometer.




- Calibration 0.94 mm per degree at 3 GHz (333 ps for 360 deg)
- Vert. beam size due to the deflecting cavity: 1.45mm
 ⇒ Bunch length 1.42 ps at 1 σ (spec. 0.75 ps)

Laser pulse duration: 7 ps ⇒ the velocity bunching works

Power phase shifter will allow to tune bunch length






Cavity OFF
 $\sigma_y = 0.24$ mm



Cavity ON
 $\sigma_y = 1.47$ mm


Thanks to Luca Timeo for deflecting cavity operations




- Laser has made huge progress (many thanks to the EN/STI/LP members for their continuous efforts and availability).

[see Massimo Petrarca talk on Th.15oct. 17.30]


- It's time to regenerate the CsTe photocathode (this week).




- Improve energy (and emittance) using more powerful RF compression laws.
- Improve charge and emittance with even more laser power/ UV conversion/transport efficiency and spot size.
- Improve bunch length or energy, tuning the bunching structure phase with the power phase shifter (to be installed soon).
- Improve reliability, C/C easiness, diagnostics accuracy...



MKS30 @ 37.5 kV, PLI: 130 MW




MKS30 @ 39 kV, detector saturated



RF power phase shifter under construction





- This year was dedicated to the achievement of CALIFES construction and to deliver its first beams with constant improvements.
- We are reasonably confident in reaching full performances and to provide a beam useful for ACS qualification in the TBTS.

- Beyond CALIFES, CEA IRFU is involved in the CLIC/CTF3 program within the 12 GHz stand alone test station and the development of wakefield monitors for the ACS.

- I am grateful to all teams members from CERN, CEA and the other collaborating institutes for having given to me the opportunity to live such a exciting experience : the starting of a new accelerator.