


CLIC09 WORKSHOP

Status and progress of the module studies

G. Riddone on behalf of the CLIC Module WG, 13.10.2009




- ▶ Introduction and motivation
- ▶ Module types
- ▶ **Systems/components: design status and studies**
- ▶ **Module integration: design status and studies**
- ▶ Conclusions

Dedicated talks on module baseline, test program, integration and overall simulations in the WG5 on Wed 14.10




INTRODUCTION AND MOTIVATION

CLIC overall layout – 3 TeV



A fundamental element of the CLIC concept is two-beam acceleration, where RF power is extracted from a high-current and low-energy beam (drive beam) in order to accelerate the low-current main beam to high energy (main beam).




10 CLIC Feasibility Issues

Two Beam Acceleration:

- Drive beam generation
- Beam Driven RF power generation
- Two Beam Module

CLIC specific



Drive beam
100 A

PETS
-6.5 MV/m, 136 MW,
213 mm


Main beam
~1 A

Accelerating structure
+100 MV/m, 64 MW,
229 mm

Two-beam module




Current activities



- ▶ Definition of overall layout (space reservation, number of components and their exact position and dimension)
- ▶ **Definition of boundary conditions and design constraints to the CLIC technical systems**
- ▶ **Detailed study and mechanical design of the module**, as well as integration and fabrication issues [WG5]
- ▶ Definition of layout of special regions (drive beam turn-around loops)
- ▶ Module integration in the tunnel, including module transport and installation in collaboration with CES WG [WG5]
- ▶ Design and construction of the so called “Test Modules” [WG5]
- ▶ Cost estimate
- ▶ Provide feedback for other areas of the study



Organization



Working group
with link persons for main
technical systems and interfaces



Collaborators

Technical systems

- RF: I. Syratchev, W. Wuensch, R. Zennaro,
- RF instrumentation: F. Peauger, R. Zennaro
- Beam instrumentation: L. Soby
- Vacuum: C. Garion
- Magnet: M. Modena
- Pre-alignment: F. Lackner, H. Mainaud-Durand, T. Touzé
- Stabilization: K. Artoos, A. Jeremie
- Structure supports: N. Gazis, J. Huopana, R. Nousiainen
- Beam feedback: H. Schmickler
- Integration: A. Samoshkin, D. Gudkov;
- Tunnel and Transport: J. Osborne, K. Kershaw

Interface to

Beam physics: D. Schulte
Transfer lines: B. Jeanneret
Radiation issues: S. Mallows

CEA/Saclay

CIEMAT

DUBNA/JINR

UH/VTT

LAPP

NTUA

NCP (Pakistan)

PSI

UPPSALA




**University of
Manchester**

....



MODULE TYPES

Module type 0






8 accelerating structures
8 wakefield monitors

4 PETS
2 DB quadrupoles
2 DB BPM


Total per linac (3 TeV)
8374 standard modules

Other module types




Type 2

Total per linac (3 TeV)
 type 1: 154 type 2: 634
 type 3: 477 type 4: 731
Other modules
 - modules in the damping region (no structures)
 - modules with dedicated instrumentation
 - modules with dedicated vacuum equipment ...



Type 3





- ✓ RF system (Accelerating Structures [AS], PETS, RF distribution)
- ✓ Magnet system
- ✓ Pre-alignment, stabilization, supporting systems
- ✓ Beam instrumentation
- ✓ Cooling, vacuum systems

SYSTEMS/COMPONENTS – DESIGN STATUS AND ISSUES




Accelerating structures

A. Grudiev, D. Gudkov, j. Huopana, A. Samoshkin




- ▶ Engineering design under way. Many systems to be designed & integrated around the “super-structure”
 - ▶ Micro-precision assembly (5 μm)
 - ▶ Wakefield monitor (1 per AS)
 - ▶ Incorporating damping is mechanically complex and requires transverse space.
 - ▶ Cooling circuits (400 W per AS) – internal/external under study
 - ▶ Vacuum system (10^{-8} mbar)
 - ▶ Interconnection to MB Q (stabilization!)
 - ▶ Structure support (alignment)
 - ▶ Connection to RF distribution (flexibility)





PETS


D. Gudkov, J. Huopana, A. Samoshkin, I. Syratchev



Compact coupler with on-off mechanism

Minitank

Cooling



Compact coupler details


Engineering design well advanced

- ▶ 8 octants with “compact” couplers and integrated on-off mechanism
- ▶ Minitank for octants
- ▶ Cooling circuits (size for 0.5% beam loss) – couplers water cooled, bars conduction cooled
- ▶ RF distribution to AS
- ▶ Vacuum system (sizing of mini-tank)
- ▶ Interconnection to BPM (limited space – few tens of mm)
- ▶ Minitank support (fiducialisation)




RF distribution


D. Gudkov, A. Samoshkin, I. Syrathev



Beam inter-axis – 650 mm ONLY



- Study of compact 3-dB RF splitter with choke mode flange, including assembly and alignment features
- Study of waveguide routing
- Study of HP loads at the outlet of the AS with integrated RF diagnostic devices



The **compact 3-dB splitter** is an adapter from a rectangular (H10) to two circular (H11) waveguides with two integrated choke mode flanges (CMF). CMF allows the power transmission without electrical contact between waveguides.

Dynamic range for the accepted performance ($S_{11} < -45$ dB):

- x – shift: ± 0.25 mm
- y – shift: ± 0.5 mm
- z – shift: ± 0.5 mm
- Twist: $< 5^\circ$



Magnets

M. Modena

MAIN BEAM



- ✓ Four different magnetic lengths, namely 0.35, 0.85, 1.35 and 1.85m (weight 400 kg).
- ✓ Beam pipe supported by the magnet. *The beam pipe centre needs to be aligned to the magnetic centre of the quad with an accuracy better than 30 μm .* → design at CERN, prototype under tendering

- ✓ For the beam-based feedback, a 1-cm long magnet in front of each quadrupole (decouple BBF and stabilisation) [**under study**]


DRIVE BEAM

- ✓ The quadrupole active length is 0.15 m.
- ✓ Total number of quadrupoles is about 42000 (on series production, optimisation on going together with Cockcroft institute)

Powering of magnets to be optimized to limit power dissipation




Nominal Gradient: **200 T/m**
Magnet bore \varnothing : **10 mm**



Nominal Gradient: **81.2 -8.12 T/m**
Magnet bore \varnothing : **23 mm**

Pre-alignment

H. Mainaud-Durand and SU team See talks WG5




Mechanical pre-alignment within ± 0.1 mm (1σ) \rightarrow
Active pre-alignment: within ± 10 μ m (3σ)

Concept: straight alignment reference over 20 km
based on overlapping references

- ▶ Accelerating structures and PETS pre-aligned on independent girders [mono-girder alternative also under study]
- ▶ “Snake system/articulation point” adopted for girder pre-alignment \rightarrow “CTF2 concept”, validated in CTF2, with beam.
- ▶ MB quad pre-aligned independently

To be considered in the pre-align. system study:


- ▶ Integration of the pre-alignment systems in the modules \rightarrow transport and installation
- ▶ Fiducialisation (design and tests – stability during time, impact of thermal variations)



CTF2 validation, but:

- ▶ Resizing needed (higher loads)
- ▶ Actuators not on the shelf (alternative study-cam system)
- ▶ Stability with AS requirements
- ▶ Kinematics (14 bearings)

Stabilization



K.Artoos A. Jeremie and SWG See talks plenary+WG5


Stabilization needed for the MB quadrupole (vertical tolerance: $1 \text{ nm} > 1 \text{ Hz}$)

Compatibility stabilization and pre-alignment


Under study

1. CERN option: rigid (active stabilisation + fast nano-positioning with a Hexapod)
2. LAVISTA option: soft support

size of the seismometers!



F. Lackner, K.Artoos




A. Samoshkin

For the integration of the MB quadrupole stabilisation system in the module an inventory of modal behaviour and rigidities of components is needed, as well as an inventory of vibration sources



Girder/structure supports




J. Huopana/HIP – N. Gazis/NTUA


- ▶ RF structures (accelerating structures and PETS) on dedicated supports which are connected to the SiC girder
- ▶ For the girder, SiC material chosen as best compromise for damping to stiffness ratio (2 m long girder seems to be feasible – contacts with several companies under way)
 - ▶ Other material (such as steel) are not abandoned
 - ▶ Different shape configurations are under study
- ▶ Supports shall be compatible
 - ▶ with thermal loads (sizing in parallel with cooling system design)
 - ▶ with pre-alignment design and “fiducialisation”
 - ▶ with stabilisation requirements



Study on the MB & DB Girder



Q (force), M (momentum) reaction on the the girder.



MB[Type0]


Weight estimation for the structures of the CLIC-Module

MAIN BEAM	DRIVE BEAM
MB-magnet Support	DB Magnets
Cradles	Cradles
Integral "V" Support (StSt)	Integral "V" Support (StSt)
Vacuum Manifold (StSt)	Vacuum Manifold (StSt)
Pumps	Pumps
Vacuum Reservoir (StSt)	Vacuum Reservoir (StSt)
Accelerating Structure (Cu)	PETS (Cu)
Loads (StSt)	Mini-Tank (Cu)
Waveguides from CMF to ACS (Cu)	DB Drift Tube (StSt)
Splitter (Cu)	RF Distribution (Cu)
Cooling Blocks (Cu)	Cooling Blocks (Cu)
Girder Weight (SiC)	Girder Weight (SiC)

Type	Total Weight [MB+DB] (kg)
0	1800
1	1600
2	1600
3	
4	


Mechanical analysis done for main and drive beam girders

estimation of the forces and moments imposed on the structures, the girder weight is evaluated.





MB[Type0]

Layout for the forces & the momenta imposed on the Girder.




DB[Type0]

Structure supports



in →

Used cooling scheme



Thermal analysis for different support types

Temperature field for super-str. (unloaded)


Temperature
Type: Temperature
Unit: °C
Time: 1
9/22/2009 4:17 PM

34.375 Max
33.403
32.431
31.456
30.486
29.514
28.542
27.569
26.597
25.625 Min





Directional Deformation 2
Type: Directional Deformation (X Axis)
Unit: µm
Time: 1
9/22/2009 4:16 PM

2.3969 Max
-1.0023
-4.4016
-7.8009
-11.2
-14.599
-17.999
-21.398
-24.797
-28.197 Min




V-support







Vacuum

C. Garion, R. Zennaro See also talks in WG4



Detailed studies under way:


- ▶ Pumping system (MB and DB vacuum coupled via the common manifold and the waveguides)
- ▶ Quadrupole vacuum chamber with NEG films integrated
- ▶ Interconnections (intra-module and inter-module)
 - ▶ Main beam – Non-contacting interconnects acceptable. Short range wakefields essentially equal to an iris. Long range wakefields need damping
 - ▶ Drive beam – contacting interconnect necessary for baseline design due to the high drive beam current.



Solution with a gap and damping material (solution found for RF design)



Cooling



R. Nousiainen HIP/VTT


Detailed study under way:

- The structure must maintain its longitudinal and transverse tolerances during operation with varying beam-loading conditions. Power factors of roughly two in the downstream end of structure.
- RF network cooling - The rf network must maintain its correct electrical length, expansion is $0.2^\circ \text{ phase}/(^\circ\text{C} \cdot \text{meter of group delay})$.

AS ~ 412 W
PETS ~ 110 W


Linac ~ 65000 kW
Module ~ 7.7 kW

Flow / Linac: 3100 m³/h
Flow / Module: ~340 m³/h



$$\Delta T_{\text{linac}} = \Delta T_{\text{module}} = 17.5 \text{ K}$$

Beam pipe deformation:
from unloaded to loaded




High power dissipation: RF structure and magnets are water cooled (RF network to be confirmed)



Beam instrumentation

L. Søby



- ▶ Limited space for BPM integration: 60 to 100 mm
- ▶ 1 BPM per Q, 1 WFM per AS
- ▶ DB: ~ 47000 devices; MB: ~151000 devices
- ▶ BPM rigidly connected to the quadrupole

- ▶ MB BPM
 - ▶ Choke BPM: RF design made, mechanical design to be done (possible collaboration with RHUL)
 - ▶ FNAL Low-Q cavity BPM: wakefield calculation coming in few weeks
- ▶ DB BPM
 - ▶ Design will start next year - collaboration with SLAC



- ▶ WFM: Mechanical design under way – collaboration with CEA-Saclay (accelerating structure with WFM in 2010)

MODULE INTEGRATION: DESIGN STATUS AND STUDIES



System integration


A. Samoshkin DUBNA/JINR



Integration of technical systems is very challenging

- Module gives the boundary conditions and design constraints
- space reservation and conceptual to detailed design for most of the systems
- Module detail design evolving in parallel to the definition of the technical systems
- high number of instruments: ~190 signals per module


Effort on space reduction:
 - longitudinal compactness gives gradient and efficiency.
 - transverse compactness for tunnel integration





Thermo-mechanical simulation of the module


R. Nousiainen UH/VTT See Talk WG5




- ▶ ANSYS model capable to simulate the thermal-mechanical behaviour of the entire module under all operation modes
 - ▶ incrementally starting from RF structures – started now as in parallel to detailed design (feedback to technical systems)

First steps integrated

1. Transient thermal behaviour of the RF-structures coupled with cooling
2. Operation modes' relation to RF-structure movement, thermal / structural behaviour
3. Induced effect from coupling of beams, dilatations & forces
4. Mechanical response of interconnections in thermal cycle, dilatations & forces



Conclusions



- ▶ More than 20000 modules in the two linacs (~140000 accelerating structures) → two beam acceleration is one of the feasibility issues
- ▶ Module design evolves in parallel to the system design
- ▶ Detailed design for several systems (e.g. vacuum, pre-alignment,...) started in 2009 and now well advanced → must be frozen by Q1-2010
- ▶ Several studies are driven by the module (e.g. engineering design of RF structures with all systems around, power dissipation and cooling ,...)
- ▶ Several CERN people and collaborators are involved in the module studies (warm acknowledgement to all of them)
- ▶ Test modules will be built in the lab and in CLEX in the coming years (2010-2013)