



Simulations and Measurements of Long Range Beam-Beam Effects in the LHC

Coronagraph implementation choice of beam

E. Bravin, A. Goldblatt, G. Trad
CERN – BE/BI

Lyon, 30 Nov – 1 Dec 2015



Outline



- The synchrotron radiation monitors of LHC
- Differences between B1 and B2
- Light sources at 450 GeV and 6.5 TeV
- Schedule and constraints

LHC IR4

Beam 2


RF INSERTION

Beam 1




Sources

Observation




The BSRT in short




A telescope that images the synchrotron light emitted by the beam

Real BSRT - Imaging




- Adjustable telescope for two wavelengths (400nm and 250nm)

Real BSRT - Interferometer




- Adjustable telescope for two wavelengths (400nm and 250nm)
- Two slits interferometer

Real BSRT – Shack-Hartmann




- Adjustable telescope for two wavelengths (400nm and 250nm)
- Two slits interferometer
- Shack-Hartmann wave-front sensor (monitor mirror deformations)

Real BSRT - AGM



- Adjustable telescope for two wavelengths (400nm and 250nm)
- Two slits interferometer
- Shack-Hartmann wave-front sensor
- Gated MCP-PMT for abort gap monitoring

Real BSRT - LDM



- Adjustable telescope for two wavelengths (400nm and 250nm)
- Two slits interferometer
- Shack-Hartmann wave-front sensor
- Gated MCP-PMT for abort gap monitoring
- **Avalanche photo diode and/or hybrid PMT for longitudinal density monitor**

BSRT hands on



BSRT hands on



BSRT hands on



B1 vs. B2 – Present HW

B1

- Imaging
- Interferometry
- Shack-Hartmann
- AGM
- LDM

B2

- Imaging
- Calibration line
- AGM
- LDM



The coronagraph

Size matters!

It will take up
most of the
space and
render access
difficult



B1 vs B2 - Layout



B1 vs. B2 – Modification

B1

- Remove Shack-Hartmann
- Redesign coronagraph black box

B2

- Remove calibration line

B1 vs. B2 – Comparison

B1


- No access to interferometer
- No Shack-Hartmann
- Large number of motors
- + External calibration line
- + Can use PC of BSRI?

B2

- No calibration line
- + More space / less constraints

Light emission

- About 3 orders of magnitude between 450 GeV and 6.5 TeV considering full visible range
- At 450 GeV just enough light for pilot bunch single turn measurement
- For 10^5 DR with 10^{11} p @ 450 GeV need to integrate ~500 turns·bunches i.e. 50 ms with single bunch and gating at 11 kHz



Camera

- Ideally camera similar to the one of the BSRI (Andor Zyla 5.5 + Hamamatsu intensifier)
- Will place an order for 5 cameras (BSRT, Halo, SPS) >200 kCHF
- Long lead time for the intensifier (>4months)
- Will take a while with FI as well...
- Need a temporary solution
 - Old Proxivision S/N much worse (like BSRT)
 - Digital non intensified camera

Schedule

- All major work on BSRT has to be terminated by beginning of February.
- To install coronagraph need to extract the optical table, install the optical components then reinstall and align the table.
- Cables already ordered (motors and camera), should be OK for both beams (to be confirmed)

Constraints

- IR4 to RF on 22 February!
- If installing on B1 need extra margin to allow fixing eventual issues on interferometer (need to extract the table again)

Conclusions

- Installation of coronagraph possible on both beams
- Schedule is quite tight, need to decide before start of YETS
- Installation on B2 would be easier and would have less impact on the BSRT
- Can not get the camera for this year, need to decide on a backup solution