



Test Progress at CERN

H. Bajas



TE-MSC-TF



- Feather_0 Magnet
- Variable temperature 20 kA test facility at SM18
- Magnet-Facility connection issues
- Magnet protection strategy
- Data monitoring systems

Feather_0 Magnet


- Magnet characteristics
 - Geometry (90x500mm)
 - HTS
 - easy to be burnt
 - μH inductance
 - Instrumentation
 - Voltage taps, T-sensors array, Fiber optic, Hall probe, Quench Antenna
 - Spot heater
- Operating conditions
 - $T = [4.2 - 80] \text{ K}$
 - $I_{\text{mag}} = [0 - 10000] \text{ A}$



→ SM18 «Diode test station»

Variable temperature 20 kA test facility («Diode» bench)

- Purpose
 - Test of: HTS current leads test, Diodes pulse test,
 - Optical Fiber calibration, others cryo-devices
- 20 kA Power Convertor
 - very low magnet inductance might require fine-tuning of its setting (need check...)
 - Shared with 3 other benches (availability...)
- Cryostat Gas-Liquid Helium supply
 - Helium inlet temperature controlled by He gas preparation in an external tank hosting heaters
 - LHe valve opening and heater power regulation based on thermometry and manometry in the He circuit
 - 4.2 – 100 K stable but need careful set of PID regulation (good experience so far...)
 - Cryostat temperature uniformity not fully insured (need check...)
 - Current leads in the gas (Need shunted-lead test...)




Magnet-Facility connection issues

– Holding plate

- Need of 20 kg magnet support
- Rods, thrilled yoke, etc
- **Need to agree on and machining pieces**

– Instrumentations

- Insert able to host several tens of wires
- **Need check for connection interfacing**
- Numbers of sensors **(68)**





Magnet-Facility connection issues

– Instrumentations

List of instrumentations/ Feather M0 / 27.11.2015

Device	Type	Number	Comments	Number of wires total
Coil spot heaters				
Coil end heater	smaller one	2		8
Heater on straight part	larger one	2		8
Each spot heater needs 4 wires (2 for current and 2 for voltage).				
Temperature sensors				
Non-calibrated	CCS	40		8
Calibrated	CCS	3		12
Calibrated temperature sensors need 4 wires each (2 for current and 2 for voltage).				
Non-Calibrated temperature sensors are in 2 arrays connected in parallel and need 4 wires each array (2 for current and 2 for voltage).				
Voltage taps				
Current leads		4	Two taps on each lead for redundancy	4
Roebel inside the magnet		4	Two taps on each Roebel for redundancy	4
Hall Probe				
	TBD	1		4
Hall probes need four wires (2 current and 2 voltage).				
Quench antenna arrays				
	Array of 5 coils on PCB	4		20
Arrays top to bottom counterwound, this means we have 10 Coils in total in Feather M0. We need 10x2 wires for these coils.				
Acoustic				
		1 to 3	Need 3 holes for optional locations	???
Optical fiber				
		1	(Only one survived from impregnation out of 2)	???
				Total


68

Magnet-Facility connection issues

– Powering


- Joint current-lead to magnet
 - HTS to cylindrical Copper bar with clamping box & Indium sheet
 - The two leads from the magnet should come with the right angle
 - Need to stiffen the two leads (no motion allowed)
 - Need to agree on and machine pieces

- Heat load from the resistive lead to HTS cable
 - May quench the HTS cables by heat propagation
 - Need to optimize the join thermal behavior
 - Fast and accurate protection for the connections
 - (extra-voltage taps)




Magnet protection strategy

- Quench detection
 - Based on voltage signal
 - Linked to safety matrix (triggers)
 - **Need to define threshold and time window**
 - First guess from simulation result



- Energy extraction
 - With 1-2 mΩ from the powering circuit, the time constant of the current decay will be few tens of ms.
 - **No need of dump, current turn off trigger**



Data Acquisition systems

– PXI-DAQ

- Acquires voltage taps signal from “Potaim cards” (40 taps)
- Acquires Temperature (40 sensors)
- Connection to safety matrix (triggers protection)
- **Baseline for facility connections**

– cRio-FBGA

- New data acquisition system
 - Low frequency-long aquisition time
 - 112 channels
- Can produced trigger
 - **need connection to Protection System**
- **Need wiring and cabling work**
- **Just monitoring at the start**





Conclusion

- Feather_0 can be tested in the «Diode Test» Bench
- Use of the «satellite» for Helium inlet liquid/gas temperature control
- Instrumentation connections requires cabling preparation
- Current lead joint requires relevant solution
- Current lead in the gas should be tests
- New DAQ has to be implemented in parallel to classic system
- New DAQ asks for important cabling work.
 - Test in January 2016 before shut-down is challenging
 - Cryo-shut down from the 1st of February.



Test Progress at CERN




Thank you for your attention,

HTS Quench DAQ

NI-CompactRIO

224 total

Received at CERN March 2014



7 modules: 16 differential analog inputs each
 +/- 200 mV till +/- 10 V input range
 7.8 kS/s per channel, 16 bits

1 module: 32 digital outputs
 5 V TTL
 7 μ s response time

Processor:

667 MHz dual-core ARM
 512 MB RAM
 1 GB storage
 NI Linux Real-Time OS

FPGA:

Xilinx Artix-7
 2 M cells

Recording:

Continuous streaming of all channels to external
 3 TB disk for 12 hours tested.

Also available: **high speed module**

4 differential analog inputs, 1 MS/s, 16 bits
 simultaneous sampling

A similar system is used by the EL group to capture voltage transients on the electrical network caused by EDF switching, thunderstorms and internal load changes.